

78300100 PAVEMENT MARKING REMOVAL

SQ FT	LOCATION	OFFSET	REMARKS
461	440+65.6 TO 447+57.0		STAGE I - Double Yellow
105	442+53.0 TO 445+68.3		STAGE II - white edge line
77	442+90.9 TO 445+23.5		STAGE I - white edge line
643	TOTAL		

XX001135 PAVEMENT PATCHING SPECIAL

SQ YD	LOCATION	OFFSET	REMARKS
55	421+06 TO 421+37	RT	STAGE I AFTER PIPE INSTALLATION
55	421+06 TO 421+37	RT	STAGE III - REM OF EXIST STR NO. 1 - RT
110	TOTAL		

Z0005400 BREAKER-RUN CRUSHED STONE

TON	LOCATION	OFFSET	REMARKS
119	421+25		
205	444+08		
324	TOTAL		

X0323988 TEMPORARY SOIL RETENTION SYSTEM

SQ. FT	LOCATION	OFFSET	REMARKS
300	443+89 TO 444+30		STAGE I
359	443+89 TO 444+30		STAGE II
659	TOTAL		

Z0017100 DOWEL BARS

EACH	LOCATION	OFFSET	REMARKS
10	421+06		
10	442+37		
10	443+87		
10	444+32		
40	TOTAL		

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	OFFSET	REMARKS
1	442+84		STAGE I
1	445+33		STAGE I
2	TOTAL		

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	OFFSET	REMARKS
1	442+34		STAGE II
1	445+83		STAGE II
2	TOTAL		

Z0075300 TIE BARS

EACH	LOCATION	OFFSET	REMARKS
32	421+06 TO 421+37		
46	443+87 TO 444+32		
78	TOTAL		