

SCHEDULE OF QUANTITIES

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION
	US BUS 20
340	Sta 72+ 00 - 75+ 40 Stage 2
340	TOTAL

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION
	US BUS 20
230	Sta 73+ 15 - 75+ 45 Stage 3
230	TOTAL

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS

SQ FT	LOCATION
	US BUS 20
15.6	Sta 36 + 83 White - LT Turn Arrow
15.6	Sta 37 + 84 White - LT Turn Arrow
15.6	Sta 38 + 85 White - LT Turn Arrow
46.8	TOTAL

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

FOOT	LOCATION
	US BUS 20
1,150	Sta 37 + 20 - 83 + 00 White Skip Dash - RT
1,150	Sta 37 + 20 - 83 + 00 White Skip Dash - LT
4,580	Sta 37 + 20 - 83 + 00 White EOP - RT
4,580	Sta 37 + 20 - 83 + 00 White EOP - LT
11,460	White Total
4,395	Sta 38 + 87 - 82 + 80 Yellow EOP - LT
4,395	Sta 38 + 87 - 82 + 80 Yellow EOP - RT
8,790	Yellow Total
20,250	TOTAL

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"

FOOT	LOCATION
	US BUS 20
250	Sta 38 + 85 - 41+ 35 White - LT Turn Lane
250	TOTAL

78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"

FOOT	LOCATION
24	WELDON ROAD - LT White - Stop Bar
24	WELDON ROAD - RT White - Stop Bar
48	TOTAL

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION
	US BUS 20
58	Sta 37 + 65 - 83+ 00 One-way Crystal - 80' o.c. - LT
58	Sta 37 + 65 - 83+ 00 One-way Crystal - 80' o.c. - RT
8	Sta 38 + 85 - 41+ 35 One-way Crystal - 40' o.c. - LT Turn Lane
124	TOTAL

78300100 PAVEMENT MARKING REMOVAL

SQ FT	LOCATION
	US BUS 20
58.3	Sta 61 + 00 - 68+ 00 Stage 2 - White EB Centerline Dash
151.7	Sta 67 + 60 - 85+ 80 Stage 2 - White WB Centerline Dash
283.3	Sta 61 + 00 - 69+ 50 Stage 2 - Yellow EB EOP
283.3	Sta 69 + 50 - 78+ 00 Stage 2 - Yellow WB EOP
73.3	Sta 78 + 00 - 80+ 20 Stage 2 - Yellow EB EOP
50.0	Sta 55 + 00 - 61+ 00 Stage 3 - White EB Centerline Dash
103.3	Sta 68 + 00 - 80+ 40 Stage 3 - White EB Centerline Dash
56.7	Sta 67 + 80 - 69+ 50 Stage 3 - Yellow WB EOP
283.3	Sta 69 + 50 - 78+ 00 Stage 3 - Yellow EB EOP
160.0	Sta 78 + 00 - 82+ 80 Stage 3 - Yellow WB EOP
1,503.2	TOTAL

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION
	US BUS 20
58	Sta 37 + 65 - 83 + 00 80' o.c. - LT
58	Sta 37 + 65 - 83 + 00 80' o.c. - RT
8	Sta 38 + 85 - 41+ 35 40' o.c. - LT Turn Lane
124	TOTAL

A2006514 TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED

EACH	LOCATION
	US BUS 20
31	As Directed by the Landscape Architect
31	TOTAL

X0323988 TEMPORARY SOIL RETENTION SYSTEM

SQ FT	LOCATION
	US BUS 20
432.5	Sta 73 + 70 Stage 2
432.5	Sta 73 + 70 Stage 3
865.0	TOTAL

X0712400 TEMPORARY PAVEMENT

SQ YD	LOCATION
	US BUS 20
702	Sta 67 + 40 - 72 + 08 Median Removal
1,195	Sta 72 + 68 - 80 + 60 Median Removal
1,897	TOTAL

X0919000 TEMPORARY PAVEMENT REMOVAL

SQ YD	LOCATION
	US BUS 20
702	Sta 67 + 40 - 72 + 08 Median Removal
1,195	Sta 72 + 68 - 80 + 60 Median Removal
1,897	TOTAL

X6064201 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06

FOOT	LOCATION
	US BUS 20
144	Sta 62 + 56 - 64 + 00 LT
144	Sta 62 + 56 - 64 + 00 RT
729	Sta 64 + 73 - 72 + 02 LT
729	Sta 64 + 73 - 72 + 02 RT
998	Sta 72 + 75 - 82 + 73 LT
998	Sta 72 + 75 - 82 + 73 RT
3,742	TOTAL