SUMMARY OF QUANTITIES

CONTRACT NO. 64D24

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
88	•	••	64	4
STA.		TO STA.		
FED. AID PROJECT	ILLINOIS	FED. ROAD DIST. NO.		

• BRIDGE DECK REPAIRS 2007-1
•• ROCK ISLAND & WHITESIDE

				← ROCK ISLAND →				← WHITESIDE →			
				90% FEDERAL 10% STATE X2 31-2A 286TH ST	100% ROCK ISLAND COUNTY X2 31-2A 286TH ST	90% FEDERAL 10% STATE X2 31-2A 317TH ST	100% ROCK ISLAND COUNTY X2 31-2A 317TH ST	90% FEDERAL 10% STATE X2 31-2A WILMOT RD	100% FENTON TOWNSHIP X2 31-2A WILMOT RD	90% FEDERAL 10% STATE X2 31-2A LYNDON RD	100% WHITESIDE COUNTY X2 31-2A LYNDON RD
	PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	S.N. 081-0126 QUANTITY		S.N. 081-0132 QUANTITY		S.N. 098-0058 QUANTITY		S.N. 098-0066 QUANTITY	
	28100107	STONE RIPRAP, CLASS A4	SQ. YD.	380	96		115		98		71	
	28200200	FILTER FABRIC	SQ YD	380	96		115		98		71	
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	304	53	13	64	16	63	14	69	12
	42001300	PROTECTIVE COAT	SQ. YD.	94				25		35		34
	44004250	PAVED SHOULDER REMOVAL	SQ. YD.	91				25		30		36
	44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ. YD.	2622	632	149	766	178	748	149		
	44001114	HOT-MIX ASPHALT SURFACE REMOVAL (ASBESTOS)	SQ. YD.	951							827	124
	48300400	PORTLAND CEMENT CONCRETE SHOULDERS 9"	SQ. YD.	93				24		35		34
	50102400	CONCRETE REMOVAL	CU. YD.	32.1	6.6		9.1		8.3		8.1	
	50157300	PROTECTIVE SHIELD	SQ. YD.	1101	243		286		273		299	
	50300255	CONCRETE SUPERSTRUCTURE	CU. YD.	35.8	7.0		9.9		9.6		9.3	
	50300300	PROTECTIVE COAT	SQ. YD.	84	16		21		24		23	
	50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	6740	1520		1690		1570		1960	
	50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	34	8		8		8		10	
	50600600	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1	1							
	50600700	CLEANING AND PAINTING STEEL BRIDGE NO. 2	L SUM	1			1					
	50600800	CLEANING AND PAINTING STEEL BRIDGE NO. 3	L SUM	1					1			
	50600900	CLEANING AND PAINTING STEEL BRIDGE NO. 4	L SUM	1							1	
	50606401	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1	1							
	50606402	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 2	L SUM	1			1					
	50606403	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 3	L SUM	1					1			
	50606404	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 4	L SUM	1							1	
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5210	1,040		1,360		1,420		1,390	
	52000110	PREFORMED JOINT STRIP SEAL	FOOT	274	61		72		68		73	
	52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	34	8		8		8		10	
	52100520	ANCHOR BOLTS, 1"	EACH	136	32		32		32		40	
	58100200	WATERPROOFING MEMBRANE SYSTEM	SQ. YD.	3520	622	147	755	175	737	147	816	121
	60260100	INLETS TO BE ADJUSTED	EACH	12				4		4		4
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	2		2		2		2	
	67100100	MOBILIZATION	L SUM	1	0.25		0.25		0.25		0.25	
	70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	8	2		2		2		2	
	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.25		0.25		0.25		0.25	
	70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.25		0.25		0.25		0.25	
	70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.25		0.25		0.25		0.25	
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1420	355		355		355		355	
	70300520	PAVEMENT MARKING TAPE, TYPE III LINE 4"	FOOT	48664	12,136		12,176		12,168		12,184	
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	16,221	4,045		4,059		4,056		4,061	
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	486							486	
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	3366	948		968		964		486	

• DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
BRIDGE REHABILITATION
OVER I-88
ROCK ISLAND AND
WHITESIDE COUNTIES

SUMMARY OF QUANTITIES

SCALE: NTS DRAWN BY EF
DATE 12/09/08 CHECKED BY RS

FILE: S:\Jan 10 12:41:37 2009