

CONTRACT NO. 64D24

# SUMMARY OF QUANTITIES

← ROCK ISLAND → ← WHITESIDE →

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
88	*	**	64	5
STA.		TO STA.		
FED. AID PROJECT ILLINOIS		FED. ROAD DIST. NO.		
* BRIDGE DECK REPAIRS 2007-1				
** ROCK ISLAND & WHITESIDE				

PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	S.N. 081-0126		S.N. 081-0132		S.N. 098-0058		S.N. 098-0066	
				90% FEDERAL 10% STATE X2 31-2A 286TH ST	100% ROCK ISLAND COUNTY X2 31-2A 286TH ST	90% FEDERAL 10% STATE X2 31-2A 317TH ST	100% ROCK ISLAND COUNTY X2 31-2A 317TH ST	90% FEDERAL 10% STATE X2 31-2A WILMOT RD	100% FENTON TOWNSHIP X2 31-2A WILMOT RD	90% FEDERAL 10% STATE X2 31-2A LYNDON RD	100% WHITESIDE COUNTY X2 31-2A LYNDON RD
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	10206	1,584	1,972	1,920	466	1,872	398	1,716	278
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	24332	6,068		6,088		6,084		6,092	
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	1952	488		488		488		488	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	16	4		4		4		4	
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	94	4		4		4		82	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	8,761	2,185		2,192		2,191		2,193	
X0321468	PLUG EXISTING DECK DRAINS	EACH	68	12		8		36		12	
X0321743	SILICONE JOINT SEALER, 1"	FOOT	65				19		18		28
X0323082	DRAINAGE SCUPPERS, DS-33	EACH	16	4		4		4		4	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	819	150		295		198		176	
X5067501	BRIDGE CLEANING AND PAINTING WARRANTY NUMBER 1	L SUM	1	1							
X5067502	BRIDGE CLEANING AND PAINTING WARRANTY NUMBER 2	L SUM	1			1					
X5067503	BRIDGE CLEANING AND PAINTING WARRANTY NUMBER 3	L SUM	1					1			
X5067504	BRIDGE CLEANING AND PAINTING WARRANTY NUMBER 4	L SUM	1								1
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1	0.25		0.25		0.25		0.25	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.25		0.25		0.25		0.25	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	32	3		6		21		2	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	103	9		12		27		55	
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	349	32		128		63		126	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	8	2		2		2		2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	8	2		2		2		2	

\* DENOTES SPECIALTY ITEM

\$FILE\$ Sat Jan 10 12:41:41Z 1999

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 BRIDGE REHABILITATION  
 OVER I-88  
 ROCK ISLAND AND  
 WHITESIDE COUNTIES  
**SUMMARY OF QUANTITIES**  
 SCALE: NTS  
 DATE 10/08/08  
 DRAWN BY EF  
 CHECKED BY RS