

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
88	*	**	64	6
STA.		TO STA.		
FED. AID PROJECT		ILLINOIS	FED. ROAD DIST. NO.	

- BRIDGE DECK REPAIRS 2007-1
- ROCK ISLAND & WHITESIDE

STATION		OFFSET	48300400	42001300	60260100	44004250
FROM	TO		PCC SHOULDER, 9"	PROTECTIVE COAT	INLETS TO BE ADJUSTED	PAVED SHOULDER REMOVAL
			SQ YD	SQ YD	EACH	EACH
317TH ST CH 49						
2129+07.3	2129+22.3	LEFT	6.1	6.1	1	7
2129+23.7	2129+38.4	RIGHT	6	6	1	6
2132+17.9	2132+31.9	LEFT	5.7	5.7	1	6
2132+33.9	2132+48.9	RIGHT	6.1	6.1	1	6
SUBTOTAL 317TH ST CH 49			24	24	4	25
WILMOT RD CH 17						
3012+70.9	3012+92.9	LEFT	9.2	9.2	1	9.1
3012+83.1	3013+06.2	RIGHT	8.4	8.4	1	7.5
3015+74.7	3015+94.7	LEFT	8.4	8.4	1	7.3
3015+87.9	3016+09.9	RIGHT	9.3	9.3	1	6.4
SUBTOTAL WILMOT RD CH 17			35	35	4	30.3
LYNDON RD CH 37						
3528+33.6	3528+44.6	LEFT	8.6	8.6	1	9
3528+33.6	3528+44.6	RIGHT	8.6	8.6	1	9
3530+94.6	3531+05.2	LEFT	8.6	8.6	1	9
3530+94.6	3531+05.2	RIGHT	8.6	8.6	1	9
SUBTOTAL LYNDON RD CH 37			34	34	4	36
TOTALS			93	93	12	91

STATION		OFFSET	78001110	
FROM	TO		PAVEMENT MARKING LINE 4" WHITE EDGE LINE	PAVEMENT MARKING LINE 4" YELLOW CENTERLINE
			FOOT	FOOT
286TH ST				
2007+16.97	2009+63.57	C/L		1972
TOTAL 286TH ST			1,972	
317th ST				
2131+97.9	2132+27.7	LT/RT & C/L	120	120
2129+57.9	2131+97.9	LT/RT & C/L	960	960
2129+29.7	2129+57.9	LT/RT & C/L	113	113
TOTAL 317th ST			2,386	
WILMOT RD				
3015+57.3	3015+82.4	LT/RT & C/L	101	101
3013+23.3	3015+57.3	LT/RT & C/L	936	936
3012+98.9	3013+23.3	LT/RT & C/L	98	98
TOTAL WILMOT RD			2,270	
LYNDON RD				
3530+76.7	3530+94.1	LT/RT & C/L	70	70
3528+62.1	3530+76.7	LT/RT & C/L	859	859
3528+44.9	3528+62.1	LT/RT & C/L	69	69
TOTAL LYNDON RD			1,996	
TOTALS			8,624	

LOCATION	OFFSET	70300100	70300520		70301000	78008210		78008230	78300100
		SHORT TERM PAVEMENT MARKING	YELLOW PAVEMENT MARKING TAPE TYPE III 4"	WHITE PAVEMENT MARKING TAPE TYPE III 4"	WORK ZONE PAVEMENT MARKING REMOVAL	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4" WHITE EDGE LINE	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4" YELLOW EDGE LINE	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6" WHITE LANE SKIP-DASH	PAVEMENT MARKING REMOVAL
		FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	SQ FT
I-88 UNDER 286TH ST CH 25		355	6,068	6,068	4,045	3,034	3,034	488	2,185
I-88 UNDER 317TH ST CH 49		355	6,088	6,088	4,059	3,044	3,044	488	2,192
I-88 UNDER WILMOT RD CH 17		355	6,084	6,084	4,056	3,042	3,042	488	2,191
I-88 UNDER LYNDON RD CH 37		355	6,092	6,092	4,061	3,046	3,046	488	2,193
TOTALS		1,420	48,664	48,664	16,221	24,332	24,332	1,952	8,761

LOCATION	70400100		78200520	Z0030250	70400200		Z0030350
	TEMPORARY CONCRETE BARRIER (WB)	TEMPORARY CONCRETE BARRIER (EB)	BARRIER WALL MARKERS TYPE B	IMPACT ATTENUATOR NON-RD	RELOCATE CONCRETE BARRIER (WB)	RELOCATE CONCRETE BARRIER (EB)	IMPACT ATTENUATOR NON-RD
	FOOT	FOOT	EACH	EACH	FOOT	FOOT	EACH
I-88 UNDER 286TH ST CH 25	0	0	0	0	474	474	4
I-88 UNDER 317TH ST CH 49	0	0	0	0	484	484	4
I-88 UNDER WILMOT RD CH 17	0	0	0	0	482	482	4
I-88 UNDER LYNDON RD CH 37	243	243	78	2	243	243	2
TOTALS	243	243	78	2	1683	1683	14

\$FILE\$ Sat Jan 10 12:55:00 2009

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
BRIDGE REHABILITATION
OVER I-88
ROCK ISLAND AND
WHITESIDE COUNTIES
SCHEDULE OF QUANTITIES

SCALE: NTS
DATE 12/09/08

DRAWN BY EF
CHECKED BY RS