

F.A.P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-681	(1150RS-3 & 1161RS-2)	FORD & LIVINGSTON	12	3
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED. 20% STATE	
				I000 FORD COUNTY	I000 LIVINGSTON COUNTY
				20400800	FURNISHED EXCAVATION
25000200	SEEDING, CLASS 2	ACRE	0.06	0.05	0.01
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	5.5	4.7	0.8
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	5.5	4.7	0.8
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	5.5	4.7	0.8
25100630	EROSION CONTROL BLANKET	SQ YD	287	246	41
28100107	STONE RIP RAP, CLASS A4	SQ YD	86	86	0
28200200	FILTER FABRIC	SQ YD	86	86	0
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	4.3	4.3	0
40600100	BITUMINOUS MATERIALS(PRIME COAT)	GALLON	16539.9	14148.4	2391.5
40600300	AGGREGATE(PRIME COAT)	TON	412.7	352.7	60
40600400	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON	30.4	26	4.4
40600525	LEVELING BINDER (HAND METHOD), N50	TON	50.8	43.5	7.3
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	4282.9	3664.6	618.3
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.85	0.15
40600990	TEMPORARY RAMP	SQ YD	274.7	231.5	43.2
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	8648.7	7394.3	1254.4
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	216.8	183.9	32.9
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	104657.2	89433.1	15224.1
48101200	AGGREGATE SHOULDERS TYPE B	TON	2699	2307	392
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	207	207	0
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	4	4	0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	3.4	0.6
67100100	MOBILIZATION	L SUM	1	0.85	0.15
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.85	0.15
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.85	0.15
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7174	6138	1036
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	73056	61382	11674
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	8969	7673	1296
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1196	1023	173
78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	73056	61382	11674
78001130	PAINT PAVEMENT MARKING-LINE 6"	FOOT	8969	7673	1296
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	450	385	65
78200405	GUARDRAIL MARKERS	EACH	210	194	16
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	42	34	8
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	450	385	65
Z0021700	EXPANSION JOINT REHABILITATION	FOOT	320	254	66

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____

DATE _____

DRAWN BY _____
 CHECKED BY _____

DATE-TIME: 01/14/2014 10:40:10 AM C:\DWG\WORK\1001\corperferd\ans8240\summary.dgn