

CONTRACT #66422

PAVEMENT MARKING							
LOCATION	SIDE	LENGTH	PAINT PVMT MARK LINE 4"		PAINT PVMT MARK LINE 6"	RAISED REF PVMT MARK	RAISED REF PVMT MARK REM
			WHITE FOOT	YELLOW FOOT	YELLOW FOOT		
STA						EACH	EACH
LIVINGSTON							
156+00 W TO 104+18 W		5182	10364		1296	65	65
NO PASS ZONE							
144+50 W TO 137+30 W	EASTBOUND	720		720			
134+30 W TO 128+40 W	WESTBOUND	590		590			
SUBTOTALS			10364	1310	1296	65	65
FORD							
104+18 W TO 4+77 W		9941	19882		2485	125	125
4+60 E TO 212+10 E		20750	41500		5188	260	260
SUBTOTALS			61382		7673	385	385
TOTALS			73056		8969	450	450

TEMPORARY PAVEMENT MARKING							
LOCATION	SIDE	LENGTH	TEMP PAINT PVMT MARK 4"		TEMP PAINT PVMT MARK 6"	SHORT TERM PVMT MARK	WORK ZONE PVMT MARK REM
			WHITE FOOT	YELLOW FOOT	YELLOW FOOT		
STA						FOOT	SQ FT
LIVINGSTON							
156+00 W TO 104+18 W		5182	10364		1296	1036	173
NO PASS ZONE							
144+50 W TO 137+30 W	EASTBOUND	720		720			
134+30 W TO 128+40 W	WESTBOUND	590		590			
SUBTOTAL			10364	1310	1296	1036	173
FORD							
104+18 W TO 4+77 W		9941	19882		2485	1988	331
4+60 E TO 212+10 E		20750	41500		5188	4150	692
SUBTOTAL			61382		7673	6138	1023
TOTALS			73056		8969	7174	1196

GUARDRAIL MARKERS			
LOCATION	SIDE	GUARDRAIL MARK	TERM MARK DIRECT APPLIED
STA		EACH	EACH
LIVINGSTON			
148+65 W TO 150+05 W	SOUTH	4	2
148+40 W TO 149+82 W	NORTH	4	2
124+78 W TO 127+22 W	NORTH	4	2
124+78 W TO 127+22 W	SOUTH	4	2
SUBTOTALS		16	8
FORD			
58+55 W TO 53+25 W	SOUTH	7	2
26+78 W TO 19+78 W	SOUTH	9	2
19+44 W TO 10+87 W	SOUTH	11	2
4+75 E TO 10+57 E	SOUTH	8	1
21+37 E TO 29+03 E	SOUTH	10	2
21+62 E TO 29+40 E	NORTH	10	2
53+55 E TO 53+87 E	SOUTH	4	2
53+87 E TO 62+39 E	NORTH	11	2
58+70 E TO 62+46 E	SOUTH	5	2
62+93 E TO 63+95 E	NORTH	4	2
106+36 E TO 140+01E	SOUTH	42	4
140+01E TO 147+01 E	NORTH	9	4
170+76 E TO 172+57 E	NORTH	4	2
170+76 E TO 175+74 E	SOUTH	7	1
173+23 E TO 176+16 E	NORTH	4	2
176+74 E TO 179+40 E	NORTH	4	2
176+31 E TO 212+10 E	SOUTH	45	2
SUBTOTALS		194	34
TOTAL		210	42

SHOULDER AND DITCH STABILIZATION SCHEDULE										
LOCATION	LENGTH	SHLDR WIDTH	DITCH WIDTH	HMA SHLDR 6"	HMA SURF CSE	LEVEL BIND (MM)	BIT MAT PRIME COAT	STONE RIPRAP CL A4	FILTER FABRIC	
STA	FOOT	FOOT	FOOT	SQ YD	TON	TON	GAL	SQ YD	SQ YD	
FORD COUNTY										
52+55 E TO 52+66 E	11		11					13.4	13.4	
52+66 E TO 53+05 E	39	3	11	13	1.1	0.5	1.0	47.7	47.7	
53+05 E TO 53+25 E	20	3	11	7	0.6	0.3	0.6	24.4	24.4	
53+25 E TO 58+85 E	560	3	11	187	15.7	7.9	15.0			
TOTALS				207	17.4	8.7	16.6	85.5	85.5	

PERMANENT SURVEY MARKERS	
LOCATION	EACH
STA	
FORD	
104+18 W	1
52+70 W	1
53+25 E	1
159+26 E	1
TOTALS	4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. _____
 DATE: _____ HORIZ. _____
 DRAWN BY _____
 CHECKED BY _____

* DATE - TIME *
 C:\p_wor\k\p_wor\carpenter\dms82640\def01 is .dgn