

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAU ROUTE 6757 (US ROUTE 150)			80% FED	CONSTRUCTION TYPE CODE		
SUMMARY OF QUANTITIES			20% STATE	RWY	STR	STR
CODE NO.	ITEM	UNIT	URBAN TOTAL	M 1000	BRM X020-2A	M X081-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	44	44		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	129	129		
20100500	TREE REMOVAL, ACRES	ACRE	0.3	0.3		
20200100	EARTH EXCAVATION	CU YD	2059	2059		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	50	50		
20300100	CHANNEL EXCAVATION	CU YD	4930	4930		
20400800	FURNISHED EXCAVATION	CU YD	783	783		
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	821		583	238
20800150	TRENCH BACKFILL	CU YD	989	989		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3391	3391		
21301048	EXPLORATION TRENCH 48" DEPTH	FOOT	1233	1233		
* 25000210	SEEDING, CLASS 2A	ACRE	0.75	0.75		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	70	70		
* 25000500	PHOSPORUS FERTILIZER NUTRIENT	POUND	70	70		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	70	70		
* 25100115	MULCH, METHOD 2	ACRE	0.75	0.75		
25100630	EROSION CONTROL BLANKET	SQ YD	1017	1017		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	400	400		
28000310	AGGREGATE DITCH CHECKS	EACH	2	2		
28000400	PERIMETER EROSION BARRIER	FOOT	1793	1793		

FAU ROUTE 6757 (US ROUTE 150)			80% FED	CONSTRUCTION TYPE CODE		
SUMMARY OF QUANTITIES			20% STATE	RWY	STR	STR
CODE NO.	ITEM	UNIT	URBAN TOTAL	M 1000	BRM X020-2A	M X081-2A
28000500	INLET AND PIPE PROTECTION	EACH	5	5		
28100109	STONE RIPRAP, CLASS A5	SQ YD	1659	81		1578
28200200	FILTER FABRIC	SQ YD	1717	81		1636
28400100	GABIONS	CU YD	8		8	
28500100	FABRIC FORMED CONCRETE REVETMENT MAT	SQ YD	942		942	
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	628	628		
35100100	AGGREGATE BASE COURSE, TYPE A	TON	536	536		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	13.8	13.8		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	180	180		
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	5.5	5.5		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	517	517		
40603230	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	3266	3266		
40603535	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	391	391		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	482	482		
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	393	393		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	79	79		
44000100	PAVEMENT REMOVAL	SQ YD	5429	5429		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1847	1847		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	577.9	577.9		

* SPECIALTY ITEM

FILE NAME =	USER NAME = brucebm	DESIGNED - ST	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C:\Documents and Settings\kilmanck\Local	Settings\Temporary Internet Files\DLK178\au	DRAWN - ST	REVISED - ---				6757	(105B) BR-2, (105B) BR-3	TAZEWELL	3	133
	PLOT SCALE = 20,000' / IN.	CHECKED - FL	REVISED - ---	SUMMARY OF QUANTITIES US 150 OVER LITTLE FARM CREEK			CONTRACT NO. 68086				
	PLOT DATE = 10/16/2008	DATE - 12/2007	REVISED - ---	SCALE: N/A	SHEET NO. OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			