

EARTHWORK

STATION TO STATION	STAGE 1			STAGE 2			STAGE 3			TOTAL	
	LOCATION	EARTH EXCAVATION	EMBANKMENT	EARTH EXCAVATION ADJ. FOR SHRINKAGE	EARTH EXCAVATION	EMBANKMENT	EARTH EXCAVATION ADJ. FOR SHRINKAGE	EARTH EXCAVATION	EMBANKMENT	EARTH EXCAVATION ADJ. FOR SHRINKAGE	FURNISHED EXCAVATION WASTE (+) SHORTAGE (-)
STATION TO STATION	CU. YD.										
US 150 - S.N. 090-0038 47+35.00 52+05.00	248	89	186	51	94	38.25	8	112	6		-64.75
N EAST LANE 10+50.00 13+46.36				447	25	335.25					+310.25
S EAST LANE							178	8.3	133.5		+125.2
CATHERINE STREET 50+11.81 50+50.00				17	3	12.75					+9.75
US 150 S.N. 090-0040 86+50.00 93+50.00	39	778	29.25	33	277	24.75	0	64	0		-1065
N EAST LN STORM SEWER & INLETS 12+03.06 12+03.06				333	235	249.75					+14.75
S EAST LN STORM SEWER & INLETS 49+06.46 49+43.06	362	254	271.5								+17.5
US 150 S.N. 090-0040 CULVERT EXTENSION 90+50.00 92+40.55	343	388	257.25								-130.75
<b>TOTAL</b>	<b>992</b>	<b>1509</b>	<b>744</b>	<b>881</b>	<b>634</b>	<b>660.75</b>	<b>186</b>	<b>184.3</b>	<b>139.5</b>		<b>-783.05</b>
	<b>STAGE 1 TOTAL</b>		<b>-765</b>	<b>STAGE 2 TOTAL</b>		<b>26.75</b>	<b>STAGE 3 TOTAL</b>		<b>-44.8</b>		<b>-783.05</b>

TOP SOIL FURNISH AND PLACE, 4"

LOCATION	QUANTITY
STATION TO STATION	SQ. YD.
US 150 S.N. 090-0038	
47+35.00 47+65.00	64.86
47+65.00 48+00.00	60.21
48+00.00 48+50.78	101.87
48+50.78 49+00.00	62.88
49+00.00 49+50.00	31.07
49+50.00 49+56.00	4.78
49+56.00 50+00.00	56.32
50+00.00 50+50.00	104.76
50+50.00 51+00.00	89.15
51+00.00 51+50.00	74.72
51+50.00 51+75.00	60.11
51+75.00 52+05.00	75.61
N EAST LANE	
10+50.00 11+00.00	95.79
11+00.00 11+50.00	156.79
11+50.00 12+03.06	176.57
12+03.06 12+47.40	130.07
12+47.40 12+97.79	160.61
12+97.79 13+25.00	73.59
13+25.00 13+37.50	20.63
13+37.50 13+46.38	6.38
CATHERINE STREET	
50+19.00 50+50.00	7.30
50+50.00 50+99.33	17.65
50+99.33 51+25.00	27.64
51+25.00 51+80.00	24.46
US 150 S.N. 090-0040	
87+61.06 87+91.06	132.72
87+91.06 88+00.00	38.87
88+00.00 88+50.00	147.77
88+50.00 89+00.00	217.18
89+00.00 89+49.00	353.79
90+12.00 90+50.00	196.89
90+50.00 91+00.00	151.85
91+00.00 91+50.00	113.33
91+50.00 91+94.00	114.56
91+94.00 92+00.00	16.45
92+00.00 92+24.00	56.71
S EAST LANE	
	166.67
<b>TOTAL</b>	<b>3391</b>

EXPLORATION TRENCH, 48" DEPTH

LOCATION	FOOT
US 150 S.N. 090-0038 47+35.00 52+05.00 LT	470
N EAST LANE 10+50.00 13+50.00 LT	300
US 150 S.N. 090-0040 87+61.06 92+24.00	463
<b>TOTAL</b>	<b>1233</b>

TRENCH BACKFILL

LOCATION	CU. YD.
S.N. 090-0038 49+06.46 TO 49+43.21 RT 49+00.75 TO 49+55.89 LT	324 355
S.N. 090-0040 90+50.00 TO 92+90.29 RT	310
<b>TOTAL</b>	<b>989</b>

CHANNEL EXCAVATION

LOCATION	CU. YD.
US 150 S.N. 090-0038	1410
US 150 S.N. 090-0040	3520
<b>TOTAL</b>	<b>4930</b>