

TREE REMOVAL

STATION & OFFSET	DIAMETER (INCH)	6 TO 15 UNITS DIAMETER	OVER 15 UNITS DIAMETER
US 150 S.N. 090-0038			
49+11.92 105.1' LT	15	15	
49+27.19 83.2' LT	54		54
50+82.35 69.3' LT	10	10	
US 150 S.N. 090-0040			
88+58.82 30.5' LT	7	7	
89+30.00 69.6' LT	17		17
89+40.85 47.0' LT	18		18
89+92.73 41.8' LT	24		24
89+99.00 68.7' LT	12	12	
90+01.01 41.8' LT	16		16
TOTAL		44	129

PAVEMENT REMOVAL

LOCATION	SQ. YD.
US 150 S.N. 090-0038	
47+65.00 51+75.00	603.7
S EAST LANE	225.8
N EAST LANE	385.7
US 150 S.N. 090-0040	
89+16.98 TO 90+44.13	402.1
TEMP. PAVEMENT REMOVAL	
S.N. 090-0038	1998
S.N. 090-0040	1813
TOTAL	5429

GUARDRAIL REMOVAL

LOCATION	FOOT
US 150 S.N. 090-0038	
47+36.46 48+62.24 LT	126.0
49+11.96 49+13.59 RT	24.8
49+84.03 51+09.81 RT	125.7
US 150 S.N. 090-0040	
88+49.50 90+38.87 LT	189.6
88+55.48 91+45.00 RT	289.6
TOTAL	756

PIPE CULVERT REMOVAL

LOCATION	FOOT
US 150 S.N. 090-0038	
49+08.79 49+26.52 RT	48
49+16.50 50+74.44 LT	159
49+18.49 49+94.39 LT	63
US 150 S.N. 090-0040	
91+19.90 92+26.00 RT	107
92+52.70 92+90.29 RT	38
TOTAL	415

BITUMINOUS CONCRETE SHOULDER REMOVAL

LOCATION	SQ. YD.
US 150 S.N. 090-0038	
47+35.00 48+76.66 LT	55.9
47+35.00 48+71.94 RT	117.8
49+33.29 50+94.66 LT	100.8
49+80.35 52+05.00 RT	108.6
51+35.82 52+05.00 LT	45.3
US 150 S.N. 090-0040	
87+61.06 92+24.00 LT	288.3
87+61.06 92+24.00 RT	280.7
TOTAL	998

TREE REMOVAL, ACRE

LOCATION	ACRE
S.N. 090-0040 RT	0.3
TOTAL	0.3

DRIVEWAY PAVEMENT REMOVAL

LOCATION	SQ. YD.
US 150 S.N. 090-0038	
47+53.52 RT	60.6
CATHERINE STREET	
50+99.34 LT	11.6
51+25.00 RT	49.9
51+47.21 LT	11.2
51+68.71 RT	15.9
US 150 S.N. 090-0040	
88+29.64 LT	34.8
90+52.00 LT	304.1
92+73.82 RT	89.8
TOTAL	577.9

PAVEMENT MARKING REMOVAL

LOCATION	SQ. FT.
US 150 S.N. 090-0038	
47+35.00 52+05.00	550
US 150 S.N. 090-0040	
87+61.06 92+24.00	540
TOTAL	1090

REINFORCEMENT BARS, EPOXY COATED

LOCATION	POUND
US 150 S.N. 090-0040	
CULVERT EXTENSION COLLAR	37
TOTAL	37

SLOPE WALL REMOVAL

LOCATION	SQ. YD.
US 150 S.N. 090-0038	
49+16.22 49+91.21 RT	175
TOTAL	175

CONCRETE HEADWALL REMOVAL

LOCATION	EACH
US 150 S.N. 090-0040	
92+46.41 21.72' RT	1
TOTAL	1

SIDEWALK REMOVAL

LOCATION	SQ. FT.
CATHERINE STREET	
50+58.68 50+90.56 LT	103
TOTAL	103

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

LOCATION	EACH
S.N. 090-0038	12
S.N. 090-0040	12
TOTAL	24

METAL END SECTIONS 12"

LOCATION	EACH
US 150 S.N. 090-0040	
NW CORNER	1
SW CORNER	1
TOTAL	2

METAL END SECTIONS 18"

LOCATION	EACH
US 150 S.N. 090-0040	
92+90.29 34.80' RT	1
TOTAL	1