SUMMARY OF QUANTITIES

CODE NO.	ITEM	100% STATE SAFETY-2A KNOX COUNTY UNIT	RURAL	TOTAL
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQYD	632	632
40603335	HOT MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	37.2	37.2
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQYD	632	632
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQYD	47	47
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQFT	1586	1586
58100200	WATERPROOFING MEMBRANE SYSTEM	SQYD	225.3	225.3
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	783	783
67100100	MOBILIZATION	LSUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2500	2500
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQFT	833	833
70400100	TEMPORARY CONCRETE BARRIER	FOOT	637.5	637.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	312.5	312.5
* 78005110	EPOXY PAVEMENT MARKING-LINE 4"	FOOT	1800	1800
78300105	PAVEMENT MARKING REMOVAL	FOOT	1800	1800
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQFT	1605	1605
* X7200201	WIDTH RESTRICTION SIGNING	LSUM	1	1
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	2	2
Z0030250	IMPACT ATTENUATORS, TEMPORARY(NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE(NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2

* SPECIALTY ITEM

SN.048-0075 IL.97
over Spoon River

FILE NAME = SN048-0075 IL.97ovrSpoonRiv.dgn	USER NAME = janesca	DESIGNED - CEJ	REVISED - ___	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES
		DRAWN - CEJ	REVISED - ___		
	PLOT SCALE = 102.0149 ' / IN.	CHECKED - ___	REVISED - ___		
	PLOT DATE = 12/9/2008	DATE - 12/03/2008	REVISED - ___		SCALE: _____ SHEET NO. __ OF ___ SHEETS STA. _____ TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
626	(44-B-1)I	KNOX	13	3
PPC BEAM REPLACEMENT		CONTRACT NO. 68855		
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		