

PAVEMENT MARKINGS													
LOCATION				COMMENTS	LINE COLOR	SHORT TERM	PREFORMED PLASTIC TY B LINE - 100 MM	THERMOPLASTIC		URETHANE			PAVEMENT MARKING REMOVAL
O/S	STA	O/S	STA					LINE 100 MM	LINE 200 MM	LINE 100 MM	LINE 200 MM	LINE 300 MM	
LT	37+440.0	LT	37+504.0	ACCL. LANE EOP LINE	WHITE	2.6							12.8
LT	37+441.0	LT	37+505.0	CHEVRONS	WHITE						64.0		1.8
LT	38+150.0	LT	38+200.0	CHEVRONS	WHITE							6.0	15.0
LT	38+248.0	LT	38+285.0	CHEVRONS	WHITE							15.3	4.6
LT	37+441.0	LT	37+505.0	CL SKIP DASH	WHITE	6.4				16.0			1.6
LT	38+100.0	LT	38+210.8	CL SKIP DASH	WHITE	11.1	27.7						2.8
LT	38+210.8	LT	38+315.1	CL SKIP DASH	WHITE	10.4				26.1			2.6
LT	38+315.1	LT	38+753.0	CL SKIP DASH	WHITE	43.8	109.5						10.9
LT	37+441.0	LT	37+505.0	DL EOP	WHITE	2.6				64.0			6.4
LT	38+140.0	LT	38+208.3	DL EOP	WHITE	2.7		68.3					6.8
LT	38+208.3	LT	38+285.0	DL EOP	WHITE	3.1				76.7			7.7
LT	38+424.6	LT	38+602.0	DL EOP	WHITE	7.1		177.4					17.7
LT	38+348.0	LT	38+424.6	DL EOP SKIP DASH	WHITE	3.1		51.1					5.1
LT	38+125.0	LT	38+285.0	EXIT RAMP LINE	WHITE	6.4				160.0			16.0
LT	38+237.7	LT	38+285.0	EXIT RAMP LINE	WHITE	1.9				47.3			4.7
LT	37+441.0	LT	37+505.0	PL EOP	YELLOW	2.6				64.0			6.4
LT	38+100.0	LT	38+602.0	PL EOP	YELLOW	20.1		502.0					50.2
LT	37+440.0	LT	37+504.0	RAMP LANE EOP LINE	WHITE	2.6				64.0			12.8
RT	37+158.0	RT	37+194.0	AUILLARY LANE LINE	WHITE	1.4				36.0			7.2
RT	37+540.0	RT	37+648.9	CHEVRONS	WHITE						18.5		5.5
RT	36+400.0	RT	37+413.0	CL SKIP DASH	WHITE	101.3	253.3						25.3
RT	37+413.0	RT	37+537.2	CL SKIP DASH	WHITE	12.4				31.0			3.1
RT	37+537.2	RT	38+210.8	CL SKIP DASH	WHITE	67.4	168.4						16.8
RT	38+210.8	RT	38+318.0	CL SKIP DASH	WHITE	10.7				26.8			2.7
RT	38+318.0	RT	38+625.0	CL SKIP DASH	WHITE	30.7	76.8						7.7
RT	36+530.7	RT	36+598.7	DL EOP	WHITE	2.7			68.0				13.6
RT	37+413.0	RT	37+537.2	DL EOP	WHITE	5.0				124.2			24.8
RT	37+537.2	RT	37+658.0	DL EOP	WHITE	4.8				120.8			24.2
RT	37+658.0	RT	37+950.8	DL EOP	WHITE	11.7		292.8					29.3
RT	37+950.8	RT	38+087.0	DL EOP	WHITE	5.4			136.2				27.2
RT	38+241.5	RT	38+318.0	DL EOP	WHITE	3.1				76.5			7.7
RT	38+318.0	RT	38+625.0	DL EOP	WHITE	12.3		307.0					30.7
RT	37+093.0	RT	37+172.0	DL EOP SKIP DASH	WHITE	3.2				79.0			15.8
RT	37+371.0	RT	37+413.0	DL EOP SKIP DASH	WHITE	1.7				28.0			5.6
RT	37+398.4	RT	37+511.0	EXIT LANE EOP LINE	WHITE	4.5				112.6			11.3
RT	37+158.0	RT	37+242.9	EXIT LANE LINE	WHITE	3.4					84.9		17.0
RT	37+513.0	RT	37+528.0	EXIT RAMP EOP LINE	WHITE	0.6				15.0			3.0
RT	37+350.0	RT	37+413.0	PL EOP	YELLOW	2.5		63.0					6.3
RT	37+413.0	RT	37+537.2	PL EOP	YELLOW	5.0				124.2			12.4
RT	37+537.2	RT	38+210.8	PL EOP	YELLOW	26.9		673.6					67.4
RT	38+210.8	RT	38+318.0	PL EOP	YELLOW	4.3				107.2			10.7
RT	38+318.0	RT	38+625.0	PL EOP	YELLOW	12.3		307.0					30.7
RT	36+501.5	RT	36+588.6	RAMP LANE LINE	WHITE	3.5				87.1			17.4
RT	38+039.0	RT	38+087.0	RAMP LANE LINE	WHITE	1.9				48.0			9.6
ACTUAL TOTAL						465.0	635.6	2442.2	447.0	932.4	508.2	89.8	619.0
USE TOTAL						465.0	636.0	2443.0	447.0	933.0	509.0	90.0	619.0

TEMPORARY PAVEMENT MARKING LINE 100 MM					
LOCATION				YELLOW (DL)	WHITE (PL)
O/S	STATION	TO	STATION	METER	METER
STAGE I					
RT	36+948.4	TO	37+248.4	300.0	0.0
RT	37+248.4	TO	37+398.4	150.0	0.0
RT	37+398.4	TO	37+417.6	19.2	38.4
RT	37+417.6	TO	37+511.0	0.0	93.4
RT	37+417.6	TO	38+050.0	0.0	632.4
RT	37+417.6	TO	38+575.0	1157.4	0.0
LT	38+130.4	TO	38+426.8	297.0	0.0
RT	38+287.6	TO	38+575.0	0.0	287.4
LT	38+426.8	TO	38+583.1	156.3	156.3
RT	38+575.0	TO	38+625.0	50.0	50.0
LT	38+583.1	TO	38+602.3	19.2	19.2
LT	38+602.3	TO	38+752.3	150.0	0.0
LT	38+752.3	TO	39+052.3	300.0	0.0
STAGE II					
RT	36+100.0	TO	36+400.0	0.0	300.0
RT	36+400.0	TO	36+550.0	0.0	150.0
RT	36+501.5	TO	36+550.0	48.5	0.0
RT	36+512.2	TO	36+635.0	0.0	122.8
RT	36+635.0	TO	37+060.0	0.0	425.0
RT	37+060.0	TO	37+240.9	0.0	180.9
RT	37+149.3	TO	37+245.2	0.0	95.9
RT	37+149.3	TO	37+425.0	0.0	275.7
RT	37+349.4	TO	37+425.0	75.6	0.0
RT	37+425.0	TO	38+479.4	1054.4	1054.4
LT	37+915.6	TO	38+125.0	209.4	0.0
LT	38+100.0	TO	38+150.0	0.0	50.0
LT	38+100.0	TO	38+582.8	482.8	0.0
LT	38+125.0	TO	38+150.0	0.0	25.0
LT	38+125.0	TO	38+233.6	0.0	108.6
LT	38+233.6	TO	38+582.8	0.0	349.2
RT	38+479.4	TO	38+625.1	145.7	145.7
LT	38+582.8	TO	38+602.2	19.4	19.4
LT	38+602.2	TO	38+752.4	0.0	150.2
LT	38+752.4	TO	39+052.4	0.0	300.0
ACTUAL TOTAL				4634.9	5029.9
USE TOTAL				9665.0	

*NOTE: FOR REFERENCE ONLY; COST INCLUDED IN VARIOUS TRAFFIC CONTROL ITEMS

WORK ZONE PAVEMENT MARKING REMOVAL			
Item	LENGTH	WIDTH	AREA
	METER	METER	SQ M
Temp. Pav't Mkgs	9665.0	0.1	966.5
Short-Term	465.0	0.1	46.5
ACTUAL TOTAL			1013.0
USE TOTAL			1013.0

SCHEDULE OF QUANTITIES
F.A.I. 55
MCLEAN COUNTY