

# SUMMARY OF QUANTITIES

SHEET 2 OF 2

LOCATION OF WORK:

	FAI 55 RURAL MCLEAN COUNTY STA 132+18.00 TO STA 279+42.41 90% FEDERAL 10% STATE	FAI 55 URBAN MCLEAN COUNTY STA 132+18.00 TO STA 279+42.41 90% FEDERAL 10% STATE	FAI 55 RURAL MCLEAN COUNTY STA 279+42.41 TO STA 784+99.19 (BK) STA 100+00.00 (AH) TO STA 461+67.02 90% FEDERAL 10% STATE
--	---	---	--

CONSTRUCTION TYPE CODE:

	SFTY-3J	SFTY-3N	SFTY-3J	SFTY-3N
--	---------	---------	---------	---------

CODE NO	ITEM	UNIT	TOTAL QUANTITY	SFTY-3J	SFTY-3N	SFTY-3J	SFTY-3N
*63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	2.0	0.0	0.0	2.0	0.0
*63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	30.0	1.0	0.0	29.0	0.0
63200310	GUARDRAIL REMOVAL	FOOT	10,462.5	237.5	0.0	10225.0	0.0
63400105	GUARD POSTS	EACH	90.0	0.0	10.0	0.0	80.0
63500105	DELINEATORS	EACH	6.0	0.0	0.0	6.0	0.0
63500120	DELINEATOR REMOVAL	EACH	6.0	0.0	0.0	6.0	0.0
67100100	MOBILIZATION	L SUM	1.0	0.1	0.1	0.4	0.4
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	8.0	4.0	0.0	4.0	0.0
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0	0.1	0.0	0.9	0.0
78200410	GUARDRAIL MARKERS, TYPE A	EACH	187.0	4.0	0.0	183.0	0.0
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	30.0	1.0	0.0	29.0	0.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28.0	0.5	0.5	13.5	13.5
Z0002005	ATTENUATOR BASE	SO YD	914.0	0.0	101.6	0.0	812.4
Z0013300	CONCRETE REMOVAL (SPECIAL)	SO YD	21.0	0.0	0.0	0.0	21.0
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	18.0	0.0	2.0	0.0	16.0
Z0056220	SAND MODULE IMPACT ATTENUATOR TO BE REMOVED	EACH	24.0	0.0	0.0	0.0	24.0

\* SPECIALTY ITEMS

FILE NAME : c:\p\work\p\WIDOT\PIERSONBR\0101466\d5	USER NAME : piersonbr 0745-sht-S00.dgn	DESIGNED - MLB	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.I. RTE. 55	SECTION D5Safety-2	COUNTY McLEAN	TOTAL SHEETS 79	SHEET NO. 6
		DRAWN - BBP	REVISED -		SCALE:	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	CONTRACT NO. 70745
	PLOT SCALE = 40.0000" / IN.	CHECKED -	REVISED -									
	PLOT DATE = 12/16/2008	DATE - 12/03/08	REVISED -									