

FAU 7830 FAU7830
 FAU7830 I000-2A FAS1597 Y031-1F Y030-1E

SUMMARY OF QUANTITIES					FAU 7830		FAS 1597		FAU 7830		FAU 7830		FAS 1597		FAU 7830		
CODE NO.	ITEM	SP. PROV.	UNIT	TOTAL QUANTITIES	HSIP SAFETY 90% FED 10% STATE URBAN	HSIP SAFETY 90% FED 10% STATE RURAL	STP 80% FED 20% STATE URBAN (SEE NOTE)	STP 80% FED 20% STATE RURAL (SEE NOTE)	HSIP SAFETY 90% FED 5% STATE 5% COUNTY SIGNALS URBAN	HSIP SAFETY 90% FED 5% STATE 5% COUNTY LIGHTING URBAN	FAU 7830 Y002-1C 100% STATE URBAN	FAS 1597 I000-2A 100% COUNTY RURAL	FAU 7830 3FTY-1B 50% STATE 50% COUNTY URBAN				
54200457	PIPE CULVERTS, TYPE 1 RCCP 42"		FOOT	124		97		27									
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"		FOOT	188	64	83	18	23									
54200643	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"		FOOT	56		44		12									
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"		EACH	1		1											
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"		EACH	1		1											
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"		EACH	2		1						1					
54215550	METAL END SECTIONS 15"	•	EACH	10	4	5		1									
54215553	METAL END SECTIONS 18"	•	EACH	2		2											
5422C015	PIPE CULVERTS, CLASS C, TYPE 2 15" (TEMPORARY)		FOOT	62		49		13									
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"		FOOT	362	58	184	16	52				52					
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"		FOOT	338		263		75									
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"		FOOT	304		19		5				280					
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"		FOOT	206								206					
60100915	PIPE DRAINS 6"		FOOT	50	20	20	5	5									
60100925	PIPE DRAINS 8"		FOOT	50	20	20	5	5									
60100935	PIPE DRAINS 10"		FOOT	50	20	20	5	5									
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE		EACH	1		1											
60236200	INLETS, TYPE A, TYPE 8 GRATE		EACH	5		2						3					
60240320	INLETS, TYPE B, TYPE 15 FRAME AND LID		EACH	1		1											
60242820	INLETS, SPECIAL, TYPE E	•	EACH	8	1	4						3					
60500060	REMOVING INLETS		EACH	1		1											
60600605	CONCRETE CURB, TYPE B		FOOT	84		66		18									
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	•	FOOT	1838	56	623	15	178				966					
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06		FOOT	173		135		38									
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24		FOOT	266	107	101	30	28									
60623200	CONCRETE MEDIAN, TYPE SM-6.24		SQ FT	54		42		12									
61100605	MISCELLANEOUS CONCRETE		CU YD	0.3	0.1	0.2											

NOTE: HSIP SAFETY FUNDS ARE CAPPED AT \$1.981 MILLION. STP FUNDING BEGINS WHEN HSIP FUNDING IS EXHAUSTED.
 PAY ITEM BREAKOUTS SHOWN HAVE BEEN PRORATED BASED ON THE ENGINEER'S COST ESTIMATE.
 UPON EXCEPTANCE OF THE CONTRACT BID, THESE BREAKOUTS WILL BE ADJUSTED ACCORDINGLY.