

I000-2A

FAU 7830 Y031-1F
FAU 7830 Y030-1E

SUMMARY OF QUANTITIES

CODE NO.	ITEM	SP. PROV.	UNIT	TOTAL QUANTITIES	FAU 7830	FAS 1597	FAU 7830	FAS 1597	FAU 7830	FAS 1597	FAU 7830	FAS 1597	FAU 7830
					HSIP SAFETY 90% FED 10% STATE URBAN	HSIP SAFETY 90% FED 10% STATE RURAL	STP 80% FED 20% STATE URBAN (SEE NOTE)	STP 80% FED 20% STATE RURAL (SEE NOTE)	HSIP SAFETY 90% FED 5% STATE 5% COUNTY SIGNALS URBAN	HSIP SAFETY 90% FED 5% STATE 5% COUNTY LIGHTING URBAN	URBAN 100% STATE	RURAL 100% COUNTY	URBAN 50% STATE 50% COUNTY
80500100	SERVICE INSTALLATION, TYPE A		EACH	1									
81012200	CONDUIT IN TRENCH, 3/4" DIA., PVC		FOOT	69									
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC		FOOT	1142									
81012600	CONDUIT IN TRENCH, 2" DIA., PVC		FOOT	50									
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC		FOOT	10									
81012800	CONDUIT IN TRENCH, 3" DIA., PVC		FOOT	3									
81013000	CONDUIT IN TRENCH, 4" DIA., PVC		FOOT	9									
81021540	CONDUIT, AUGERED 1 1/2" DIA., PVC	*	FOOT	218									
81021570	CONDUIT, AUGERED 3" DIA., PVC	*	FOOT	209									
81021590	CONDUIT, AUGERED 4" DIA., PVC	*	FOOT	76									
81306100	JUNCTION BOX (SPECIAL)	*	EACH	8									
81400100	HANDHOLE		EACH	3									
81400300	DOUBLE HANDHOLE		EACH	1									
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK		FOOT	1283									
82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250 WATT		EACH	4								4	
85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET		EACH	1									
86000100	MASTER CONTROLLER		EACH	1									
86200200	UNINTERRUPTIBLE POWER SUPPLY, STANDARD	*	EACH	1									
86400100	TRANSCEIVER - FIBER OPTIC		EACH	1									
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C		FOOT	488									
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C		FOOT	1281									
87301265	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 9C		FOOT	651									
87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR		FOOT	1833									
87301525	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 6 PAIR		FOOT	668									
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3 C		FOOT	19									
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.		EACH	3									
87702900	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 34 FT.		EACH	1									

NOTE: HSIP SAFETY FUNDS ARE CAPPED AT \$1.981 MILLION. STP FUNDING BEGINS WHEN HSIP FUNDING IS EXHAUSTED. PAY ITEM BREAKOUTS SHOWN HAVE BEEN PRORATED BASED ON THE ENGINEER'S COST ESTIMATE. UPON EXCEPTANCE OF THE CONTRACT BID, THESE BREAKOUTS WILL BE ADJUSTED ACCORDINGLY.

*Specialty Items

FILE NAME : c:\pwwork\pwwid01\LAUGH\INRL\d014681\03\SUMMARY01.dgn	USER NAME : laughlrv1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE : 100.0000 ' / IN.	CHECKED -	REVISED -	*			(I)IN	ADAMS	117	7	
PLOT DATE : Dec-12-2008 02:56:18PM	DATE -	REVISED -	* - FAS 1597 & FAU 7830			CONTRACT NO. 72817				
SCALE: NONE SHEET NO. 5 OF 6 SHEETS STA. TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT										