

**ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES**

LOCATION OF WORK				SAFETY 90% FED 10% STATE	100% STATE	6TH ST. 90% FED 5% STATE 5% QUINCY	4TH ST. 90% FED 10% STATE	100% QUINCY
<i>URBAN</i>								
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
PAY CODE	PAY ITEM	UNIT	TOTAL QUANTITY	A000-1A	Y031-1F	Y031-1F	Y031-1F	Y031-1F
54248515	CONCRETE COLLAR	EACH	2	2				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	163	163				
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	68	68				
60237000	INLETS, TYPE A, TYPE 15 FRAME ^{AND} LID	EACH	4	4				
60242820	INLETS, SPECIAL, TYPE E	EACH	1	1				
60500060	REMOVING INLETS	EACH	6	6				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	635	635				
60609100	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06 (VARIABLE WIDTH GUTTER FLAG)	FOOT	76	76				
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	425	425				
60622400	CONCRETE MEDIAN, TYPE SM-6.06	SQ FT	48	48				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
* 72000100	SIGN PANEL - TYPE 1	SQ FT	32		32			
* 78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	94	94				
* 78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	83	83				
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	976	976				
* 78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	171	171				

** Specialty Items*

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\PNWIDOT\LAUGHLINRL\dms240891	652407-sht-soa.dgn	DRAWN -	REVISED -			745	•	ADAMS	37	4	
PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -				CONTRACT NO. 72A96					
PLOT DATE = Jan-05-2009 09:25:03AM	DATE -	REVISED -				FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT					
					SCALE:	SHEET NO. OF SHEETS		STA.	TO STA.		
• D-6 INTERSECTION IMPROVEMENTS											