

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			80% FEDERAL 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			80% FEDERAL 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		X071-2A			CODE NO	ITEM	UNIT		X071-2A		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	20	20		50500505	STUD SHEAR CONNECTORS	EACH	2304	2304			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	52	52		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	55380	55380			
20200500	EARTH EXCAVATION (WIDENING)	CU YD	105	105		50800515	BAR SPLICERS	EACH	567	567			
20300100	CHANNEL EXCAVATION	CU YD	400	400		51201600	FURNISHING STEEL PILES HP12X53	FOOT	1200	1200			
20400800	FURNISHED EXCAVATION	CU YD	275	275		51202305	DRIVING PILES	FOOT	1200	1200			
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	148	148		51203600	TEST PILE STEEL HP12X53	EACH	4	4			
25000200	SEEDING, CLASS 2	ACRE	0.5	0.5		51204650	PILE SHOES	EACH	24	24			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45	45		51205200	TEMPORARY SHEET PILING	SQ FT	507	507			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45	45		51500100	NAME PLATES	EACH	1	1			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45	45		52100520	ANCHOR BOLTS, 1"	EACH	48	48			
25100115	MULCH, METHOD 2	ACRE	0.5	0.5		59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	84	84			
25100630	EROSION CONTROL BLANKET	SQ YD	200	200		60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	160	160			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	150	150		* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	300	300			
28000400	PERIMETER EROSION BARRIER	FOOT	1110	1110		* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
28100109	STONE RIPRAP, CLASS A5	SQ YD	1056	1056		* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4			
28200200	FILTER FABRIC	SQ YD	1056	1056		63200310	GUARDRAIL REMOVAL	FOOT	470	470			
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	430	430		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.1	0.1		67100100	MOBILIZATION	L SUM	1	1			
40600300	AGGREGATE (PRIME COAT)	TON	1	1		70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD T01326	L SUM	1	1			
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	23	23		70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD T01321 (SPECIAL)	EACH	1	1			
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	231	231		70106600	TEMPORARY BRIDGE TRAFFIC SIGNALS (STATE FURNISHED CONTROLLER)	EACH	1	1			
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	46	46		70106700	TEMPORARY RUMBLE STRIP	EACH	6	6			
44000100	PAVEMENT REMOVAL	SQ YD	220	220		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	124	124			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	270	270		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2652	2652			
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	90	90		70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	737.5	737.5			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	925	925			
50200100	STRUCTURE EXCAVATION	CU YD	231	231		70400100	TEMPORARY CONCRETE BARRIER	FOOT	425	425			
50300225	CONCRETE STRUCTURES	CU YD	149	149		70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	312.5	312.5			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	177.5	177.5		* 72000100	SIGN PANEL - TYPE 1	SQ FT	6	6			
50300260	BRIDGE DECK GROOVING	SQ YD	478	478		* 73000100	WOOD SIGN SUPPORT	FOOT	10	10			
50300280	CONCRETE ENCASEMENT	CU YD	8.4	8.4		* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1990	1990			
50300300	PROTECTIVE COAT	SQ YD	624	624		* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	662	662			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1		* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1	1			

FILE NAME =	USER NAME = owenbj	DESIGNED -	REVISED -
c:\pwork\pwork\owenbj\dms63281\p1n22105a.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.

<i>*SPECIALTY ITEMS</i>				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	5A-BR	CALHOUN	60	3
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 76886	