

GENERAL NOTES

- IT IS THE GENERAL INTENT FOR THIS PROJECT TO REMOVE AND REPLACE ALL WEATHERING STEEL GUARDRAIL INSTALLATIONS. ALL REPLACEMENT GUARDRAIL AND TERMINALS SHALL CONFORM TO SECTIONS 630 AND 631 OF THE STANDARD SPECIFICATIONS
- ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

- | | |
|-------------------------------------------------|------------------------|
| •AMEREN IP | GAS & ELECTRIC |
| •AMEREN UE | ELECTRIC |
| •AT&T ILLINOIS | COMMUNICATIONS |
| •AT&T CORPORATION | COMMUNICATIONS |
| •BUCKEYE PARTNERS, L.P. | PIPELINE |
| •CENTERPOINT ENERGY | PIPELINE |
| •CHARTER COMMUNICATIONS, INC. | CABLE TV |
| •CITY OF COLLINSVILLE | WATER & SANITARY SEWER |
| •CONSOLIDATED COMMUNICATIONS | COMMUNICATIONS |
| •CITY OF EDWARDSVILLE | SANITARY SEWER |
| •EXPLORER PIPELINE COMPANY | PIPELINE |
| •VILLAGE OF GLEN CARBON | WATER & SANITARY SEWER |
| •ILLINOIS AMERICAN WATER COMPANY | WATER |
| •MARATHON PIPE LINE LLC | PIPELINE |
| •PAETEC/MCLEOD USA TELECOMMUNICATIONS, INC. | COMMUNICATIONS |
| •MADISON COUNTY SPECIAL SERVICE AREA #1 | SANITARY SEWER |
| •MITCHELL PUBLIC WATER DISTRICT | WATER |
| •NORTHEAST CENTRAL COUNTY PUBLIC WATER DISTRICT | WATER |
| •PLAINS MARKETING, L.P. | PIPELINE |
| •VILLAGE OF ROXANA | WATER & SANITARY SEWER |
| •SOUTHWESTERN ELECTRIC COOPERATIVE, INC. | ELECTRIC |
| •LEVEL 3 COMMUNICATIONS | COMMUNICATIONS |

MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY *.
NON J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

- PORTIONS OF THESE PLANS WERE DEVELOPED FROM OFFICE RECORDS OR OTHERWISE HISTORICAL DATA. FIELD MEASUREMENTS WERE TAKEN TO VERIFY SOME INFORMATION AND WAS LIMITED. REMOVAL ITEMS AND QUANTITIES WERE BASED ON THIS INFORMATION AND SHOULD BE CONSIDERED AS ESTIMATES. PAYMENT FOR REMOVAL ITEMS WILL BE MADE FOR ITEMS AND LENGTHS ACTUALLY REMOVED.
- TRAFFIC CONTROL AND PROTECTION REQUIRED FOR THIS PROJECT CONTAINS PROVISIONS FOR THE USE OF FLAGGERS. WHEN FLAGGERS ARE NOT PRESENT, THE FLAGGER SIGNS SHALL BE REMOVED OR OTHERWISE COVERED IN A MANNER MEETING THE APPROVAL OF THE ENGINEER.
- THE MESSAGE BOARD INCLUDED IN TRAFFIC CONTROL PROTECTION STANDARD 701400 WHICH IS USED FOR ALL INTERSTATE WORK SHALL BE PLACED 3 MILES FROM LANE CLOSURE, OR AS APPROVED BY THE ENGINEER.
- ALL HOLES REQUIRED FOR THE ATTACHMENT OF TRAFFIC BARRIER TERMINALS TO CONCRETE STRUCTURES SHALL BE CORED. DRILLED HOLES WILL NOT BE PERMITTED. ALL EXISTING HOLES IN CONCRETE STRUCTURES, WHICH ARE NOT REQUIRED FOR THE NEW INSTALLATION, SHALL BE GROUTED IN A MANNER MEETING THE APPROVAL OF THE ENGINEER.
- EXISTING GUARDRAIL AND GUARDRAIL TERMINALS SHALL BE REMOVED FOR THIS PROJECT IN ACCORDANCE WITH GUARDRAIL REMOVAL (SPECIAL). SEE SPECIAL PROVISIONS.
- ROAD CONSTRUCTION SIGNS AND PORTABLE CHANGEABLE MESSAGE SIGNS SHALL BE INSTALLED ON ALL ROADWAYS WITH DIRECT ACCESS ONTO I-255/FAP 310 FROM AND INCLUDING HORSESHOE LAKE ROAD TO IL ROUTE 143 AS DIRECTED BY THE ENGINEER. THE SIGNS SHALL ALSO BE INSTALLED ON ALL ROADWAYS WITH DIRECT ACCESS ONTO I-270 FROM AND INCLUDING ILLINOIS ROUTE 111 TO ILLINOIS ROUTE 157. THE SIGNS SHALL BE INSTALLED PRIOR TO PERFORMING WORK ON THIS PROJECT AND SHALL REMAIN IN PLACE FOR THE DURATION OF THIS CONTRACT UNLESS OTHERWISE DIRECTED BY THE ENGINEER. ALL SIGNS SHALL BE 48 INCHES. COSTS OF THIS WORK WILL NOT BE PAID FOR SEPARATELY AND CONSIDERED AS INCLUDED IN THE OTHER ITEMS OF WORK.
- THE RESIDENT ENGINEER SHALL VERIFY THE EXISTENCE OF HIGHWAY LIGHTING AND/OR ITS UTILITIES WITHIN THE PROJECT LIMITS. IF HIGHWAY LIGHTING AND/OR ITS EXISTS WITHIN THE PROJECT LIMITS, AND IF THESE ITEMS REQUIRE LOCATING, THE CONTRACTOR SHALL BE DIRECTED TO DO SO ACCORDING TO SECTION 803 OF THE STANDARD SPECIFICATIONS. IF LOCATING UNDERGROUND CABLE IS NOT INCLUDED AS PART OF THE PLANS, THIS WORK SHALL BE PAID FOR ACCORDING TO ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS.
- ALL EXISTING AND PROPOSED RIGHT-OF-WAY LINES AND PROPERTY LINES SHOWN ON THE PLAN SHEETS ARE GRAPHICAL REPRESENTATIONS AND SHALL NOT BE USED AS A MEANS TO ESTABLISH OWNERSHIP. IN ALL MATTERS RELATING TO RIGHT-OF-WAY, THE PLAT OF HIGHWAYS SHALL BE THE CONTROLLING DOCUMENT.

COMMITMENTS: NONE

INDEX OF SHEETS

- | | |
|-------|----------------------------------------------------|
| 1 | TITLE SHEET |
| 2 | GENERAL NOTES, INDEX OF SHEETS AND STANDARDS |
| 3 | SUMMARY OF QUANTITIES |
| 4-9 | KEY SHEET SUMMARY |
| 10-11 | SCHEDULE OF QUANTITIES |
| 12-33 | EXISTING AND PROPOSED GUARDRAIL REPLACEMENT SHEETS |
| 34-35 | STORM WATER POLLUTION PREVENTION PLAN |
| 36-37 | DETAILS |

IDOT HIGHWAY STANDARDS

- 000001-05
- 280001-04
- 630001-08
- 631011-05
- 631026-05
- 631031-07
- 631033-03
- 635006-03
- 635011-02
- 701101-02
- 701201-03
- 701301-03
- 701400-03
- 701406-05
- 701411-05
- 701456
- 701901-01

*FAI 255/FAP 310

FILE NAME =	USER NAME = paul	DESIGNED - JLS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES, INDEX OF SHEETS AND STANDARDS	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
S:\Projects\407-0029-SHY-1-255-IGLARDRAIL\1.dgn\CA00	shea\0876C3-sh1-gemnote.dgn	DRAWN - JLS	REVISED -			*	60-(8,9,10,11)J	MADISON	37	2	
	PLOT SCALE = 50.0000' / IN.	CHECKED - BRM	REVISED -			CONTRACT NO. 76C31					
	PLOT DATE = 12/9/2008	DATE - 9-05-08	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.