

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	1000-2A		CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	1000-2A	
20100500	TREE REMOVAL, ACRES	ACRE	0.75	0.75		70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	225	225		70500100	TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	362.5	362.5	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	225	225		* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	5	5	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	225	225		* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3	
20200100	EARTH EXCAVATION	CU YD	14250	14250		X7050167	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	3	3	
20400800	FURNISHED EXCAVATION	CU YD	12650	12650							
25000200	SEEDING, CLASS 2	ACRE	2.5	2.5							
25100115	MULCH, METHOD 2	ACRE	2.5	2.5							
25100630	EROSION CONTROL BLANKET	SQ YD	810	810							
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	250	250							
28000300	TEMPORARY DITCH CHECKS	EACH	1	1							
28000400	PERIMETER EROSION BARRIER	FOOT	1515	1515							
28000500	INLET AND PIPE PROTECTION	EACH	4	4							
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	2250	2250							
40200700	AGGREGATE SURFACE COURSE, TYPE A 8"	SQ YD	470	470							
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	725	725							
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	190	190							
44000100	PAVEMENT REMOVAL	SQ YD	2250	2250							
44004250	PAVED SHOULDER REMOVAL	SQ YD	90	90							
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	55	55							
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	90	90							
50105220	PIPE CULVERT REMOVAL	FOOT	60	60							
54213459	END SECTIONS 24"	EACH	6	6							
54213471	END SECTIONS 36"	EACH	4	4							
5422D024	PIPE CULVERTS, CLASS D, TYPE 2 24" (TEMPORARY)	FOOT	255	255							
5422D036	PIPE CULVERTS, CLASS D, TYPE 2 36" (TEMPORARY)	FOOT	50	50							
542D1081	PIPE CULVERTS, CLASS D, TYPE 2 36"	FOOT	60	60							
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	200	200							
63200310	GUARDRAIL REMOVAL	FOOT	225	225							
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3							
67100100	MOBILIZATION	L SUM	1	1							
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1							

**Specialty Items*

Rev.

FILE NAME =	USER NAME = oawenbj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr:\pw_work\pawenbj\dms51591\p1n02205b.dgn		DRAWN -	REVISED -			817	42IR-1	ST. CLAIR	29	3	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 76C74					
PLOT DATE = 12/19/2008		DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.