

6/30/2008 1:58:55 PM P:\01010001\Chicoppo_CADD\Sheet 103_SumQuant.dgn

FAR. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
• 00-00043-00-BR	FORD	51	3	
FED. ROAD DIST. NO. 3	ILLINOIS	CONTRACT NO. 87198		

HOLMES ST.
PINE ST.
CENTER ST.

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	(1)	(2)	(3)
				X120-5B HOLMES STREET	X120-5B PINE STREET	X120-5B CENTER STREET
20200100	EARTH EXCAVATION	CU YD	502	365	77	60
20700400	POROUS GRANULAR EMBANKMENT (SPECIAL)	CU YD	121	121		
20800150	TRENCH BACKFILL	CU YD	86	13		73
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,873	1,515	63	295
25000300	SEEDING, CLASS 3	ACRE	0.38	0.31	0.01	0.06
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	47	32	5	10
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	47	32	5	10
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	47	32	5	10
25100115	MULCH, METHOD 2	ACRE	0.29	0.13	0.06	0.10
25100630	EROSION CONTROL BLANKET	SQ YD	1,876	1,517	64	295
25200110	SODDING, SALT TOLERANT	SQ YD	1,035	369	319	347
25200200	SUPPLEMENTAL WATERING	UNIT	15	5	5	5
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,440	960	160	320
28000300	TEMPORARY DITCH CHECKS	EACH	3	3		
28000400	PERIMETER EROSION BARRIER	FOOT	2,078	1,316	268	494
28000500	INLET AND PIPE PROTECTION	EACH	4	4		
31102100	SUB-BASE GRANULAR MATERIAL, TYPE C 4"	SQ YD	871	871		
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	801	433	150	218
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	241	241		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	235	221	6	8
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	131	85	19	27
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	117	76	17	24
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	3			3
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	100	100		
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	284	284		
42001300	PROTECTIVE COAT	SQ YD	128	128		
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	104	104		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	33	33		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,658	1,658		
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	221	221		

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	(1)	(2)	(3)
				X120-5B HOLMES STREET	X120-5B PINE STREET	X120-5B CENTER STREET
44000100	PAVEMENT REMOVAL	SQ YD	678		301	377
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	127			127
44000600	SIDEWALK REMOVAL	SQ FT	1,022		375	647
48101000	AGGREGATE SHOULDERS TYPE A, 11"	SQ YD	14	14		
48101100	AGGREGATE SHOULDER TYPE A, 12"	SQ YD	18		18	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2		1	1
50100200	REMOVAL OF EXISTING STRUCTURES	L SUM	1	1		
50157300	PROTECTIVE SHIELD	SQ YD	287		136	151
50200100	STRUCTURE EXCAVATION	CU YD	492	492		
50300225	CONCRETE STRUCTURES	CU YD	335	335		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	537	537		
50300254	RUBBED FINISH	SQ YD	362	362		
50300260	BRIDGE DECK GROOVING	SQ YD	537	537		
50300300	PROTECTIVE COAT	SQ YD	861	861		
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	880	880		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	168,210	168,210		
51100100	SLOPE WALL 4 INCH	SQ YD	587	587		
51201105	FURNISHING METAL PILE SHELLS 14"	FOOT	3,510	3,510		
51202305	DRIVING PILES	FOOT	3,510	3,510		
51203200	TEST PILE METAL SHELLS	EACH	4	4		
51500100	NAME PLATES	EACH	1	1		
52000030	PREFORMED JOINT SEAL 2 1/2"	FOOT	122	122		
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE 1	EACH	11	11		
55039700	STORM SEWERS TO BE CLEANED	FOOT	197	197		
550A0050	STORM SEWER, CLASS A, TYPE 1 12"	FOOT	65			65
550B0050	STORM SEWER, CLASS B, TYPE 1 12"	FOOT	396	396		
56103000	* DUCTILE IRON WATER MAIN 8"	FOOT	20	10		10
56103100	* DUCTILE IRON WATER MAIN 8"	FOOT	225			225
56105500	* INSERTING VALVES 6"	EACH	1			1
56105600	* INSERTING VALVES 8"	EACH	1			1

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES			
HOLMES STREET OVER ILLINOIS CENTRAL RAILROAD CITY OF PAXTON, FORD COUNTY			
DESIGN BY DRAWN BY CHECKED BY	KLA DJR JAH	DRAWING NO. C-3	Job# C-93-016-01 DATE 7/1/08 SCALE H: 1"=10' V: 1"=5'

Edwards and Kelcey	DATE	REVISIONS