

| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|----------------|-------------------|--------------|-----------|
| 6713 | 05-00148-00-PV | TAZEWELL | 74 | 03 |
| STA. 145+50.00 | | TO STA. 156+60.00 | | |
| FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT | | | | |

| SUMMARY OF QUANTITIES | | | | TAZEWELL COUNTY | | |
|-----------------------|---|-------|----------------|-----------------|-----------------|-----------------|
| CODE NO. | PAY ITEM | UNIT | TOTAL QUANTITY | 5000-2A | 8071-2A | 9031-1F |
| | | | | ROADWAY | CAMP ST. BRIDGE | TRAFFIC SIGNALS |
| 20200100 | EARTH EXCAVATION | CU YD | 1899.0 | 1899.0 | | |
| 20800150 | TRENCH BACKFILL | CU YD | 53.0 | 53.0 | | |
| 21001000 | GEOTECHNICAL FABRIC FOR GROUND STABILIZATION | SQ YD | 4253.0 | 4253.0 | | |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 4624.0 | 4624.0 | | |
| 25000210 | SEEDING, CLASS 2A | ACRE | 1.0 | 1.0 | | |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 86.0 | 86.0 | | |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 86.0 | 86.0 | | |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 86.0 | 86.0 | | |
| 25100115 | MULCH, METHOD 2 | ACRE | 1.0 | 1.0 | | |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 285.0 | 285.0 | | |
| 28000400 | PERIMETER EROSION BARRIER | FOOT | 122.0 | 122.0 | | |
| 28000500 | INLET AND PIPE PROTECTION | EACH | 4.0 | 4.0 | | |
| 28000510 | INLET FILTERS | EACH | 4.0 | 4.0 | | |
| 31100300 | SUB-BASE GRANULAR MATERIAL, TYPE A 4" | SQ YD | 77.0 | 77.0 | | |
| 35100100 | AGGREGATE BASE COURSE, TYPE A | TON | 2901.0 | 2901.0 | | |
| 35300410 | PORTLAND CEMENT CONCRETE BASE COURSE 9 1/2" | SQ YD | 1045.0 | 1045.0 | | |
| 40500200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 10.8 | 10.8 | | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 3.0 | 3.0 | | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 206.0 | 206.0 | | |
| 40600990 | TEMPORARY RAMP | SQ YD | 70.0 | 70.0 | | |
| 40603540 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MX D, N70 | TON | 64.0 | 64.0 | | |
| 40701861 | HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH) 9" | SQ YD | 1085.0 | 1085.0 | | |
| 42000411 | PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED) | SQ YD | 2123.0 | 2123.0 | | |
| 42001165 | BRIDGE APPROACH PAVEMENT | SQ YD | 334.0 | 334.0 | | |
| 42001420 | BRIDGE APPROACH PAVEMENT CONNECTOR (PCC) | SQ YD | 670.0 | 670.0 | | |
| 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH | SQ YD | 77.0 | 77.0 | | |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 2935.0 | 2935.0 | | |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 308.0 | 308.0 | | |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 1303.0 | 1303.0 | | |
| 44201747 | CLASS D PATCHES, TYPE IV, 8 INCH | SQ YD | 44.0 | 44.0 | | |
| 50101500 | REMOVAL OF EXISTING SUPERSTRUCTURES | EACH | 1.0 | | 1.0 | |
| 50102400 | CONCRETE REMOVAL | CU YD | 16.3 | | 16.3 | |

| SUMMARY OF QUANTITIES | | | | TAZEWELL COUNTY | | |
|-----------------------|---|-------|----------------|-----------------|-----------------|-----------------|
| CODE NO. | PAY ITEM | UNIT | TOTAL QUANTITY | 5000-2A | 8071-2A | 9031-1F |
| | | | | ROADWAY | CAMP ST. BRIDGE | TRAFFIC SIGNALS |
| 50104720 | REMOVAL OF EXISTING CONCRETE DECK | EACH | 1.0 | | 1.0 | |
| 50200100 | STRUCTURE EXCAVATION | CU YD | 43.0 | | 43.0 | |
| 50300100 | FLOOR DRAINS | EACH | 6.0 | | 6.0 | |
| 50300225 | CONCRETE STRUCTURES | CU YD | 25.2 | | 25.2 | |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 149.3 | | 149.3 | |
| 50300260 | BRIDGE DECK GROOVING | SQ YD | 548.0 | | 548.0 | |
| 50300300 | PROTECTIVE COAT | SQ YD | 636.0 | | 636.0 | |
| 50500105 | FURNISHING AND ERECTING STRUCTURAL STEEL | L SUM | 1.0 | | 1.0 | |
| 50500505 | STUD SHEAR CONNECTORS | EACH | 1869.0 | | 1869.0 | |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 40807.0 | 27.0 | 40580.0 | |
| 50800515 | BAR SPLICERS | EACH | 519.0 | | 519.0 | |
| 51500100 | NAME PLATES | EACH | 1.0 | | 1.0 | |
| 52000020 | PREFORMED JOINT SEAL 1 3/4" | FOOT | 79.6 | | 79.6 | |
| 52000050 | PREFORMED JOINT SEAL 4" | FOOT | 76.1 | | 76.1 | |
| 52100010 | ELASTOMERIC BEARING ASSEMBLY, TYPE I | EACH | 5.0 | | 5.0 | |
| 54248510 | CONCRETE COLLAR | CU YD | 1.0 | 1.0 | | |
| 55100500 | STORM SEWER REMOVAL 12" | FOOT | 64.0 | 64.0 | | |
| 55100700 | STORM SEWER REMOVAL 15" | FOOT | 220.0 | 220.0 | | |
| 55101200 | STORM SEWER REMOVAL 24" | FOOT | 297.0 | 297.0 | | |
| 58700300 | CONCRETE SEALER | SQ FT | 263.0 | | 263.0 | |
| 59000200 | EPOXY CRACK INJECTION | FOOT | 103.0 | | 103.0 | |
| 60221000 | MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID | EACH | 1.0 | 1.0 | | |
| 60221700 | MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE | EACH | 2.0 | 2.0 | | |
| 60236200 | INLETS, TYPE A, TYPE 8 GRATE | EACH | 1.0 | 1.0 | | |
| 60241900 | INLETS, TYPE G-1, SPECIAL | EACH | 2.0 | 2.0 | | |
| 60500040 | REMOVING MANHOLES | EACH | 3.0 | 3.0 | | |
| 60500060 | REMOVING INLETS | EACH | 3.0 | 3.0 | | |
| 60602200 | CONCRETE GUTTER | FOOT | 52.0 | 52.0 | | |
| 60605000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 | FOOT | 1348.0 | 1348.0 | | |
| 60618300 | CONCRETE MEDIAN SURFACE, 4 INCH | SQ FT | 223.0 | 223.0 | | |
| 63000000 | STEEL PLATE BEAM GUARD RAIL, TYPE A | FOOT | 100.0 | 100.0 | | |
| 63100085 | TRAFFIC BARRIER TERMINAL, TYPE 6 | EACH | 2.0 | 2.0 | | |

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
CAMP STREET CONNECTOR
SUMMARY OF QUANTITIES

SCALE: VERT. DATE 12/22/2008
 HORIZ. DATE 12/22/2008

DRAWN BY JLT
 CHECKED BY CSA