

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY		STRUCTURES	
				ANDREWS DRIVE U. S. ROUTE 40 (FAU 9832) WOLF INDUSTRIAL DRIVE 99-00036-00-BR	J000-2A	ANDREWS DRIVE OVER U. S. ROUTE 40 (S. N. 003-6000) 99-000-36-00-BR	X531-2A
20200100	EARTH EXCAVATION	CU YD	4760	4760			
20400100	BORROW EXCAVATION	CU YD	125922	125922			
20800150	TRENCH BACKFILL	CU YD	50.5	50.5			
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	3729	3729			
25000200	SEEDING, CLASS 2	ACRE	13.00	13.00			
25000350	SEEDING, CLASS 7	ACRE	24.00	24.00			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1170	1170			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1170	1170			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1170	1170			
25000700	AGRICULTURAL GROUND LIMESTONE	TON	26.0	26.0			
25100115	MULCH, METHOD 2	ACRE	12	12			
25100630	EROSION CONTROL BLANKET	SQ YD	4424	4424			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2400	2400			
28000300	TEMPORARY DITCH CHECKS	EACH	65	65			
28000400	PERIMETER EROSION BARRIER	FOOT	2350	2350			
28000500	INLET AND PIPE PROTECTION	EACH	8	8			
28100205	STONE RIPRAP, CLASS A3	TON	132			132	
28100207	STONE RIPRAP, CLASS A4	TON	71	71			
28200200	FILTER FABRIC	SQ YD	370	106		264	
30200550	PROCESSING MODIFIED SOIL 10"	SQ YD	16367	16367			
30201500	LIME	TON	385.6	385.6			
31000300	PROCESSING LIME STABILIZED SOIL MIXTURE 8"	SQ YD	2119	2119			
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	9410	9410			
31102100	SUB-BASE GRANULAR MATERIAL, TYPE C 4"	SQ YD	3521	3521			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	83	83			
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4451	4451			
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	GALLON	848	848			
40300500	COVER COAT AGGREGATE	TON	16	16			
40300600	SEAL COAT AGGREGATE	TON	16	16			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	115	115			

* SPECIALTY ITEMS

USER NAME = Pcp00836	DESIGNED - MH	REVISED -
PLOT SCALE = 1.0000' / 1in.	DRAWN - DJP	REVISED -
PLOT DATE = 12/29/2009	CHECKED - MH	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: 50 SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	99-00036-00-BR	BOND	99	3
CONTRACT NO. 97366			ILLINOIS FED. AID PROJECT	