

STRIPING SCHEDULE

LOCATION	TYPE	POLYUREA PAVEMENT MARKINGS					RAISED REFL. PVT. MRKR.
		4" YELLOW (FOOT)	4" WHITE (FOOT)	6" WHITE (FOOT)	12" WHITE (FOOT)	LETTERS & SYMBOLS (SQ FT)	TWO-WAY AMBER (EACH)
GLEN CROSSING ROAD - PHASE 2							
STA. 36+81.24 TO STA. 75+50.00							14
	EDGE LINE		7297				
	SKIP DASH 10'-30'	684			102		
	STOP BAR						
	CROSSWALKS			534			
	DOUBLE CENTERLINE	2335					
	LANE LINE		34				
	ARROWS				31		
TOTAL		3019	7331	534	102	31	14

TRENCH BACKFILL SCHEDULE

LOCATION	TRENCH BACKFILL (CU YD)
GLEN CROSSING ROAD - PHASE 2	
STORM SEWER SCHEDULE	908
STORM SEWER REMOVAL SCHEDULE	0
CULVERT SCHEDULE	1
CULVERT REMOVAL SCHEDULE	75
TOTAL	984

RIPRAP SCHEDULE

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)			DEPTH "X" (FOOT)	STONE DUMPED RIPRAP CLASS A4 (SQ YD)	FILTER FABRIC FOR USE WITH RIPRAP (SQ YD)	AGGREGATE BEDDING (TON)
		"A"	"B"	"C"				
GLEN CROSSING ROAD - PHASE 2								
STA. 42+66.31 - 57.93' LT TO STA. 42+78.08 - 34.30' LT								
	25	2	2	2	0.7	16.7	16.7	6
STA. 48+41.10 - 56.63' LT TO STA. 48+60.04 - 46.80' LT								
	17.7	5	2	5	1.5	23.5	23.5	8
STA. 58+64.45 - 35.35' LT TO STA. 58+70.45 - 58.33' LT								
	23	2	2	2	0.5	15.3	15.3	5
STA. 74+34.48 - 30.29' LT TO STA. 74+46.15 - 53.33' LT								
	23	5	2	5	1.6	30.7	30.7	11
TOTAL						86	86	30

PERIMETER EROSION BARRIER SCHEDULE

LOCATION	PERIMETER EROSION BARRIER (FOOT)
GLEN CROSSING ROAD - PHASE 2	
STA. 42+25.00 - 24.47' LT TO STA. 43+50.00 - 26.77' LT	125.5
STA. 48+25.00 - 33.23' LT TO STA. 49+50.00 - 22.81' LT	127.4
STA. 48+25.00 - 30.78' RT TO STA. 48+84.50 - 32.40' RT	61.9
STA. 57+25.00 - 26.46' RT TO STA. 59+25.00 - 25.52' RT	201.0
STA. 58+45.00 - 40.13' LT TO STA. 59+00.00 - 27.01' LT	57.4
TOTAL	573

NOTE: AGGREGATE BEDDING QUANTITY PROVIDED FOR INFORMATION ONLY
 *PLEASE REFER TO RIPRAP DETAIL ON SHEET 55 FOR APPLICATION OF DIMENSIONS.


EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE(+) OR SHORTAGE(-) (CU YD)
ROADS AND DITCHES				
GLEN CROSSING ROAD - PHASE 2	4786	3590	3285	(+) 305
TOTAL	4786	3590	3285	(+) 305

NOTE: BASED ON 25% SHRINKAGE

TOPSOIL SCHEDULE

LOCATION	TOPSOIL 4" (SQ YD)
GLEN CROSSING ROAD - PHASE 2	
STA. 36+81.24 TO STA. 75+50.00	7744
TOTAL	7744

 Juneau Associates, Inc. P.C. CONSULTING ENGINEERS AND LAND SURVEYORS <small>2100 State Street, P.O. Box 1325 Rockville, IL 61154-0132 Phone: (618) 359-0500 Fax: (618) 359-0501</small>		QUANTITY SCHEDULES F.A.U. ROUTE 8899 GLEN CROSSING ROAD PHASE 2 GLEN CARBON, ILLINOIS SECTION No. 07-00026-02-RP									
REVISIONS <table border="1"> <thead> <tr> <th>NO.</th> <th>DATE</th> <th>BY</th> <th>REMARKS</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>		NO.	DATE	BY	REMARKS					SCALE: N.T.S. DSN. BY: BFK DATE: 2/15/08 DWN. BY: JJB DATE: 2/15/08 CHK'D: BFK DATE: 2/15/08 DWG. NO. E070614B DGN. NAME: comsch OF 81 SMTS	
NO.	DATE	BY	REMARKS								

DATE _____ BY _____
 SURVEYED _____
 PLOTTED _____
 NOTE BOOK TEMPLATE _____
 AREAS CHECKED _____
 NO. _____

DATE _____ BY _____
 ORIGINAL SURVEYED _____
 PLOTTED _____
 NOTE BOOK TEMPLATE _____
 AREAS CHECKED _____
 NO. _____