

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331		JACKSON	23	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

• (12-3)RS-2,(4-5)RS-3

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN	
				FAP 331 (IL 13) 80% FED / 20% STATE JACKSON COUNTY	FAP 331 (IL 13) PARKING LANE 100% CARBONDALE JACKSON COUNTY
				1000 QUANTITY	1000 QUANTITY
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6,582	6449	133
40600300	AGGREGATE (PRIME COAT)	TON	108	106	2
40600855	POLYMERIZED LEVELING BINDER (MACHINE METHOD),N105	TON	1,536	1474	62
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600990	TEMPORARY RAMP	SQ YD	227	227	
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIXTURE "E", N105	TON	3,072	2948	124
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	47	47	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	36,939	35464	1475
44200152	PAVEMENT PATCHING, TYPE I, 13 INCH	SQ YD	25	25	
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	515	515	
44200162	PAVEMENT PATCHING, TYPE IV, 13 INCH	SQ YD	76	76	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2	
67100100	MOBILIZATION	L SUM	1	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2	
70300100	SHORT- TERM PAVEMENT MARKING	FOOT	2,091	2091	
70300210	TEMPORARY PAVEMENT MARKING- LETTERS ^{AND} SYMBOLS	SQ FT	409.4	409.4	
70300220	TEMPORARY PAVEMENT MARKING- LINE 4"	FOOT	5,397.0	5,264.0	133
70300240	TEMPORARY PAVEMENT MARKING- LINE 6"	FOOT	1,197.0	1,197.0	
70300260	TEMPORARY PAVEMENT MARKING- LINE 12"	FOOT	220.0	220.0	
70300280	TEMPORARY PAVEMENT MARKING- LINE 24"	FOOT	359.0	359.0	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,471.0	2,427.0	44
* 78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS ^{AND} SYMBOLS	SQ FT	409.4	409.4	
* 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	5,397.0	5,264.0	133
* 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	1,197.0	1,197.0	
* 78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"	FOOT	220.0	220.0	
* 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	359.0	359.0	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	232.0	232.0	
* 88600100	DETECTOR LOOP, TYPE I	FOOT	620	620	

*Specialty Items

PLOT DATE = 12/1/2008
 FILE NAME = c:\pwworking\autodesk\AutoCAD 2008\AutoCAD 2008\p10.dwg
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = mcorbett