0

0

0

FOR INDEX OF SHEETS, SEE SHEET NO. 2

PROJECT LOCATED IN CITY OF CHICAGO HEIGHTS

03-06-2020 LETTING ITEM 014

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

PROPOSED HIGHWAY PLANS

FAU ROUTE 2860: CHICAGO ROAD OVER THORN CREEK TRIBUTARY (0.3 MILES N OF IL RTE 1 CUTOFF) SN 016-2305 **SECTION 2018-055-CR** PROJECT STP-5MZC(407) **CULVERT REPLACEMENT COOK COUNTY**

C-91-279-18



BLOOM TOWNSHIP

LOCATION MAP NOT TO SCALE

GROSS LENGTH = NET LENGTH = 1168 FT = 0.221 MILE

COUNTY SHEETS NO. 2018-055-CR RUNOS CONTRACT NO. 72G92

* 67 + 2 = 69 TOTAL SHEETS D-91-354-18



STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION SUBMITTED DECEMBER 10 20 1

> PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

TRAFFIC DATA

2014 ADT = 6.100

POSTED SPEED = 35 MPH

DESIGN CLASSIFICATION **MAJOR COLLECTOR**

HBM ENGINEERING CROUP, LLC ROBERT T. BORO. P.E. *062-043749

DATE: 12/05/2019 SIGNATURE AND SEAL AFBLY TO DRAWINGS:

EXPIRATION DATE: 11-30-2021

Mountal A. Bu DATE: 12/05/2019

HBM ENGINEERING GROUP, LLC MOUSSA A. ISSA, PH.D. P.E., S.E. *081-005738

SIGNATURE AND SEAL 30938 TO DRAWINGS: 24-33

EXPIRATION DATE: 11-30-2020

ACCURATE GROUP, INC. LISA REBECCA CHRZASC, P.E. *062-067628

DATE: 12/05/2019

SIGNATURE AND SEAL 9J20,7 6'0 9)RAWIN45it B 8-18. 20-23 AND 39-52 EXPIRATION DATE: 11-30-2021 14-38

ACCURATE GROUP, INC. SNEHA PRIYANG SHAH, S.E. *081-007062

DATE: 12/05/2019

EXPIRATION DATE: 11-30-2020

IMPROVEMENT ENDS -STA. 159+00

IMPROVEMENT BEGINS -

STA: 147+31:78

CULVERT REPLACEMENT -SN 016-1341 (EXISTING) SN 016-2305 (PROPOSED)

FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES, REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES, IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION 1-800-892-0123 OR 811

PROJECT MANAGER FAWAD AQUEEL, PE, PTOE (847) 705-4247 PROJECT ENGINEER PRAVEEN KAINI, PE (847) 705-4237

CONTRACT NO. 62G92

INDEX OF SHEETS

- COVER SHEET INDEX OF SHEETS AND HIGHWAY STANDARDS GENERAL NOTES SUMMARY OF QUANTITIES 4-8 9 TYPICAL SECTIONS 10-11 SCHEDULE OF QUANTITIES ALIGNMENT, TIES AND BENCHMARKS 12 * 13-14 PROPOSED PLAN AND PROFILE 15-16 DETOUR PLANS 17-20 EROSION CONTROL PLANS 21-25 WATER MAIN AND SANITARY SEWER PLANS 26-27 DRAINAGE AND UTILITY PLANS 28 ADA SIDEWALK RAMP DETAILS 29 PAVEMENT MARKING AND LANDSCAPING PLAN STRUCTURAL PLANS 30-44 45-58 CROSS SECTIONS 59 DRIVEWAY DETAILS DISTANCE BETWEEN ROW AND FACE OF CURB < 15"(4.5 M) (BD-02) 60 STORM SEWER CONNECTION TO EXISTING SEWER (BD-07) 61 TRAFFIC CONTROL & PROTECTION FOR SIDEROADS, INTERSECTIONS & DRIVEWAYS (TC-10) 62 63 TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW PLOW RESISTANT) (TC-11) TYPICAL PAVEMENT MARKINGS (TC-13) 64 65 DETOUR SIGNING FOR CLOSING STATE HIGHWAYS (TC-21) 66 ARTERIAL ROAD INFO SIGN (TC-22) DRIVEWAY ENTRANCE SIGNING (TC-26)
- * INCLUDES SHEETS 14A AND 14B

LIST OF HIGHWAY STANDARDS

STANDARD NO. DESCRIPTION

000001-07	STANDARD SYMBOLS ABBREVIATIONS AND PATTERNS
280001-07	TEMPORARY EROSION CONTROL SYSTEMS
424001-11	PERPENDICULAR CURB RAMPS FOR SIDEWALKS
601001-05	PIPE UNDERDRAINS
602001-02	CATCH BASIN, TYPE A
602301-04	INLET, TYPE A
602701-02	MANHOLE STEPS
604001-05	FRAME AND LIDS, TYPE 1
604006-05	FRAME AND GRATE, TYPE 3
606001-07	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
602416-08	PRECAST MANHOLE TYPE A 8' DIAMETER
602701-02	MANHOLE STEPS
630001-12	STEEL PLATE BEAM GUARDRAIL
630101-10	STRONG POST GUARDRAIL ATTACHED TO CULVERT
701801-06	SIDEWALK, CORNER OR CROSSWALK CLOSURE
701901-08	TRAFFIC CONTROL DEVICES
701006-05	OFF-ROAD OPERATIONS, 2L, 2W, 15' (4.5 M) TO 24" (600 MM) FROM PAVEMENT EDGE
701011-04	OFF-ROAD MOVING OPERATIONS, 2L, 2W, DAY ONLY
701101-05	OFF-ROAD OPERATIONS, MULTILANE, 15' (4.5 M) TO 24" (600 MM) FROM PAVEMENT EDGE
701301-04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701311-03	LANE CLOSURE, 2L, 2W, MOVING OPERATIONS - DAY ONLY
720001-01	SIGN PANEL MOUNTING DETAILS
720006-04	SIGN PANEL ERECTION DETAILS
720011-01	METAL POSTS FOR SIGNS, MARKERS AND DELINEATORS
725001-01	OBJECT AND TERMINAL MARKERS
728001-01	TELESCOPING STEEL SIGN SUPPORT
729001-01	APPLICATIONS OF TYPES A AND B METAL POSTS (FOR SIGNS & MARKERS)
780001-05	TYPICAL PAVEMENT MARKINGS
781001-04	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS
782006-01	GUARDRAIL AND BARRIER WALL REFLECTOR MOUNTING DETAILS

COMMITMENTS

NONE



_					
	USER NAME = ken.drabant	DESIGNED	-	KJD	REVISED -
		DRAWN	-	KJD	REVISED -
ĺ	PLOT SCALE = 40.00 ' / in.	CHECKED	-	RTB	REVISED -
	PLOT DATE = 1/24/2020	DATE	-	12/12/2019	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCALE: 40.00 ' / in.

IN	DEX OF SH	IEETS AI	ND HIGI	HWAY S	TANDARDS	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CHI	CHICAGO ROAD OVER THORN CREEK TRIBUTARY				2860	2018-055-CR	соок	67	2	
UIII							CONTRACT	NO. 62	2G92	
' / in.	SHEET 1	OF 1	SHEETS	STA	TO STA.		LILINOIS LEED A	ID DROIECT		

GENERAL NOTES

- 1. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, AND THE CITY OF CHICAGO HEIGHTS.
- 2. THE REMOVAL OF GUARDRAIL TERMINAL SECTIONS SHALL BE INCLUDED IN THE UNIT PRICE PER FOOT FOR "GUARDRAIL REMOVAL."
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE NOTIFICATION OF ALL EMERGENCY SERVICES, SCHOOL DISTRICTS, I.D.O.T.'S COMMUNICATIONS CENTER, SPRINGFIELD TRUCK PERMIT SECTION AND OTHER AGENCIES AFFECTED BY THE CLOSURE. THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR POSTING SIGNS THAT WILL INDICATE THE DATES THE CLOSURE WILL BE IN PLACE.
- 5. CONSTRUCTION SHALL COORDINATE AND KEEP THE BLOOM TOWNSHIP HIGH SCHOOL INFORMED OF THE PROPOSED DETOUR PLANS AND SCHEDULE. THE DETOUR FOR THE IMPROVEMENT AND PROJECT SCHEDULE SHOULD BE COORDINATED SO THAT WORK OCCURS DURING THE SUMMER RECESS TO MINIMIZE IMPACTS TO THE SCHOOL BUSING.
- 6. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0213 OR 811 FOR FIELD LOCATIONS OR BURIED ELECTRIC, TELEPHONE, AND GAS UTILITIES. 48 HOUR NOTIFICATION IS REQUIRED.
- 7. THE EXACT LOCATION OF ALL UTILITIES SHALL BE FIELD VERIFIED BY THE CONTRACTOR BEFORE ORDERING ANY MATERIALS AND STARTING ANY WORK. FOR LOCATIONS OF UTILITIES, LOCALLY OWNED EQUIPMENT, LEASED ENFORCEMENT CAMERA SYSTEM FACILITIES AND IDOT UNDERGROUND FACILITIES, CONTACT THE LOCAL COUNTIES, MUNICIPALITIES AND IDOT FOR LOCATES.
- 8. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE BID PRICE FOR THE WORK.
- 9. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT
- 10. SAW CUTTING PRIOR TO ANY REMOVAL ITEMS NOTED ON THE PLANS OR DIRECTED BY THE ENGINEER SHALL BE CONSIDERED INCLUDED IN THE COST OF THE ITEMS BEING REMOVED.
- 11. THE CONTRACTOR SHALL USE CARE IN REMOVING OR EXCAVATING NEAR ALL EXISTING ITEMS WHICH WILL REMAIN. ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
- 12. THE CONTRACTOR SHALL CONTACT THE IDOT DISTRICT 1 TRAFFIC CONTROL SUPERVISOR FOR ARTERIALS AT KALPANA.KANNAN-HOSADURGA@ILLINOIS.GOV AT LEAST 72 IN ADVANCE OF BEGINNING WORK.
- 13. THE ENGINEER SHALL CONTACT PATRICE HARRIS, AREA TRAFFIC FIELD TECHNICIAN, AT PATRICE.HARRIS@ILLINOIS.GOV A MINIMUM OF TWO (2) WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.
- 14. ANY SIGNAGE, PAVEMENT MARKINGS AND REFLECTORS DAMAGED DURING CONSTRUCTION OUTSIDE THE REMOVAL LINES SHOWN ON THE PLANS SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
- 15. THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.
- 16. FOR STORM SEWERS CONSTRUCTED UNDER THE ROADWAY, BACKFILLING METHODS TWO AND THREE AUTHORIZED UNDER THE PROVISIONS OF ARTICLE 550.07 OF THE STANDARD SPECIFICATIONS WILL NOT BE ALLOWED.
- 17. EXISTING BROKEN FRAMES AND LIDS SHALL BE REMOVED AND DISPOSED OF BY THE CONTRACTOR AND SHALL BE REPLACED AS DIRECTED BY THE ENGINEER. REPLACEMENT FRAMES AND LIDS WILL BE PAID FOR ACCORDING TO ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS, UNLESS A SEPARATE PAY ITEM HAS BEEN PROVIDED.
- 18. DOUBLE LANE MARKERS ARE TO BE USED AS SHOWN ON THE DISTRICT ONE DETAIL "TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)" SHOWN IN PLANS.
- 19. DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
- 20. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS FOR THE PROTECTION OF EXISTING PLANT MATERIAL FOR WHICH THE CONTRACT DOES NOT PROVIDE REMOVAL. THE PROTECTION OF EXISTING PLANT MATERIAL AND THE REPAIR OR REPLACEMENT OF EXISTING PLANT MATERIAL DAMAGED BY THE CONTRACTOR SHALL BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION 201 OF THE STANDARD SPECIFICATIONS.
- 21. THIS PROJECT REQUIRES A US ARMY CORPS OF ENGINEERS (USACE) 404 PERMIT THAT WILL BE SECURED BY THE DEPARTMENT. AS A CONDITION OF THIS PERMIT, THE CONTRACTOR WILL NEED TO SUBMIT AN IN-STREAM WORK PLAN TO THE DEPARTMENT FOR APPROVAL. GUIDELINES ON ACCEPTABLE IN-STREAM WORK TECHNIQUES CAN BE FOUND ON THE USACE WEBSITE. THE USACE DEFINES AND DETERMINES IN-STREAM WORK. THE COST OF ALL MATERIALS AND LABOR NECESSARY TO COMPLY WITH THE ABOVE PROVISIONS TO PREPARE AND IMPLEMENT AN IN-STREAM WORK PLAN WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE UNIT BID PRICES OF THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED WITH THE EXCEPTION OF COFFERDAMS WHICH WILL BE PAID FOR AS "COFFERDAM (TYPE 1) (IN-STREAM /WETLAND WORK)" WITH A BASIS OF PAYMENT OF EACH.

- 22. THE RESIDENT ENGINEER SHALL COORDINATE THE CLOSURE DATE WITH PACE'S TRANSPORTATION ENGINEER (847) 228-3584 AND PROVIDE 10 DAYS NOTICE OF THE CLOSURE.
- 23. THE SUBGRADE STABILITY SHALL BE VERIFIED BY PROOF ROLLING WITH A FULLY LOADED TANDEM-AXLE TRUCK.
- 24. AGGREGATE SUBGRADE IMPROVEMENT (CU YD) HAS BEEN PROVIDED FOR USE AT THE LOCATIONS INDICATED FOR SOILS THAT TEND TO BE UNSTABLE AND/OR UNSUITABLE. THE ACTUAL NEED FOR REMOVAL AND REPLACEMENT WITH ASI WILL BE DETERMINED IN THE FIELD AT THE TIME OF CONSTRUCTION BY THE GEOTECHNICAL ENGINEER. ALL POTENTIALLY UNSTABLE SOILS SHOULD BE TESTED WITH A STATIC OR DYNAMIC CONE PENETROMETER AND TREATED IN ACCORDANCE WITH ARTICLE 301.04 OF THE SSRBC AND IDOT SUBGRADE STABILITY MANUAL. IF UNSTABLE AND/OR UNSUITABLE SOILS ARE NOT ENCOUNTERED, THEN THE QUANTITY SHALL BE DEDUCTED AND NO ADDITIONAL COMPENSATION WILL BE DUE TO THE CONTRACTOR.
- 25. ANY AGGREGATE SUBGRADE IMPROVEMENT CONTAMINATED AND/OR DAMAGED BY THE CONTRACTOR'S VEHICLES AND/OR EQUIPMENTS IS TO BE REMOVED AND REPLACED AS DIRECT BY THE ENGINEER AT CONTRACTOR EXPENSE.
- 26. PIPE UNDERDRAINS SHALL BE INSTALLED ACCORDING TO SECTION 601 OF THE SSRBC AND STANDARD 601001-05. TOP OF PIPE UNDERDRAINS SHALL BE PLACED MINIMUM 6" BELOW THE AGGREGATE SUBGRADE IMPROVEMENT LAYER. THE COST OF MAKING PIPE UNDERDRAINS CONNECTIONS TO DRAINAGE STRUCTURES SHALL BE INCLUDED IN THE COST OF THE PIPE UNDERDRAINS.
- 27. BACKFILLING STORM SEWER CONSTRUCTED UNDER THE ROADWAY SPECIFIED UNDER ART. 550.07(b, c) OF THE SSRBC WILL NOT BE ALLOWED.
- 28. THE CONTRACTOR'S ATTENTION IS CALLED TO THE FACT THAT THE PRESERVATION OF EXISTING TREES IS OF UTMOST IMPORTANCE TO THE CITY OF CHICAGO HEIGHTS. ALL TREE PROTECTION, TREE REMOVAL, PRUNING AND ROOT PRUNING SHALL BE COMPLETED BEFORE CONSTRUCTION OPERATIONS COMMENCE IN ANY AREA. AT NO TIME SHALL THE CONTRACTOR PRUNE OR REMOVE ANY TREES UNLESS SPECIFICALLY DIRECTED BY THE ENGINEER.
- 29. ALL TREE PROTECTION, TREE REMOVAL, PRUNING AND ROOT PRUNING SHALL BE COMPLETED BEFORE CONSTRUCTION OPERATIONS COMMENCE IN ANY AREA. AT NO TIME SHALL THE CONTRACTOR PRUNE OR REMOVE ANY TREES UNLESS SPECIFICALLY DIRECTED BY THE ENGINEER.
- 30. THE CONTRACTOR SHALL ERECT A TEMPORARY FENCE AROUND ALL TREES WITHIN THE CONSTRUCTION AREA TO ESTABLISH A "TREE PROTECTION ZONE" AND AROUND EXISTING WETLANDS TO ESTABLISH A "WETLAND PROTECTION ZONE" BEFORE ANY WORK BEGINS OR ANY MATERIAL IS DELIVERED TO THE JOBSITE. NO WORK IS TO BE PERFORMED (OTHER THAN ROOT PRUNING), MATERIALS STORED OR VEHICLES DRIVEN OR PARKED WITHIN THE "TREE PROTECTION ZONE" AND "WETLAND PROTECTION ZONE". REMOVE PROTECTIVE TEMPORARY FENCE ONLY AFTER ALL CONSTRUCTION WORK HAS BEEN COMPLETED.
- 31. TREE ROOT PRUNING IS TO BE USED ON EXISTING TREES TO PREVENT THE RIPPING UP OF ROOTS WHEN TRENCHING OR EXCAVATION IS WITHIN THE ROOT ZONE OF ADJACENT TREES TO REMAIN. SUPPLEMENTAL WATERING OF TREES SHOULD BEGIN IMMEDIATELY AFTER ROOT PRUNING OF THE TREES HAS OCCURRED.
- 32. THE CONTRACTOR WILL CONTACT THE ROADSIDE DEVELOPMENT UNIT AT 847.705.4171, TO SCHEDULE A WALK THROUGH TO DETERMINE TREES FOR SELECTIVE CLEARING, PRUNING, ROOT PRUNING, REMOVAL, AND TREE PROTECTION A MINIMUM OF 7 DAYS PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
- 33. THE CONTRACTOR WILL CONTACT THE ROADSIDE DEVELOPMENT UNIT AT 847.705.4171, AT LEAST 7 DAYS PRIOR TO PLANTING FOR LAYOUT OF THE SEEDING, TREES AND PLUGS.
- 34. VEHICLES WILL NOT BE ALLOWED TO BE PARKED ON THE SOCCER FIELD NOR FOR USE OF CONSTRUCTION STAGING AT ANY TIME.
- 35. THE DEPARTMENT HAS NOT OBTAINED ANY PERMITS FOR OFFSITE BORROW, WASTE, USE (BWU) AREAS. PRIOR TO WORKING IN BWU AREAS, IF THE CONTRACTOR CHOOSES TO USE ACTIVITIES REQUIRING PERMITS IT IS THE CONTRACTOR'S RESPONSIBILITY TO SECURE THE PROPER PERMITS. IN ADDITION TO THE BORROW REVIEW (BDE 2289) AND USE/WASTE REVIEW(BDE 2290) SUBMITTALS, THE CONTRACTOR SHALL SUBMIT AN EROSION AND SEDIMENT CONTROL (ESC) PLAN FOR EVERY BWU SITE TO THE DEPARTMENT FOR ACCEPTANCE. GUIDELINES FOR ACCEPTABLE BWU PRACTICES CAN BE FOUND IN SECTION II.G.1 AND 2 OF THE SWPPP. THE COST OF ALL MATERIALS AND LABOR NECESSARY TO COMPLY WITH THE ABOVE PROVISIONS TO PREPARE AND IMPLEMENT ESC PLANS WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE UNIT BID PRICES OF THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

HBM ENGINEERING GROUP, LLC
 USER NAME
 = ken.drabant
 DESIGNED
 KJD
 REVISED

 PLOT SCALE
 = 40.00 \(\) in.
 CHECKED
 RTB
 REVISED

 PLOT DATE
 = 12/13/2019
 DATE
 12/12/2019
 REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

CHICAGO ROAD OVER THORN CREEK TRIBUTARY

SCALE: 40.00 '/ in. SHEET 1 OF 1 SHEETS STA. TO STA.

TABLE SECTION COUNTY TOTAL SHEETS NO. 2860 2018-055-CR COOK 67 3

CONTRACT NO. 62G92

	LIB			CONSTRUCTION CODE			
			URBAN	80% FED 20% STATE			
				BR I DGE			
CODE			TOTAL	0004	0043		
NO.	ITEM	UNIT	QUANT I TY	S.N. 016-2305	UTILITIES		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	61	61			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	40	40			
20101000	TEMPORARY FENCE	FOOT	846	846			
20101200	TREE ROOT PRUNING	EACH	5	5			
20200100	EARTH EXCAVATION	CU YD	1605	1605			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	547	547			
20300100	CHANNEL EXCAVATION	CU YD	295	295			
20800150	TRENCH BACKFILL	CU YD	583	196	387		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1639	1639			
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	63	63			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3259	3259			
25100115	MULCH, METHOD 2	ACRE	0.5	0.5			
25200100	SODD I NG	SQ YD	1153	1153			
25200110	SODDING, SALT TOLERANT	SQ YD	1561	1561			

				CONSTRUCTION	N CODE
			URBAN	80% FED 20% STATE	100% LOCAL
				BRIDGE	
CODE			TOTAL	0004	0043
NO.	ITEM	UNIT	QUANTITY	S.N. 016-2305	UTILITIES
25200200	SUPPLEMENTAL WATERING	UNIT	25	25	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	36	36	
28000400	PERIMETER EROSION BARRIER	FOOT	647	647	
28000510	INLET FILTERS	EACH	20	20	
28001100	TEMPORARY EROSION CONTROL BLANKET	SQ YD	544	544	
28100107	STONE RIPRAP, CLASS A4	SQ YD	286	286	
28100203	STONE RIPRAP, CLASS A2	TON	157	157	
28200200	FILTER FABRIC	SQ YD	286	286	
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	547	547	
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	6554	6554	
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	803	803	
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	980	980	
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	297	297	
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	297	297	

^{** 0042}



USER NAME = ken.drabant	DESIGNED	-	KJD	REVISED	-
	DRAWN	-	KJD	REVISED	-
PLOT SCALE = 40.0000 ' / in.	CHECKED	-	RTB	REVISED	-
PLOT DATE = 12/13/2019	DATE	-	12/12/2019	REVISED	-

	SUMMARY OF QUANTITIES		SECTION	COUNTY	TOTAL SHEETS	
	CHICAGO ROAD OVER THORN CREEK TRIBUTARY	2860	2018-055-CR	соок	67	[4
ļ		ļ		CONTRACT	NO. 62	2G92
	SCALE: 40.0000 ' / in SHEET 1 OF 5 SHEETS STA. TO STA.		ILLINOIS FED. AI	ID PROJECT		

^{*} SPECIALTY ITEM

				CONSTRUCTION	N CODE
			URBAN	80% FED 20% STATE	100% LOCAL
				BR I DGE	
CODE			TOTAL	0004	0043
NO.	ITEM	UNIT	QUANTITY	S.N. 016-2305	UTILITIES
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	214	214	
40604060	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", IL 9.5,N50	TON	34	34	
40700100	BITUMINOUS MATERIALS (TACK COAT)	POUND	4342	4342	
40701046	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8	co vp	6220	6220	
40701846	1/4"	SQ YD	6230	6230	
42001300	PROTECTIVE COAT	SQ YD	1491	1491	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	9748	8198	1550
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	621	621	
42400800	DETECTABLE WARNINGS	SQ FT	73	73	
44000100	PAVEMENT REMOVAL	SQ YD	6230	6230	
44000100	TAVERENT REPOVAL	30 10	0230	0230	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	297.0	297	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2280	2280	
44000600	SIDEWALK REMOVAL	SQ FT	5301	3751	1550
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
30100100	TENOVAL OF EXISTING STRUCTURES	LACIT		1	
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	720	720	
	1				

			LIDDAN	CONSTRUCTION CODE		
			URBAN	80% FED 20% STATE	100% LOCAL	
				BRIDGE		
CODE			TOTAL	0004	0043	
NO.	ITEM	UNIT	QUANTITY	S.N. 016-2305	UTILITIES	
50800105	REINFORCEMENT BARS	POUND	87690	87690		
50901720	BICYCLE RAILING	FOOT	126	126		
51500100	NAME PLATES	EACH	1	1		
54003000	CONCRETE BOX CULVERTS	CU YD	353.9	353.9		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	524	524		
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	170	170		
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	42	42		
55100400	STORM SEWER REMOVAL 10"	FOOT	306	306		
55100700	STORM SEWER REMOVAL 15"	FOOT	30	30		
55100900	STORM SEWER REMOVAL 18"	FOOT	11	11		
56103350	DUCTILE IRON WATER MAIN 14"	FOOT	138		138	
56105250	WATER VALVES 14"	EACH	2		2	
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	2		2	
56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	2		2	

^{** 0042}



USER NAME = ken.drabant	DESIGNED -	KJD	REVISED -
	DRAWN -	KJD	REVISED -
PLOT SCALE = 40.0000 ' / in.	CHECKED -	RTB	REVISED -
PLOT DATE = 12/13/2019	DATE -	12/12/2019	REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	SHEETS	SHEET NO.
CHICAGO ROAD OVER THORN CREEK TRIBUTARY	2860	2018-055-CR	соок	[67	5
CHICAGO HOAD OVER THORING CHEEK THIDOTAIN			CONTRAC	T NO. 62	2G92
SCALE: 40.0000 ' / in SHEET 2 OF 5 SHEETS STA. TO STA.		(ILLINOIS (FED. A	ID PROJECT		

^{*} SPECIALTY ITEM

URBAN		URRAN	CONSTRUCTION CODE			
			0110/111	80% FED 20% STATE	100% LOCAL	
				BR I DGE		
CODE			TOTAL	0004	0043	
NO.	ITEM	UNIT	QUANTITY	S.N. 016-2305	UTILITIES	
60108204	PIPE UNDERDRAINS, TYPE 2, 4"	FOOT	2014	2014		
60200310	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	4	4		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4		4	
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1	
	MANUSCIES TYPE A OLDIAMETER TYPE 1					
60224459	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE					
60248900	1 FRAME, CLOSED LID	EACH	2		2	
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1		
60260100	INLETS TO BE ADJUSTED	EACH	2	2		
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1		
60260505	INLETS TO BE ADJUSTED WITH NEW TYPE 3V FRAME AND GRATE	EACH	1	1		
60261530	INLETS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	2	2		
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2	2		
60265900	VALVE VAULTS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3	3		
60406200	FRAMES AND LIDS, TYPE 5, OPEN LID	EACH	3	3		
60500060	REMOVING INLETS	EACH	16	16		

				URBAN	CONSTRUCTION	ı
Г		T	1	I	80% FED 20% STATE	100% LOCAL
	6005				BR I DGE	0043
	CODE	LTEM		TOTAL	0004	0043
	NO.	ITEM	UNIT	QUANTITY	S.N. 016-2305	UTILITIES
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	105	105	
	60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	2322	2322	
	63200310	GUARDRAIL REMOVAL	FOOT	470	470	
	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	305	305	
	66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2	
:	66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	LSUM	1	1	
	66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	LSUM	1	1	
	66901005	ENGINEERED BARRIER	SQ YD	45	45	
	66901006	REGULATED SUBSTANCES MONITORING	CAL DA	30	30	
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12	
	67100100	MOBILIZATION	L SUM	1	1	
	70300912	PAVEMENT MARKING TAPE, TYPE IV 12"	FOOT	444	444	
	72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	15	15	
	72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	1	1	
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2892	2892	

^{** 0042}



USER NAME = ken.drabant	DESIGNED - KJD	REVISED -
	DRAWN - KJD	REVISED -
PLOT SCALE = 40.0000 ' / in.	CHECKED - RTB	REVISED -
PLOT DATE = 12/13/2019	DATE - 12/12/2019	REVISED -

CONSTRUCTION CODE

		SUMN	ИARY	OF QU	ANTITIES	1	F.A.U. RTE.	SECTION	COUNTY	TOTAL	SHEET NO.
CHICA	AGO R	OAD	OVER	THORN	CREEK	TRIBUTARY	2860	2018-055-CR	соок	67	6
		UAD	OVE	111011114	OHLLK				CONTRACT	NO. 62	2G92
SCALE: 40.0000 ' / in S	HEET 3	0	F 5	SHEETS	STA.	TO STA.		(ILLINOIS (FED. A	ID PROJECT		

CONSTRUCTION CODE

^{*} SPECIALTY ITEM

				LIDDANI	CONSTRUCTION	N CODE
				URBAN	80% FED 20% STATE	100% LOCAL
					BRIDGE	
	CODE			TOTAL	0004	0043
	NO.	ITEM	UNIT	QUANTITY	S.N. 016-2305	UTILITIES
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE	FOOT	72	72	
		12"				
				1		
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	16	16	
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	130	130	
		TREE, AESCULUS FLAVEA (YELLOW SWEET		_	_	
*	A2002008	BUCKEYE), 2" CALIPER, BALLED AND	EACH	2	2	
*	A2002820	TREE, CATALPA SPECIOSA (NORTHERN CATALPA), 2-1/2" CALIPER, BALLED AND	EACH	1	1	
			İ			
*	A2002916	TREE, CELTIS OCCIDENTALIS (COMMON	EACH	3	3	
	712002310	HACKBERRY), 2" CALIPER, BALLED AND	L/(CI)			
		TREE CYMNOCLADUS DIOLCUS DRAIBLE TITAN				
*	A2005050	TREE, GYMNOCLADUS DIOICUS PRAIRIE TITAN, (PRAIRIE TITAN KENTUCKY COFFEETREE),	EACH	3	3	
*	A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	5	5	
		Z CALIFER, BALLED AND BORLAFFED	<u> </u>			
		TREE, QUERCUS MACROCARPA (BUR OAK), 2"			_	
*	A2006716	CALIPER, BALLED AND BURLAPPED	EACH	1	1	
*	A2006816	TREE, QUERCUS MUEHLENBERGII (CHINKAPIN OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	2	2	
*	A2007816	TREE, TILIA AMERICANA (AMERICAN LINDEN/	EACH	1	1	
	A2007010	BASSWOOD), 2" CALIPER, BALLED AND	LACIT	1	•	
*	A2008470	TREE, ULMUS AMERICANA PRINCETON (PRINCETON AMERICAN ELM), 2-1/2" CALIPER	EACH	3	3	
*	B2006116	TREE, SYRINGA PEKINENSIS MORTON (CHINA SNOW PEKING LILAC), 2" CALIPER, TREE	EACH	1	1	
		SHOW LEKING LILACY, 2 CALIFER, INCE	<u> </u>			
		PERENNIAL PLANTS, PRAIRIE TYPE, 2"				
*	K0013000	DIAMETER BY 4" DEEP PLUG	UNIT	3.04	3.04	

			URBAN	CONSTRUCTION CODE	
		ı	UNDAN	80% FED 20% STATE	100% LOCA
				BRIDGE	
CODE			TOTAL	0004	0043
NO.	ITEM	UNIT	QUANT I TY	S.N. 016-2305	UTILITIE
X0327036	BIKE PATH REMOVAL	SQ YD	308	308	
X0327518	ELASTOMERIC CHECK VALVE 12" DIAMETER	EACH	1	1	
X0840000	SANITARY SEWER REMOVAL 8"	FOOT	241		241
X0900064	MEMBRANE WATERPROOFING SYSTEM FOR BURIED STRUCTURES	SQ YD	426	426	
X0900075	COFFERDAM (TYPE 1) (IN-STREAM/WETLAND WORK)	EACH	1	1	
X0900080	TEMPORARY BOARDWALK	SQ FT	381	381	
X0900081	TEMPORARY PEDESTRIAN RAILING	FOOT	269	269	
X1900003	SEEDING, CLASS 5B (MODIFIED)	ACRE	0.25	0.25	
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	790	790	
X2502024	SEEDING, CLASS 4B (MODIFIED)	ACRE	0.25	0.25	
X2510635	HEAVY DUTY EROSION CONTROL BLANKET, SPECIAL	SQ YD	544	544	
X4420201	PAVEMENT PATCHING (SPECIAL)	SQ YD	14	14	
X5510100	STORM SEWER REMOVAL	FOOT	10	10	
X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	14	14	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL	L SUM	1	1	
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT	222	222	

^{** 0042}



USER NAME = ken.drabant	DESIGNED	-	KJD	REVISED	-
	DRAWN	-	KJD	REVISED	-
PLOT SCALE = 40.0000 ' / in.	CHECKED	-	RTB	REVISED	-
PLOT DATE = 12/13/2019	DATE	-	12/12/2019	REVISED	-

SUMMARY OF QUANTITIES		F.A.U. RTE.	SEC	ΓΙΟΝ		COUNTY	TOTAL SHEETS	SHEET NO.
CHICAGO ROAD OVER THORN CREEK TRIBU	TARV	2860	2018-0	55-CR		соок	67	7
						CONTRACT	NO. 6	2G92
SCALE: 40.0000 ' / in SHEET 4 OF 5 SHEETS STA.	TO STA.			ILLINOIS	FED. AI	ID PROJECT		

^{*} SPECIALTY ITEM

				CONSTRUCTION	N CODE
			URBAN	80% FED 20% STATE	
				BRIDGE	
CODE			TOTAL	0004	0043
NO.	ITEM	UNIT	QUANTITY	S.N. 016-2305	UTILITIES
Z0007430	TEMPORARY SIDEWALK	SQ FT	587	587	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0022800	FENCE REMOVAL	FOOT	29	29	
Z0027800	GEOTECHNICAL FABRIC	SQ YD	269	269	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	77.1	77.1	
Z0033700	LONGITUDINAL JOINT SEALANT	FOOT	7010	7010	
Z0054400	ROCK FILL	CU YD	811	811	
* Z0056900	SANITARY SEWER 8"	FOOT	265		265
Z0064800	SELECTIVE CLEARING	UNIT	8	8	
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	4	4	
* Z0076600		HOUR	500	500	
Z0076604	TRAINEES - TRAINING PROGRAM GRADUATE	HOUR	500	500	
X1200236	STEEL CASING PIPE, OPEN CUT TRENCH, 24"	FOOT	80		80
X1200237	WATERMAIN IN CASING DIDE DUCTUE IDOM 14"	FOOT	80		80
X1200237	WATERMAIN IN CASING PIPE, DUCTILE IRON, 14"		60		60
X1200238	WATERMAIN FITTINGS	POUNDS	1360		1360
	WALLAWARE ITERIOS				

			LIDDAN	CONSTRUCTION CODE			
			URBAN	80% FED 20% STATE	100% LOCAL		
				BR I DGE			
CODE			TOTAL	0004	0043		
NO.	ITEM	UNIT	QUANTITY	S.N. 016-2305	UTILITIES		
X1200239	WATER MAIN REMOVAL, 14" DIA.	FOOT	130		130		
			<u> </u>	I			


^{** 0042}




USER NAME = ken.drabant	DESIGNED	-	KJD	REVISED -
	DRAWN	-	KJD	REVISED -
PLOT SCALE = 40.0000 ' / in.	CHECKED	-	RTB	REVISED -
PLOT DATE = 12/13/2019	DATE	-	12/12/2019	REVISED -

SUMMARY OF QUANTITIES		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	
CHICAGO ROAD OVER THORN CREEK TRIBUT.	ΔRV	2860	2018-055-CR	соок	67	[:
	AII I			CONTRACT	NO. 6	2G9
SCALE: 40.0000 ' / in SHEET 5 OF 5 SHEETS STA.	TO STA.		ILLINOIS FEI	D. AID PROJECT		

^{*} SPECIALTY ITEM





VARIES 27-35'

VARIES

CHICAGO RD OVER THORN CREEK TRIBUTARY

(SN 016-2305)

STA 149+73.80 TO STA 150+17

LEGEND:

- (A) EXISTING HMA PAVEMENT, $2\frac{1}{4}$ "
- (B) EXISTING PCC PAVEMENT, 9"
- C EXISTING PCC SHARED PATH
- (D) EXISTING COMBINATION CONRETE CURB AND GUTTER, TYPE B-6.18
- (E) EXISTING STEEL PLATE BEAM GUARDRAIL
- F PROPOSED HMA SURFACE COURSE 2", MIX "D", N70
- G PROPOSED HMA BINDER COURSE, IL-19.0, N70, $6\frac{1}{4}$ ",
- H) PROPOSED AGGREGATE BASE COURSE, TYPE B 4"
- I PROPOSED 12" AGGREGATE SUBGRADE IMPROVEMENT
- J PROPOSED CULVERT
- K PROPOSED PCC SIDEWALK, 5 INCH
- L) PROPOSED COMBINATION CONRETE CURB AND GUTTER, TYPE B-6.18
- M PROPOSED 4'-6" BICYCLE RAILING
- (N) TOPSOIL FURNISH & PLACE, 4"

HOT-MIX ASPHALT MIXTURE REQUIREMENTS CHART

OPERATION	MIXTURE TYPE	AIR VOIDS @ Ndes	QUALITY MANAGEMENT PROGRAM (QMP)			
HMA PAVEMENT (FD) 84"	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70, (IL-9.5mm), 2" HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70; 6½"	4% @ 70 GYR. 4% @ 70 GYR.	QC/QA QC/QA			
* GRADE CORRECTION & OVER CULVERT	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70; THICKNESS VARIES	4% @ 70 GYR.	QC/QA			
DRIVEWAYS	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (IL 9.5 mm); 2" HOT-MIX ASPHALT BASE COURSE, 6", (HMA BINDER IL-19 mm)	4% @ 50 GYR. 4% @ 50 GYR.	QC/QA QC/QA			
TEMPORARY SIDEWALK	HOT-MIX ASPHALT BINDER COURSE, (IL 19.0) N50, 4"	4% @ 50 GYR.	QC/QA			
QMP DESIGNATIONS: QUALITY CONTROL/QUALITY ASSURANCE (QC/QA); QUALITY CONTROL FOR PERFORMANCE (QCP); PAY FOR PERFORMANCE (PFP)						

NOTES

SCALE:

- 1. THE UNIT WEIGHT USED TO CALCULATE ALL HMA SURFACE MIXTURE QUANTITIES IS 112 LBS/SQ YD/IN
- 2. THE "AC TYPE" FOR NON-POLYMERIZED HMA SHALL BE "PG 64-22" UNLESS MODIFIED BY DISTRICT ONE SPECIAL PROVISIONS.
- 3. FOR USE OF RECYCLED MATERIALS SEE SPECIAL PROVISIONS.
- 4. QUALITY MANAGEMENT PROGRAM (QMP) IDENTIFIES THE PARTICULAR QUALITY CONTROL SPECIFICATION THAT APPLIES TO THE HMA MIXTURE.
- 5. FOR HMA FULL DEPTH "AC TYPE" SEE SPECIAL PROVISIONS.
- 6. THE LONGITUDINAL JOINT SEALANT SHALL BE PLACED BEFORE THE LAST BINDER LIFT AND BEFORE SURFACE LIFT OF HMA PAVEMENT (FD).



* HOT-MIX ASPHALT BINDER COURSE IS USED ON TOP OF THE PROPOSED CULVERT TO THE NECESSARY

THICKNESS IN LIEU OF 12"AGGREGATE SUBGRADE

IMPROVEMENT AND IS PAID AS HOT-MIX ASPHALT

BINDER COURSE, IL-19.0, N70

USER NAME = johnn	DESIGNED - IH	REVISED -
	DRAWN - IH	REVISED -
PLOT SCALE = 10.0000 ' / in.	CHECKED - JMT	REVISED -
PLOT DATE = 12/12/2019	DATE - 08/16/2019	REVISED -

STATE OF ILLINO	IS
DEPARTMENT OF TRANSP	ORTATION

	TYPICAL SECTIONS CHICAGO ROAD OVER THORN CREEK TRIBUTARY						
CF							
01	IIOAGO K	OND OVE		ZINEEN IINII	JOIANI		
	SHEET	OF	SHEETS	STA.	TO STA.		

				F.A	ARTHWORK SCHEDUL	F			
STA	CUT sq. ft.	AVG END AREA	LENGTH	CU YD	ADJUSTMENT FOR SHRINKAGE*	FILL sq. ft.	AVG END AREA	LENGTH	CU YD
147+00	0.00					0.00			
		27.00	50.00	50.00	42.50		0.00	50.00	0.00
147+50	54.00					0.00			
		61.10	50.00	113.15	96.18		0.00	50.00	0.00
148+00	68.20					0.00			
		62.15	50.00	115.09	97.83		0.19	50.00	0.34
148+50	56.10					0.37			
		54.95	50.00	101.76	86.50		0.99	50.00	1.82
149+00	53.80					1.60			
		44.95	50.00	83.24	70.75		4.15	50.00	7.69
149+50	36.10					6.70			
		36.10	26.00	34.76	29.55		6.70	26.00	6.45
149+76	36.10					6.70			
					CULVERT				
150+14	47.10					2.30			
		47.10	36.00	62.80	53.38		2.30	36.00	3.07
150+50	47.10					2.30			
		48.15	50.00	89.17	75.79		1.25	50.00	2.31
151+00	49.20					0.20			
		45.90	50.00	85.00	72.25		0.15	50.00	0.28
151+50	42.60	10.00		55.55	1	0.10	0.20		1
101.00	12.00	39.25	50.00	72.69	61.78	5,125	0.15	50.00	0.28
152+00	35.90	33.23	30.00	72.03	02.70	0.20	0.23	30.00	- 0.20
152.00	33.30	31.45	50.00	58.24	49.50	0.20	1.25	50.00	2.31
152+50	27.00	31.43	30.00	30.24	45.50	2.30	1.23	30.00	2.51
132130	27.00	28.55	50.00	52.87	44.94	2.50	1.60	50.00	2.96
153+00	30.10	20.55	30.00	32.07	44.34	0.90	1.00	30.00	2.50
155100	30.10	27.50	50.00	50.93	43.29	0.50	1.20	50.00	2.22
153+50	24.90	27.50	30.00	30.55	45.25	1.50	1.20	30.00	2.22
155+50	24.50	22.20	50.00	41.11	34.94	1.50	1.50	50.00	2.78
154+00	19.50	22.20	30.00	41.11	34.34	1.50	1.50	30.00	2.70
134100	15.50	17.90	50.00	33.15	28.18	1.50	2.00	50.00	3.70
154+50	16.30	17.50	30.00	33.13	20.10	2.50	2.00	30.00	- 3.70
134130	10.30	18.50	50.00	34.26	29.12	2.50	4.20	50.00	7.78
155+00	20.70	10.50	30.00	34.20	25.12	5.90	4.20	30.00	+ /./6
133100	20.70	20.50	50.00	37.96	32.27	3.30	3.95	50.00	7.31
155+50	20.30	20.50	30.00	37.50	32.21	2.00	3.55	30.00	7.51
155150	20.30	18.15	50.00	33.61	28.57	2.00	3.55	50.00	6.57
156+00	16.00	10.13	50.00	55.01	20.37	5.10	3.33	50.00	0.57
130100	10.00	20.50	50.00	37.96	32.27	3.10	3.05	50.00	5.65
156+50	25.00	20.50	30.00	37.30	32.21	1.00	3.03	50.00	3.03
130130	25.00	29.10	50.00	53.89	45.81	1.00	1.05	50.00	1.94
157+00	33.20	25.10	30.00	33.03	45.01	1.10	1.03	30.00	1.54
13/100	33.20	34.45	50.00	63.80	54.23	1.10	0.65	50.00	1.20
157+50	35.70	34.43	30.00	03.60	34.23	0.20	0.03	30.00	1.20
13/130	33.70	39.15	50.00	72.50	61.63	0.20	0.45	50.00	0.83
158+00	42.60	33.13	30.00	12.30	01.05	0.70	0.43	30.00	0.65
130+00	42.00	EQ 0F	E0 00	100.25	02.05	0.70	0.25	EO 00	0.65
150.50	75.50	59.05	50.00	109.35	92.95	0.00	0.35	50.00	0.65
158+50	75.50	61.05	E0.00	11417	07.04	0.00	0.00	E0 00	1000
150.00	47.00	61.65	50.00	114.17	97.04	0.00	0.00	50.00	0.00
159+00	47.80					0.00			
				1605.0	1261.0				60.0
				1605.0	1361.0				68.0

			COMBINATION CON	NCRETE CURB AND GUTTER	SCHEDULE	
STATION	STATION	OFFSET	COMBINATION CURB AND GUTTER REMOVAL (FOOT)	COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.12 (FOOT)	COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.18 (FOOT)	
CHICAGO F	ROAD					
147+70	147+95	RT	44	83		
148+34	159+00	RT	1069		1069	
148+40	159+00	LT	1060		1168	
160+55	160+70	LT	30		30	
160+55	160+70	RT	30		30	
147+82	147+96	RT	22	22		
148+31	149+50	RT	25		25	
TOTAL			2280	105	2322	

			CHAININ	EL EXCAV	ATION SCHEDUL	_				
STA	CUT sq. ft.	AVG END AREA	LENGTH	CU YD	ADJUSTMENT FOR SHRINKAGE*		FILL sq. ft.	AVG END AREA	LENGTH	CU YE
10+37	69.40						0.00			
		80.15	18.00	53.43	45.42			0.85	18.00	0.57
10+55	90.90						1.70			
		66.74	10.00	24.72	21.01			1.40	10.00	0.52
10+65	42.57						1.10			
		44.79	10.00	16.59	14.10			2.30	10.00	0.85
10+75	47.00						3.50			
		•								
11+60	196.00						3.40			
		186.50	10.00	69.07	58.71			1.70	10.00	0.63
11+70	177.00						0.00			
		186.05	10.00	68.91	58.57			0.00	10.00	0.00
11+80	195.10						0.00			
		116.20	14.06	60.51	51.43			0.00	14.06	0.00
11+94	37.30						0.00			
				295.0	249.0					3.0

10+37	0.00			
10+57	0.00		40.00	
		4.45	18.00	2.97
10+55	8.90			
		13.00	10.00	4.81
10+65	17.10			
		9.20	10.00	3.41
10+75	1.30			
11+60	0.90			
		27.25	10.00	10.09
11+70	53.60			
		48.80	10.00	18.0
11+80	44.00			
		44.50	14.06	23.1
11+94	45.00			
				63.0

				SIDEWALK SCHEDUL			
STATION	STATION	DETECTABLE WARNING (SQ FT)	PCC SIDEWALK, 5 INCH (SQ FT)	PCC SIDEWALK, 8 INCH (SQ FT)	SIDEWALK REMOVAL (SQ FT)	TEMPORARY SIDEWALK (SQ FT)	TEMPORARY BOARDWALK (SQ FT)
CHICAGO R	OAD						
147+31.78	147+81	14			189		
148+41	148+76	9			196		
153+80	153+90				52		
154+45	154+50	ĺ			26		
155+24	156+00				355		
147+31.78	147+92		420				
148+24	149+86		1380				
148+36	150+98		1534				
151+41	152+23		404				
152+55	153+90		671				
150+19	151+49		2829				
154+45	155+14		347				
155+24	155+62		190				
155+73	156+00		132				
157+70	157+95		130				
158+20	158+53		161				
150+98	151+41			220			
152+23	152+55			168			
155+14	155+24			50			
155+62	155+73			57			
157+95	158+20			126			
147+32	147+92				425	425	
147+87	147+92	20					
148+35	149+59				920	920	
148+39	148+41	10					
149+59	150+13						381
150+13	152+83				1588	1588	
160+60	160+65	10					
160+60	160+65	10					
TOT	ΓAL	73	8198	621	3751	2933	381

		<i>F</i>	AGGREGATE SCHEDULE		
STATION	STATION	AGGREGATE BASE COURSE, TYPE B 4" (SQ YD)	AGGREGATE BASE COURSE, TYPE B 6" (SQ YD)	SUBBASE GRANULAR MATERIAL, TYPE B 4" (SQ YD)	AGGREGATE SUBGRADE IMPROVEMENT 12" (SQ YD)
CHICAGO R	CAD				
147+31.78	147+92	47			
148+36	153+90	153			
154+45	156+00	333			
157+70	158+53	314			
148+24	149+86	86			
150+19	151+49	46			
150+97	151+41		54		
152+23	152+56		47		
154+20	154+40		31		
155+09	155+29		26		
155+60	155+77		23		
156+00	156+15		24		
156+89	157+08		44		
157+91	158+26		48		
147+31.78	159+00				6554
UNDER COM	MBINATION			803	
CURB AND	GUTTER				
	TOTAL	980	297	803	6554

A A	С	С	u	r	а	t	6
		GF	ROUP	, IN	C.		

USER NAME = johnn	DESIGNED	-	LRC	REVISED	-
	DRAWN	-	LRC	REVISED	-
PLOT SCALE = 2.0000 ' / in.	CHECKED	-	JMT	REVISED	-
PLOT DATE = 1/24/2020	DATE	-	08/16/2019	REVISED	_

SCHEDULE OF QUANTITIES - I	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	
CHICAGO ROAD OVER THORN CREEK TRIBUTARY	2860	2018-055-CR	COOK	67	10
CHICAGO ROAD OVER HIGHNORIER INIDOTARI			CONTRACT	NO.	62G92
SCALE: SHEET OF SHEETS STA. TO STA.		ILLINOIS FED. AI	D PROJECT		

				LANDSCAPING SCH	IEDULE		
STATION	STATION	OFFSET	SODDING (SALT TOLERANT) (SQ YD)	SODDING (SQ YD)	SEEDING, CLASS 5B (MODIFIED) (ACRE)	SEEDING, CLASS 4B (MODIFIED) (ACRE)	TOPSOIL FURNISH AND PLACE, 4" (SQ YD)
CHICAGO	ROAD						
148+40	149+81	LT	61				61
150+20	159+00	LT	630				630
148+42	149+72	RT	40				40
150+10	150+96	RT	27				27
151+42	152+21	RT	27				27
152+56	154+20	RT	170				170
154+40	158+95	RT	558				558
148+30	149+50	LT		176			176
150+81	151+75	LT		120			120
147+25	147+95	RT		148			148
148+42	149+31	RT		156			156
150+44	151+00	RT		40			40
151+42	152+21	RT		145			145
152+56	154+20	RT		176			176
154+40	158+95	RT		191			191
149+50	150+09	LT			0.03	0.03	125
150+26	150+81	LT			0.03	0.03	137
149+31	149+70	RT			0.03	0.03	141
150+03	150+44	RT			0.03	0.03	141
160+55	160+70	LT	26				26
160+55	160+70	RT	23				23
L RO	UNDED TOTA	٩L	1561	1153	0.25	0.25	3259

PAVEMENT MARKER SCHEDULE							
STATION	STATION	RAISED REFLECTIVE PAVEMENT MARKER					
CHICAGO ROAD		(EACH)					
147+32	147+83	8					
148+40	159+00	60					
147+32	147+83	6					
148+40	159+00	56					
	TOTAL	130					

		TREE REMOVAL	
STATION OFFSET		TREE REMOVAL (6-15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)
CHICAGO	ROAD		
149+38	40' RT	12	
149+39	36' RT		22
149+75	33' RT	8	
150+10	35' RT	10	
149+66	60' RT	6	
149+75	77' RT	12	
150+13	67.5' RT	13	
150+29	54' LT		18
TOTAL	·	61	40

		TEMPORA	RY LANDSCAPING AND	EROSION SCHEDULE	
STATION	STATION	OFFSET	TEMPORARY EROSION CONTROL SEEDING (POUND)	TEMPORARY EROSION CONTROL BLANKET (SQ YD)	HEAVY DUTY EROSION CONTROL BLANKET, SPECIAL (SQ YD)
CHICAGO F	ROAD				
149+50	150+09	LT	9	125	125
150+26	150+81	LT	9	137	137
149+31	149+70	RT	9	141	141
150+03	150+44	RT	9	141	141
ROUNDED	TOTAL		36	544	544

				PAVEMENT SCHEDU	JLE		
STATION	STATION	HOT-MIX ASPHALT BASE COURSE, 6" (SQ YD)	BITUMINOUS MATERIALS (TACK COAT) (POUND)	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (TON)	HOT-MIX BINDER COURSE, IL-19.0, N70 (TON)	HOT-MIX PAVEMENT (FULL DEPTH), $8 \ \frac{1}{4}$ " (SQ YD)	PAVEMENT PATCHING (SPECIAL) (SQ YD)
CHICAGO I	ROAD						
147+31.78	159+00		4205			6230	
147+76	150+15				214		
150+97	151+41	53.7	25	6.0			
152+23	152+56	47.0	22	5.3			
154+20	154+40	30.9	14	3.5			
155+09	155+29	25.9	12	2.9			
155+60	155+77	23.2	11	2.6			
156+00	156+15	24.2	11	2.7			
156+89	157+08	43.7	20	4.9			
157+91	158+26	47.8	22	5.4			
148+22	SE QUAD						3
148+22	NE QUAD						3
160+59	W QUAD						4
160+59	E QUAD						4
TC	TAL	297	4342	34	214	6230	14

TEMPO	RARY FENCE	
STATION	OFFSET	TEMPORARY FENCE (FOOT)
CHICAGO ROAD		
150+29	54' LT	34
151+02	51.4' LT	30
151+60	53.5' LT	33
150+52 TO 150+95	34'-53' RT	67
153+65	34.2' RT	33
153+87	33.1' RT	33
154+14	34.3' RT	33
154+51	33.2' RT	33
157+49	35' RT	33
157+81	34.3' RT	33
148+43 TO 149+54	27.9' RT	111
150+18 TO 153+90	27.2' RT	372
TOT	AL	846

PER	IMETER EROSION	BARRIER SCH	EDULE
STATION	STATION	OFFSET (LT/RT)	PERIMETER EROSION BARRIER (FOOT)
CHICAGO ROAI	5		
148+31	148+34	31'-50' LT	20
148+34	149+50	50' LT	116
149+50	149+50	50'-60' LT	10
149+50	149+80	60' LT	30
149+80	149+80	60'-68' LT	8
149+80	150+09	68' LT	30
150+78	150+52	68' LT	27
150+52	150+78	50'-68' LT	18
150+78	151+75	50' LT	97
151+75	151+75	33'-50' LT	11
148+41	149+36	50' RT	95
149+36	149+36	50'-80' RT	30
149+36	149+57	80' RT	21
150+03	150+36	80' RT	32
150+36	150+36	80' RT	30
150+36	151+00	50' RT	64
151+00	150+97	41.2'-50' RT	8
		TOTAL	647

TREE ROOT PRUNING					
STATION	OFFSET	TREE ROOT PRUNING (EACH)			
CHICAGO ROAD					
153+65	34' RT	1			
153+87	33' RT	1			
154+14	34' RT	1			
154+51	33' RT	1			
157+81	34' RT	1			
TOTAL		5			


	INLET FILTERS	ı
STATION	OFFSET (LT/RT)	INLET FILTERS (EACH)
HICAGO ROAD		
147+89	RT	1
148+02	LT	1
148+36	RT	1
149+45	LT	1
149+47	RT	1
150+69	LT	1
152+19	LT	1
152+21	LT	1
153+69	RT	1
153+71	LT	1
154+44	RT	1
154+44	LT	1
155+97	RT	1
156+02	LT	1
157+65	LT	1
157+66	RT	1
159+26	RT	1
159+26	RT	1
160+83	RT	1
160+85	LT	1
TOTAL		20


				P.A.	VEMENT MARKING SCHEDULI			
TATION	STATION	TYPE	OFFSET	THERMOPLASTIC PAVEMENT MARKING-LINE 4" (FOOT)	THERMOPLASTIC PAVEMENT MARKING-LINE 12" (FOOT)	THERMOPLASTIC PAVEMENT MARKING-LINE 24" (FOOT)	PAVEMENT MARKING TAPE, TYPE IV 12" (FOOT)	TEMPORARY PAVEMENT MARKING REMOVAL (SO FT)
CHICAGO	ROAD			(1001)	(1001)	(1001)	(1001)	(34 11)
147+32	147+83	DOUBLE YELLOW	CENTERLINE	102				
148+40	159+00	DOUBLE YELLOW	CENTERLINE	2120				
148+40	159+00	YELLOW DASH	LT	390				
147+32	147+83	YELLOW DASH	RT	10				
148+40	159+00	YELLOW DASH	RT	270				
147+82	148+40	WHITE	31' RT		72			
148+40	159+00	WHITE STOP BAR	47' RT			16		
148+22		PEDESTRIAN					216	108
160+59		PEDESTRIAN					228	114
TO	TAL			2892	72	16	444	222


TEMPORARY PAVEMENT MARKING REMOVAL WILL BE USED TO REMOVE THE TEMPORARY PAVEMENT MARKING TAPE, TYPE IV 12" FOR THIS CONTRACT

		REMOVAL SCHED	ULE	
STATION STATION		BIKE PATH REMOVAL (SQ YD)	DRIVEWAY PAVEMENT REMOVAL (SQ YD)	PAVEMENT REMOVAL (SQ YD)
CHICAGO P	OAD			
147+31.78	159+00			6230
148+24	149+86	154		
150+19	151+49	154		
150+97	151+41		54	
152+23	152+56		47	
154+20	154+40		31	
155+09	155+29		26	
155+60	155+77		23	
156+00	156+15		24	
156+89	157+08		44	
157+91	158+26		48	
TO.	TAL	308	297	6230

	USER NAME = JENT	DESIGNED - AB	REVISED -		SCHEDULE OF QUANTITIES - II CHICAGO ROAD OVER THORN CREEK TRIBUTARY						F.A.U. RTE.	SECTION	COUNTY	TOTAL SHE
!		DRAWN - AB	REVISED -	STATE OF ILLINOIS							2860	2018-055-CR	соок	67 1
	PLOT SCALE = 2.0000 '/ in.	CHECKED - JMT	REVISED -	DEPARTMENT OF TRANSPORTATION	DEPARTMENT OF TRANSPORTATION CHICAGO ROAD OVER HIGHN CREEK HIGHDIAKT				INIBUIANI			CONTRAC	T NO. 62G	
	PLOT DATE = 1/17/2020	DATE - 08/16/2019	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.		ILLINOIS FEE	. AID PROJECT	







MAINTENANCE OF PEDESTRIAN ACCESS GENERAL NOTES

- 1. TEMPORARY FACILITIES SHALL BE DETECTABLE AND ACCESSIBLE.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING LABOR, SIGNS AND TRAFFIC CONTROL DEVICES NECESSARY FOR THE MAINTENANCE OF TRAFFIC UNLESS NOTED OTHERWISE IN THE SPECIAL PROVISIONS.
- 3. ALL EXISTING SIGNS THAT CONFLICT WITH THE TRAFFIC CONTROL PLAN SHALL BE COVERED OR REMOVED IN ACCORDANCE WITH ARTICLE 107.25 OF THE STANDARD SPECIFICATIONS.
- 4. ALL TEMPORARY PAVEMENT MARKINGS SHOWING DETERIORATION AFTER SEVEN (7) DAYS OF SERVICE SHALL BE REPLACED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER. ALL MARKINGS THAT REQUIRE REPLACEMENT PRIOR TO SEVEN (7) DAYS OF SERVICE OR REPLACEMENT SHALL BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE.
- 5. ALL TRAFFIC CONTROL DEVICES SHALL BE REMOVED, COVERED OR TURNED AWAY FROM THE TRAFFIC IMMEDIATELY WHEN THEY ARE NO LONGER NECESSARY. WHEN A SIGN IS COVERED, ITS POST SHALL HAVE A REFLECTIVE 3" X 6" DELINEATOR INSTALLED, COST OF THE DELINEATOR IS INCLUDED IN THE COST OF TRAFFIC CONTROL AND PROTECTION, (SPECIAL).
- 6. IMMEDIATELY AFTER THE COMPLETION OF CONSTRUCTION, THE CONTRACTOR SHALL RESTORE ALL PERMANENT PAVEMENT MARKINGS, SIGNS, AND OTHER TRAFFIC CONTROL DEVICES THAT WERE COVERED, REMOVED, DAMAGED OR OTHERWISE AFFECTED BY CONSTRUCTION.
- 7. THE CONTRACTOR SHALL MAINTAIN THE EXISTING PEDESTRIAN CROSSINGS AND WALKWAYS TO THE BEST OF THEIR ABILITY.
- 8. TEMPORARY SIDEWALK SHALL BE USED, AS NECESSARY, IN LOCATIONS SPECIFIED BY THE RESIDENT ENGINEER.
- 9. BOARDWALK AND PEDESTRIAN RAILING SHALL BE CONTRACTOR DESIGNED AND PROVIDED, MUST MEET ADA STANDARDS, AND RAILING SHALL BE EQUIVALENT TO 4 FEET HIGH CHAIN LINK FENCE. CONTRACTOR TO PROVIDE SHOP DRAWINGS FOR REVIEW AND

SUGGESTED SEQUENCE OF CONSTRUCTION

THE FOLLOWING SEQUENCE OF CONSTRUCTION IS SUGGESTED. VARIATIONS MAY BE MADE WITH THE APPROVAL OF THE ENGINEER.

- 1. INSTALL EROSION CONTROL DEVICES PER EROSION CONTROL PLANS.
- 2. INSTALL TRAFFIC CONTROL DEVICES AS PER HIGHWAY STANDARD STANDARD 701101.
- 3. RELOCATE WATERMAIN ON EAST SIDE OF CHICAGO RD AS SHOWN IN WATERMAIN PLANS.
- CONSTRUCT PCC SIDEWALK WHERE THERE ARE GAPS IN THE EXISTING SIDEWALK ON THE EAST SIDE OF CHICAGO RD AS PER THE LIMITS SHOWN IN MOT PLANS.
- CONSTRUCT HMA AND CONCRETE TEMPORARY SIDEWALK, TEMPORARY BOARDWALK, TEMPORARY RAILING, CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT AND PAVEMENT PATCHING AS SHOWN IN MOT PLANS.
- INSTALL DETECTABLE WARNINGS AND TEMPORARY CROSSWALKS ACROSS CHICAGO RD AND PARKSIDE DR AS SHOWN IN TEMPORARY SIDEWALK PLANS.
- INSTALL TRAFFIC CONTROL DEVICES AS PER MOT PLANS AND HIGHWAY STANDARD 701801
 TO CLOSE THE SIDEWALKON THE WEST SIDE OF CHICAGO RD AND SHIFT PEDESTRIANS TO
 THE EAST SIDE.
- 8. CLOSE CHICAGO RD AND DETOUR THE TRAFFIC AS PER DETOUR PLANS.
- 9. REMOVE AND RECONSTRUCT THE ROADWAY AND THE CULVERT, REMOVE GUARDRAIL, CONSTRUCT JUNCTION CHAMBERS, INSTALL DRAINAGE STRUCTURES AND PIPES, RELOCATE SANITARY SEWER, RECONSTRUCT THE WEST SIDE SIDEWALK AND CONCRETE CURB AND GUTTER AND AS SHOWN IN PLANS.
- 10. SHIFT PEDESTRIAN TRAFFIC ON TO THE NEW SIDEWALK ON WEST SIDE AS PER HIGHWAY STANDARD 701801.
- 11. REMOVE THE TEMPORARY SIDEWALK, CONCRETE CURB AND GUTTER ON TH EAST SIDE OF CHICAGO RD. CONSTRUCT THE PROPOSED PCC SIDEWALK, COMBINATION CONCRETE CURB AND GUTTER AND PAVEMENT PATCHING AS SHOWN IN PLANS.
- 12. COMPLETE ROADWAY REGRADING, CHANNEL EXCAVATION AND STONE RIPRAP INSTALLATION AS SHOWN IN PLANS.
- 13. RESTRIPE PERMANENT PAVEMENT MARKINGS.
- 14. REMOVE ALL DETOUR SIGNS AND REOPEN THE ROAD TO TRAFFIC.
- 15. COMPLETE ALL UNFINISHED LANDSCAPING.


SCALE:

16. REMOVE TEMPORARY EROSION CONTROL DEVICES AND REMAINING TRAFFIC CONTROL DEVICES.

USER NAME = JENT	DESIGNED -	AB	REVISED -	
	DRAWN -	AB	REVISED -	
PLOT SCALE = 2.0000 '/ in.	CHECKED -	JMT	REVISED -	
PLOT DATE = 1/17/2020	DATE -	08/16/2019	REVISED -	

Al	ND SUGG	ESTED SI	STRIAN AC EQUENCE (ER THORN	OF CONST	
	SHEET	OF	SHEETS	STA.	TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEE NO.
2860	2018-055-CR	соок	67	14A
		CONTRACT	NO.	62G9
	ILLINOIS FED. A	ID PROJECT		




JMT REVISED - 08/16/2019 REVISED PLOT DATE = 1/24/2020 DATE


DEPARTMENT OF TRANSPORTATION

CHICAGO ROAD OVER THORN CREEK TRIBUTARY SHEETS STA.

CONTRACT NO. 62G92



SIGN LEGEND





M1-I100.2-2412

R11-I101-2418

DETOUR

M4-10L 4818

R3-2 2424

END DETOUR

SIDEWALK

CLOSED

DETOUR

DETOUR

M4-8A(0) 2418

DETOUR

M4-10R 4818



DETOUR

W20-3(0) 4848



M3-3 2412

W20-I103(0)-36

21)

22)

(19)

M3-1 2412

ROAD CLOSED TO THRU TRAFFIC

ROAD

CONSTRUCTION AHEAD

R11-4 6030

DETOUR 10

7

8

9

11)

4≬

_4

4

5

M5-1R 2115

M6-3 2115

M5-1L 2115

16)

17

12

13)

14)

(15)

DETOUR

M4-9L 3024

M4-9R 3024



R3-1 2424

ROAD WILL **CLOSED** FROM MMM THRU 11.2" 11.6" 19.3" 16.9" 8.7" | 7" 11" 28.7" 10.6"

54"

66"

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGN ASSEMBLY (POST-MOUNTED) WITH PANELS (1) AND (2) IN PLACE ON ROAD TO BE CLOSED IN EACH DIRECTION NEAR POINT OF CLOSURE OR WITHIN SECTION TO BE FULLY CLOSED TWO (2) WEEKS PRIOR TO START DATE OF FULL CLOSURE. REMOVE ASSEMBLY AFTER CLOSURE.
- 3. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 4. ONE SIGN ASSEMBLY EQUALS 27.3 SQ. FT.
- 5. EACH SIGN ASSEMBLY SHALL BE PAID FOR AS "TEMPORARY INFORMATION SIGNING".

TYPICAL DETOUR SIGN ASSEMBLY







SCALE:

NOTES:

- THE CONTRACTOR SHALL NOTIFY THE CITY OF CHICAGO HEIGHTS ONE MONTH PRIOR TO THE ROAD CLOSURE. "ROAD WILL BE CLOSED FROM MMM ** THRU MMM" SIGNAGE NEEDS TO BE IN PLACE TWO WEEKS PRIOR TO THE CLOSURE.
- 2. PARKWAY SPACE IS LIMITED. THE CONTRACTOR WILL ENSURE THESE SIGNS DO NOT BLOCK THE SIDEWALK OR EXTEND ONTO THE STREET.
- SIGNS FOR THE DETOUR ARE INCLUDED IN THE CONTRACT LUMP SUM COST OF TRAFFIC CONTROL AND PROTECTION (SPECIAL).
- 4. SIGN PLACEMENT SHALL BE DONE ACCORDING TO DISTRICT STANDARDS TC-10 AND TC-21. (SEE SHEETS 46 AND 49 FOR DETAILS)
- 5. ALL TRAFFIC SIGNS SHALL BE IN ACCORDANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES AND SHALL MEET WITH THE APPROVAL OF THE ENGINEER REGARDING LOCATION, TYPE, SIZE, NUMBER, AND DURATION.
- 6. FOR TYPICAL SIGN INSTALLATION SEE HIGHWAY STANDARD 701901.
- APPROPRIATE IDOT TRAFFIC CONTROL STANDARDS SHALL BE USED TO INSTALL AND REMOVE TRAFFIC CONTROL AND PROTECTION DEVICES.

Accurate

USER NAME = lchrzasc DESIGNED - IH REVISED DRAWN - IH REVISED LOT SCALE = 2.0000 '/ in. CHECKED - LRC REVISED PLOT DATE = 12/12/2019 DATE - 08/16/2019 REVISED

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

DETOUR ROUTE SIGN LEGEND CHICAGO ROAD OVER THORN CREEK TRIBUTARY SHEETS STA.

SECTION COUNTY 2018-055-BR COOK 67 16 CONTRACT NO. 62G92

- 2. ALL THE SOIL EROSION AND SEDIMENT CONTROL FEATURES MUST BE CONSTRUCTED PRIOR TO THE COMMENCEMENT OF UPLAND DISTURBANCE. SOIL DISTURBANCE MUST BE PHASED OR ENACTED IN SUCH A MANNER AS TO MINIMIZE EROSION. SOIL STABILIZATION MEASURES MUST CONSIDER THE TIME OF YEAR, SITE CONDITIONS AND THE USE OF TEMPORARY AND/OR PERMANENT MEASURES.
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT SEDIMENT TRANSPORT OFF THE SITE IS REDUCED BY A COMBINATION OF MINIMIZATION OF EROSION AT THE SOURCE AND THE INSTALLATION OF SPECIFIC MEASURES TO CONTROL OR REDUCE THE TRANSPORT OF SEDIMENT. A COPY OF THE EROSION AND SEDIMENT CONTROL SCHEDULE BEING IMPLEMENTED BY THE CONTRACTOR MUST BE APPROVED BY THE ENGINEER, WILL BE ON THE CONSTRUCTION SITE AT ALL TIMES.
- 4. ALL RUNOFF ORIGINATING ON DISTURBED AREAS ASSOCIATED WITH THIS PROJECT WILL PASS THROUGH ONE OR MORE MEASURES THAT WILL MINIMIZE THE OFF-SITE SEDIMENT IMPACTS OF THE CONSTRUCTION ACTIVITIES.
- 5. THE CONTRACTOR MUST CLEAN UP, GRADE THE WORK AREA AS THE PROJECT PROGRESSES AND INSTALL EROSION PROTECTION TO ELIMINATE THE CONCENTRATION OF RUNOFF, OR MUST INSTALL APPROPRIATE SEDIMENT CONTROL DEVICES TO TRAP SEDIMENT. PAVEMENT MUST BE CLEANED DAILY OR AS NECESSARY TO REMOVE EARTHEN MATERIAL TO THE SATISFACTION OF THE ENGINEER OR AUTHORIZED IDOT PERSONNEL.
- 6. STABILIZATION OF CUT OR FILL SLOPES WITH TEMPORARY OR PERMANENT EROSION CONTROL MEASURES IS REQUIRED WHENEVER THE CUT OR FILL ACTIVITY REACHES 10-FT VERTICALLY OR THE FINISHED SLOPE EQUALS 30-FT, WHICHEVER IS MORE RESTRICTIVE. ONCE THE STABILIZATION MEASURES ARE INSTALLED, THE PLACEMENT OF FILL OR EXCAVATION ACTIVITIES ARE ALLOWED TO PROCEED.
- THE CONTRACTOR WILL ASSUME RESPONSIBILITY FOR MAINTENANCE OF ALL SOIL EROSION CONTROL DURING CONSTRUCTION. THE CONTRACTOR SHALL DESIGNATE ONE OF HIS EMPLOYEES TO BE RESPONSIBLE FOR IMPLEMENTATION OF THE EROSION AND SEDIMENT CONTROL PLAN ON ALL DISTURBED AREAS THROUGHOUT THE PROJECT.
- THE CONTRACTOR'S REPRESENTATIVE HAS TO BE KNOWLEDGEABLE ABOUT INSTALLATION AND MAINTENANCE OF THE REQUIRED MEASURES AND HAVE TAKEN AN ILLINOIS DEPARTMENT OF TRANSPORTATION OR APPROVED EQUAL EROSION AND SEDIMENT CONTROL COURSE. THIS PERSON SHALL HAVE THE AUTHORITY TO CARRY OUT THE IMPLEMENTATION OF ANY INSTRUCTION CONCERNING THE EROSION AND SEDIMENT CONTROL PLAN PROVIDED BY THE ENGINEER. THIS INDIVIDUAL AND THE ENGINEER MUST MAKE INSPECTIONS A MINIMUM OF ONCE EVERY SEVEN DAYS OF THE FOLLOWING:
 - A. DISTURBED AREAS OF THE PROJECT SITE THAT HAVE NOT BEEN FULLY STABILIZED.
 - B. STRUCTURAL CONTROL MEASURES (SUCH AS PERIMETER EROSION BARRIER, ETC.)
 - LOCATIONS WHERE VEHICLES ENTER OR EXIT THE PROJECT SITE.
 - AN ADDITIONAL INSPECTION OF ALL EROSION AND SEDIMENT CONTROL MEASURES MUST BE MADE 21. WEEKLY AND WITHIN 24-HOURS AFTER A 24-HOURS RAINFALL OR EQUIVALENT SNOWFALL EVENT GREATER THAN 0.5-INCH. DURING WINTER MONTHS, ALL MEASURES MUST BE CHECKED BY THE CONTRACTOR AFTER EACH SIGNIFICANT SNOWMELT.
- 9. ALL THE EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED DURING THE CONSTRUCTION SEASON, AS WELL AS OVER THE WINTER SHUTDOWN PERIOD AND OTHER DAYS WHEN THE PROJECT IS CLOSED DOWN FOR A LONGER DURATION. ANY CONTROL MEASURES FILLED MORE THAN 75% MUST BE CLEANED AND RESET AND THESE SPOILS REMOVED TO AN APPROVED SITE.
- 10. SALVAGED TOPSOIL SHALL BE PLACED ON WELL DRAINED LAND AWAY FROM INTERMITTENT AND ACTIVE DRAINAGE PATHS WITH THE APPROPRIATE RUNOFF CONTROL AND SEDIMENT CONTROL MEASURES INSTALLED AROUND THE STORAGE SITE. IMMEDIATELY AFTER THE FINAL SHAPING OF THE STOCKPILE, THE TOPSOIL WILL BE STABILIZED IN ACCORDANCE WITH THE METHOD APPROVED BY IDOT. THE CONTRACTOR WILL PROVIDE ADEQUATE QUANTITY OF SILT FENCE TO CONTROL THE
- EXCAVATION TO BE USED FOR EMBANKMENTS SHALL NOT BE STOCKPILED UNLESS PERIMETER CONTROLS ARE UTILIZED. WHEN THIS MATERIAL IS STOCKPILED FOR THE CONVENIENCE OF THE CONTRACTOR, THE COST OF THE CONTROLS WILL BE BORNE BY THE CONTRACTOR. IF THE MATERIAL IS STOCKPILED AT THE DIRECTION OF THE ENGINEER, THE DEPARTMENT WILL ASSUME THE COST OF INSTALLING AND MAINTAINING THE CONTROLS.
- 12. IN AREAS WHERE A PERMANENT VEGETATIVE COVER IS PRACTICABLE AND INCLUDED IN THE CONTRACT DOCUMENTS, A SPECIAL EFFORT SHOULD BE MADE TO ESTABLISH A COVER AS SOON AS A DISTURBED AREA IS BROUGHT TO FINAL GRADE. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR PROLONG FINAL GRADING AND SHAPING SO THAT THE ENTIRE PROJECT CAN BE PERMANENTLY SEEDED AT ONE TIME.

- 13. IF AND/OR WHEN THE CONTRACTOR REQUESTS CHANGE TO POSTPONE COMPLETION OF THE EXCAVATION OF A SPECIFIC AREA AS A CONTINUOUS OPERATION AND PLACING THE TOPSOIL AS DEFINED IN THE STANDARD SPECIFICATIONS, THE ENGINEER MAY ALLOW THE CONTRACTOR TO STABILIZE THE AREA USING TEMPORARY STABILIZATION WITH STRAW MULCH 25 FEET AWAY FROM THE SHOULDER OF THE ROAD PROVIDED THE FOLLOWING CONDITIONS ARE MET:
 - A. ALL AREAS BEING STABILIZED ARE 1:3 SLOPES OR FLATTER
 - THE CONTRACTOR BEARS THE COST OF PREPARING THE SEED BED AND STABILIZING THE AREA WITH TEMPORARY STABILIZATION WITH MULCH METHOD 2.
 - C. ALL REQUIRED SEDIMENT CONTROL MEASURES FOR THE SECTION OF ROAD IN QUESTION HAVE BEEN INSTALLED AND ARE BEING MAINTAINED.
- 14. TOPSOIL PLACEMENT:

TOPSOIL WILL BE PLACED ON FINAL SLOPES WHICH WILL NOT BE DISTURBED BY FUTURE CONSTRUCTION. TOPSOIL WILL NOT BE PLACED ON SURFACES WHICH WILL BE PAVED IN THE FUTURE NOR ON TEMPORARY STEEP SLOPES.

- 15. THE CONTRACTOR'S REPRESENTATIVE AND THE ENGINEER MUST KEEP A WRITTEN REPORT SUMMARIZING THE REQUIRED INSPECTIONS. THE REPORTS MUST BE KEPT AT THE SITE DURING CONSTRUCTION. THE REPORT MUST ALSO BE RETAINED FOR THREE YEARS FROM THE DATE THE SITE IS FINALLY STABILIZED.
- 16. ANY SEDIMENT LADEN DEWATERING DISCHARGE MUST BE DIRECTED TO AN APPROVED SEDIMENT TRAPPING CONTROL MEASURE PRIOR TO RELEASE FROM THE PROJECT SITE.
- 17. NO WORK IS ALLOWED BEYOND THE PERMITTED AREA. ANY WORK WITHIN A CREEK OR DITCH CAPABLE OF CONVEYING WATER MUST BE CONDUCTED IN THE DRY. PROVISIONS MUST BE MADE TO BYPASS PUMP OR DEWATER ANY AREAS IN WHICH WORK WILL BE CONDUCTED. IN HIGH FLOW CHANNELS WHERE DEWATERING IS NOT POSSIBLE OR PRACTICAL, SILT FENCE OR SEDIMENT CURTAINS MAY BE INSTALLED PARALLEL TO THE STREAM BANK. IN NO CASE WILL THE CURTAINS BE INSTALLED PERPENDICULAR TO THE FLOW. DEWATERING MUST BE DISCHARGED TO A STABLE, NON-ERODIBLE SURFACE AND IN-STREAM WORK BARRIERS MUST BE COMPOSED OF NON-ERODIBLE MATERIAL.
- 18. SEEDING USAGE

CLASS 4B (MODIFIED) AND CLASS 5B (MODIFIED): USED ON FINAL DISTURBED CONSTRUCTION AREAS INDICATED ON THE PLANS.

TEMPORARY EROSION CONTROL SEEDING: USED IN AREAS REQUIRING SHORT TERM TEMPORARY SEEDING DURING CONSTRUCTION.

- 19. THE CONTRACTOR MUST COOPERATE WITH THE ENGINEER AND HIS/HER REPRESENTATIVE WHO WILL MAKE SITE VISITS TO REVIEW THE COMPLIANCE OF THE PLANS IN THE FIELD AND AUDIT IF NECESSARY. THE CONTRACTOR MUST PREPARE THE LOGS AND RECORDS WHEN REQUIRED AND SUBMIT TO IDOT AND/OR APPROPRIATE AGENCIES.
- 20. THE INSTALLATION, MAINTENANCE, REMOVAL AND RESTORATION OF THE AREA DISTURBED BY THE PLACEMENT OF THE PERIMETER EROSION BARRIER ARE INCLUDED IN THE CONTRACT UNIT PRICE FOR PERIMETER EROSION BARRIER. AFTER ALL PERIMETER EROSION BARRIER IS REMOVED, THE AREAS DAMAGED BY THE PERIMETER EROSION CONTROL BARRIER MUST BE RESTORED TO THEIR ORIGINAL CONDITION.
- THE CONTRACTOR WILL PROVIDE THE ENGINEER A PLAN TO ENSURE THAT A STABILIZED FLOW LINE WILL BE PROVIDED DURING STORM SEWER CONSTRUCTION. THIS IS IMPORTANT WHERE NEW STORM SEWER CONNECTS TO EXISTING CULVERTS. THE USE OF A STABILIZED FLOW LINE BETWEEN INSTALLED STORM SEWER AND OPEN DISTURBANCE ESPECIALLY WHEN RAIN IS FORECAST. SO THAT FLOW WILL NOT BE EROSIVE AND WILL REDUCE THE POTENTIAL FOR THE OFFSITE DISCHARGE OF SEDIMENT-BEARING WATERS. THE LACK OF AN APPROVED PLAN OR FAILURE TO COMPLY WILL RESULT IN AN ESC DEFICIENCY DEDUCTION.
- 22. ANY LOOSE MATERIAL DEPOSITED IN THE FLOW LINE OF DRAINAGE STRUCTURES, WHICH OBSTRUCTS THE NATURAL FLOW OF WATER, SHALL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. PRIOR TO ACCEPTANCE OF THE IMPROVEMENT, ALL DRAINAGE STRUCTURES SHALL BE FREE OF DIRT AND DEBRIS. THIS WORK WILL NOT BE PAID FOR SEPARATELY. BUT SHALL BE CONSIDERED INCLUDED IN THE UNIT BID PRICES OF THE CONTRACT.
- 23. STABILIZATION MEASURES SHALL BE INITIATED IMMEDIATELY WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN ONE (1) DAY AFTER THE CONSRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED ON ALL DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION WILL NOT OCCUR FOR A PERIOD OF FOURTEEN (14) OR MORE CALENDAR DAYS.
- 24. EROSION CONTROL ITEMS ARE CONSIDERED TO BE A HIGH PRIORITY ON THIS CONTRACT. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE ENGINEER.
- 25. THE CONTRACTOR IS REQUIRED TO PROVIDE WASHOUT FACILITIES TO COMPLY WITH EROSION CONTROL PERMITS.

- 26. THE CONTRACTOR SHALL ATTACH AN ALUMINUM SIGN WITH THE FOLLOWING TEXT: "PROTECTED WETLAND - NO INTRUSION". THE SIGN(S) SHALL BE ATTACHED TO THE STAKES BY THE METHOD APPROVED BY THE ENGINEER. THE SIGN(S) WILL BE PROVIDED BY THE DEPARTMENT AND SHALL BE PICKED UP BY THE CONTRACTOR FROM THE DISTRICT ONE ROADSIDE DEVELOPMENT ARCHITECT IN SCHAUMBURG, ILLINOIS. SCHEDULING THE PICK UP OF THE SIGNS CAN BE ARRANGED BY CONTACTING THE DISTRICT ONE ROADSIDE DEVELOPMENT UNIT AT (847) 705-4171. WHEN WORK HAS BEEN COMPLETED, THE SIGN(S) SHALL BE RETURNED TO THE DISTRICT ONE ROADSIDE DEVELOPMENT UNIT. THE COST OF PICKING UP, ATTACHING THE SIGNS TO THE TEMPORARY STAKES AND RETURNING THE SIGNS WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR PERIMETER EROSION BARRIER.
- 27. THE CONTRACTOR WILL ASSUME RESPONSIBILITY FOR MAINTENANCE OF ALL SOIL EROSION CONTROL DURING CONSTRUCTION.
- 28. THE CONTRACTOR SHALL CHECK ALL ESC MEASURES WEEKLY AND AFTER EACH RAINFALL, 0.5 INCHES OR GREATER IN A 24 HOUR PERIOD, OR EQUIVALENT SNOWFALL. ADDITIONAL DURING WINTER MONTHS, ALL MEASURES SHOULD BE CHECKED BY THE CONTRACTOR AFTER EACH SIGNIFICANT SNOWMELT.
- 29. THIS PROJECT REQUIRES A US ARMY CORPS OF ENGINEERS (USACE) 404 PERMIT THAT WILL BE SECURED BY THE DEPARTMENT. THE CONTRACTOR WILL NEED TO SUBMIT AN IN-STREAM WORK PLAN TO THE DEPARTMENT FOR APPROVAL. GUIDELINES ON ACCEPTABLE IN-STREAM WORK TECHNIQUES CAN BE FOUND ON THE USACE WEBSITE. THE USACE DEFINES AND DETERMINES IN-STREAM WORK. THE COST OF ALL MATERIALS AND LABOR NECESSARY TO COMPLY WITH THE ABOVE PROVISIONS TO PREPARE AND IMPLEMENT AN IN-STREAM WORK PLAN WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE UNIT BID PRICES OF THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED WITH THE EXCEPTION OF COFFERDAMS WHICH WILL BE PAID FOR AS "COFFERDAM (TYPE 1)(IN-STREAM/WETLAND WORK)" WITH A BASIS OF PAYMENT OF EACH.
- 30. MULCH METHOD 2 SHOULD BE APPLIED TO SLOPES FOR TEMPORARY STABILIZATION PRIOR TO SEASONS WHEN TEMPORARY SEED WILL NOT GERMINATE, FOR EXAMPLE IN MID-JULY OR IN WINTER.

SOIL EROSION AND SEDIMENT CONTROL STRATEGY;

- 1. INSTALL TRAFFIC CONTROL DEVICES.
- 2. ERECT PERIMETER EROSION BARRIERS AS SHOWN ON THE PLANS.
- 3. INSTALL INLET FILTERS AS SHOWN ON THE PLANS.
- 4. ESTABLISH STABILIZED CONSTRUCTION ENTRANCES.
- REMOVE EXISTING PAVEMENTS, SIDEWALKS, AND STRUCTURES AS SHOWN ON THE PLANS.
- 6. CONSTRUCT PROJECT IMPROVEMENTS AS SHOWN ON THE PLANS.
- 7. INSPECT AND MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES FOR THE DURATION OF CONSTRUCTION.
- 8. TEMPORARY STABILIZATION OF EACH STAGE SHOULD BE COMPLETED BEFORE WORK BEGINS ON SUBSEQUENT STAGES.
- 9. STABILIZE DISTURBED AREAS WITH TEMPORARY EROSION CONTROL MEASURES. USE THE PERMANENT SEEDING WITH EROSION CONTROL BLANKET AS SHOWN ON THE PLANS FOR PERMANENT STABILIZATION.
- 10. WHEN THE PERMANENT STABILIZATION IS ESTABLISHED, REMOVE ALL TEMPORARY EROSION CONTROL DEVICES.

HIGHWAY STANDARD

STD. NO.

280001 TEMPORARY EROSION CONTROL SYSTEMS

SOIL PROTECTION SCHEDULE:

STA	ABILIZATION PE	JAN.	FEB.	MAR.	APR.	MAY	JUN.	JUL.	AUG.	SEP.	ост.	NOV.	DEC.
	RMANENT DING						-					-	
	RMANT DING			-									-
	MPORARY DING										-		
	OSION BLANKET/ DROMULCH											-	

Accurate


USER NAME = lchrzasc	DESIGNED	-	LRC	REVISED -
	DRAWN	-	LRC	REVISED -
PLOT SCALE = 2.0000 '/ in.	CHECKED	-	JMT	REVISED -
PLOT DATE = 12/12/2019	DATE	-	08/16/2019	REVISED -

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

SCALE.

EROSION AND SEDIMENT CONTROL NOTES CHICAGO ROAD OVER THORN CREEK TRIBUTARY OF SHEETS STA.


SECTION COUNTY 2018-055-BR COOK 67 17 CONTRACT NO. 62G92





USER NAME = JENT	DESIGNED - LRC	REVISED -
	DRAWN - IH	REVISED -
PLOT SCALE = 100.0000 ' / in.	CHECKED - JMT	REVISED -
PLOT DATE = 1/17/2020	DATE - 08/16/2019	REVISED -

EROSION CONTROL PLANS							
CHICAGO ROAD OVER THORN CREEK TRIBUTARY							
CHICAGO ROAD OVER IHORN CREEK IRIBUTART							
	SHEET	OF	SHEETS	STA.	TO STA.		

RTE.	SEC	TION			COUNTY	SHEETS	NO.
2860	2018-0	055-CR			COOK	67	18
					CONTRACT	NO.	62G92
		ILLINOIS	FED.	ΑI	PROJECT		










USER NAME = lchrzasc	DESIGNED - LRC	REVISED -	
	DRAWN - LRC	REVISED -	
PLOT SCALE = 2.0000 ' / in.	CHECKED - JMT	REVISED -	
PLOT DATE = 12/12/2019	DATE - 08/16/2019	REVISED -	


STABILIZED CONSTRUCTION ENTRANCE PLAN

14' Min





USER NAME = lchrzasc	DESIGNED - LRC	REVISED -
	DRAWN - LRC	REVISED -
PLOT SCALE = 2.0000 ' / in.	CHECKED - JMT	REVISED -
PLOT DATE = 12/12/2019	DATE - 08/16/2019	REVISED -





X0840000	SANI	TARY SEV	VER R	EMOVAL 8"	TOTAL (F	- T)	241	
FROM STA	NOITA	OFFS	ET	TO STATION	OFFSE [*]	\vdash	SUBTOTAL	(FT)
150+7	150+73 41.8' LT		148+32	36.6'	LT	241		


	SANITARY SEWER SUMMARY	
PAY ITEM #	PIPE DESCRIPTION	FOOT
Z0056900	SANITARY SEWER, 8"	265

	SANITARY STRUCTURE SCHEDULE									
STRUCTURE STATION		ON OFFSET STRUCTURE TYPE		RIM		INVERT	ELEVATION			
NO.	STATION	OITSLI	SINUCIONE TIPE	ELEVATION	NORTH	EAST	SOUTH	WEST		
S101	150+73	41.8' LT	MANHOLE, TYPE A, 4' DIA., TYPE 1 FRAME, CLOSED LID	644.00	633.91			633.90		
S102	150+73	63.0' LT	MANHOLE, TYPE A, 4' DIA., TYPE 1 FRAME, CLOSED LID	643.30		633.81	633.80			
S103	149+90	63.0' LT	MANHOLE, TYPE A, 4' DIA., TYPE 1 FRAME, CLOSED LID	643.67	633.46		633.45			
S104	149+60	45.0' LT	MANHOLE, TYPE A, 4' DIA., TYPE 1 FRAME, CLOSED LID	644.33	63331		633.30			
S105	148+34	45.0' LT	MANHOLE, TYPE A, 5' DIA., TYPE 1 FRAME, CLOSED LID	645.47	632.80	632.79		632.80		

	SAINTARY SEWER SCHEDULE									
PIPE NO.	PIPE DESCRIPTION	PIPE SIZE (DIA) (IN)	LENGTH (FT)	SLOPE (%)	FROM STRUCTURE	TO STRUCTURE/ PIPE	TRENCH BACKFILL (CU YD)			
P101	SANITARY SEWER C900 CERTA-LOK	8	21	0.40	S101	S102	17			
P102	SANITARY SEWER C900 CERTA-LOK	8	83	0.40	S102	S103	68			
P103	SANITARY SEWER C900 CERTA-LOK	8	35	0.40	S103	S104	29			
P104	SANITARY SEWER C900 CERTA-LOK	8	126	0.40	S104	S105	103			







NOTES:

- 1. BEDDING/HAUNCHING/INITIAL BACKFILL:
 - A. FOR FLEXIBLE (PVC) PIPE THE BEDDING/HAUNCHING/INITIAL BACKFILL MATERIAL SHALL CONFORM TO IDOT CA-11 OR CA-13 GRADATION.
 - B. FOR RIGID (D.I.) PIPE THE BEDDING MATERIAL SHALL BE CA-11, AND THE HAUNCHING/INITIAL BACKFILL SHALL MATCH THE TRENCH BACKFILL
- 2. AFTER BEDDING HAS BEEN PLACED/COMPACTED/BROUGHT TO GRADE, PLACE AND COMPACT HAUNCHING TO PIPE SPRING LINE.
- 3. PLACE INITIAL BACKFILL IN TWO STAGES AS FOLLOWS:
 1ST STAGE PLACE & COMPACT TO TOP OF PIPE
 2ND STAGE PLACE & COMPACT AT LEAST 12" OVER TOP OF PIPE
- 4. VOIDS LEFT BY SHEETING/BRACING WHEN REMOVED SHALL BE FILLED WITH FINE SAND AND SHALL BE CONSIDERED INCIDENTAL TO THE WORK. SHEETING TO BE LEFT IN PLACE WHEN SPECIFIED ON THE PLANS.
- 5. CONTRACTOR IS RESPONSIBLE FOR ALL RESTORATION BEYOND THE LIMIT OF PAYMENT AS SHOWN.

TO STA.

6. THE COST FOR BEDDING SHALL BE INCLUDED IN THE COST OF PIPE INSTALLATION.

TYPICAL TRENCH BACKFILL DETAILS & TRENCHING NOTES FOR PARKWAY AREAS AND PAVED AREAS

CHRISTOPHER B. BURKE ENGINEERING, LT 9575 W. Higgins Road, Suite 600 Rosemont, Illinois 60018 (847) 823-0500

REVISED USER NAME = rbillings DESIGNED JPC ROB REVISED DRAWN CHECKED JPC REVISED PLOT SCALE = 50' DATE REVISED PLOT DATE = 1/10/2020 12/09/2019

STATE OF ILLINOIS


SANITARY SEWER SCHEDULE AND DETAILS CHICAGO ROAD OVER THORN CREEK TRIBUTARY


SHEETS STA.


SCALE:


SECTION COUNTY 2860 2018-055-CR COOK 67 22 CONTRACT NO. 62G92 ILLINOIS FED. AID PROJECT

DEPARTMENT OF TRANSPORTATION









9575 W. Higgins Road, Suite 600 Rosemont, Illinois 60018

(847) 823-0500

USER NAME = rbillings DESIGNED JPC REVISED CHRISTOPHER B. BURKE ENGINEERING, LT ROB REVISED DRAWN JPC REVISED CHECKED PLOT SCALE = 50' DATE PLOT DATE = 12/13/2019 12/09/2019 REVISED

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE:

SANITARY DETAILS CHICAGO ROAD OVER THORN CREEK TRIBUTARY

SHEETS STA.

TO STA.


SECTION COUNTY 2860 2018-055-CR COOK 67 23 CONTRACT NO. 62G92 ILLINOIS FED. AID PROJECT


	WAT	FR MAIN	RFMO	VAL, 14" DIA.	TOTAL (F	Γ)	138	
FROM STA	OM STATION OFFSET			TO STATION	, ,		SUBTOTAL (FT)	
150+5	58	30.5'	RT	149+30	29.0' F	RT	138	

WATER MAIN SUMMARY							
PAY ITEM #	PIPE DESCRIPTION	FOOT					
	WATERMAIN IN CASING PIPE, DUCTILE IRON, 14"	80					
56103350	DUCTILE IRON WATERMAIN, 14" DIA.	138					

	WATER MAIN STRUCTURE SCHEDULE								
STRUCTURE NO.	STATION	OFFSET	STRUCTURE TYPE	RIM ELEVATION	BOTTOM ELEVATION				
S201	150+58	30.5' RT	VALVE VAULT, 5' DIA., TYPE 1 FRAME, CLOSED LID	644.50	638.00				
S202	149+30	29.0' RT	VALVE VAULT, 5' DIA., TYPE 1 FRAME, CLOSED LID	643.50	637.00				

WATER MAIN SCHEDULE									
PIPE NO.	PIPE DESCRIPTION	PIPE SIZE (DIA) (IN)	LENGTH (FT)	SLOPE (%)	FROM STRUCTURE	TO STRUCTURE/ PIPE	TRENCH BACKFILL (CU YD)		
P201	WATER MAIN, DUCTILE IRON	14	218	N/A	S201	S202	170		






NOTES:

- 1. PROVIDE 6 INCH TO 24 INCH SPACER BETWEEN AUXILIARY VALVE AND HYDRANT BARREL.
- 2. PROVIDE 18 INCHES TO 24 INCHES CLEARANCE BETWEEN NOZZLE AND FINISHED GRADE.
- 3. MINIMUM NOZZLE SIZES SHALL INCLUDE TWO 2-1/2" AND ONE 4-1/2".
- 4. PROVIDE 2 FOOT DIAMETER BY 2 FEET DEEP DRAINAGE PIT AROUND AND ADJACENT FIRE HYDRANT, FILLED WITH WASHED STONE.
- 5. THE MAIN VALVE SHALL HAVE A DIAMETER OF 5-1/4 INCHES AND SHALL OPEN IN A COUNTERCLOCKWISE DIRECTION.
- 6. PAINT HYDRANT YELLOW.

FIRE HYDRANT INSTALLATION

N.T.S.



CHRISTOPHER B. BURKE ENGINEERING, LT

9575 W. Higgins Road, Suite 600 Rosemont, Illinois 60018

(847) 823-0500

BEARING SURFACE AREA TABLE PIPE BEND IN DEGREES

1 SQ. FT.

1 SQ. FT.

2 SQ. FT.

5 SQ. FT.

60 S0. FT. 32 S0. FT. 17 S0. FT. 8 S0. FT. 35 S0. FT.

86 SQ. FT. | 47 SQ. FT. | 24 SQ. FT. | 12 SQ. FT. | 51 SQ. FT. 345 SQ. FT. 187 SQ. FT. 95 SQ. FT. 48 SQ. FT. 204 SQ. FT.

1 SQ. FT.

1 SQ. FT.

1 SQ. FT.

2 SQ. FT.

2 SQ. FT.

2 SQ. FT.

3 SQ. FT.

4 SQ. FT.

1 SQ. FT.

1 SQ. FT. | 1 SQ. FT.

2 SQ. FT. | 1 SQ. FT.

17 SQ. FT. | 9 SQ. FT.

5 SQ. FT. | 3 SQ. FT. |

7 SQ. FT. | 4 SQ. FT. | 2 SQ. FT. |

10 SQ. FT. 5 SQ. FT. 3 SQ. FT.

22 SO. FT. | 12 SO. FT. | 6 SO. FT.

27 SQ. FT. | 14 SQ. FT. | 7 SQ. FT. |

13 SQ. FT. | 7 SQ. FT. | 4 SQ. FT.

PLUG OR TEE

1 SQ. FT.

1 SQ. FT.

3 SQ. FT.


5 SQ. FT.


7 SQ. FT.

9 SQ. FT. 12 SQ. FT.

13 SQ. FT.

16 SQ. FT.






TYPICAL SECTIONS

PIPE SIZE

16′′

- 1. PROVIDE PRECAST OR CAST-IN-PLACE CONCRETE THRUST BLOCKS OF ADEQUATE SIZE AND THRUST BEARING SURFACE TO PREVENT MOVEMENT OF PIPELINE UNDER PRESSURE. SEE TABLE FOR BEARING SURFACE AREA.
- 2. PLACE THE BASE AND THRUST BEARING SIDES OF THRUST BLOCK DIRECTLY AGAINST UNDISTURBED EARTH.
- 3. PLACE THRUST BLOCKING SO THE FITTING JOINTS WILL BE ACCESSIBLE FOR REPAIR.
- 4. THE LENGTH (L) OF THE THRUST BLOCK SHALL BE APPROXIMATELY TWICE THE WIDTH (W).
- 5. THRUST BLOCKS ARE BASED ON A 2000 PSF SOIL BEARING LOAD AND 100 PSI THRUST INSIDE THE PIPE.
- 6. CONCRETE SHALL HAVE A COMPRESSIVE STRENGTH OF NOT LESS THAN 2000 PSI AFTER 28 DAYS.

TYPICAL FORCEMAIN THRUST BLOCK INSTALLATIONS




CARRIER PIPE DIA.	RECOMMENDED MIN. STEEL CASING PIPE DIA
4′′	10''
6′′	12''
8′′	16''
10′′	18''
12''	20''
14''	24''
16′′	24"
18''	30′′
20''	30′′
24''	36′′
30''	42''
36''	48′′
42''	54"
48′′	60''

SCALE:

- 1. STEEL CASING SHALL BE ONE CONTINUOUS SECTION.
- 2. SMYS-SPECIFIC MINIMUM YIELD STRENGTH.
- 3. CASING SPACERS SHALL BE CASCADE MODEL CCS OR APPROVED EQUAL.
- 4. CASING END SEALS TO BE CASCADE MODEL CCES END SEALS OR APPROVED EQUAL. MORTARING OF CASING ENDS SUBJECT ONLY TO PRE-APPROVAL.
- 5. FOR DIP WATERMAIN, ALL PUSH JOINTS IN CASING SHALL HAVE "FIELD LOK" GASKETS AS MANUFACTURED BY AMERICAN, U.S. PIPE OR EQUAL.

STEEL CASING PIPE DETAIL



	RESTRAINED LENGTH TABLE FOR DI PIPE								
	нов	RIZONTAL BEI	ND						
PIPE SIZE	90°	45°	22 . 5°	TEE	DEAD END				
3''	6 FT.	3 FT.	2 FT.	9 FT.	12 FT.				
4′′	7 FT.	3 FT.	2 FT.	12 FT.	15 FT.				
6′′	10 FT.	4 FT.	2 FT.	17 FT.	21 FT.				
8′′	13 FT.	6 FT.	3 FT.	24 FT.	27 FT.				
10′′	15 FT.	7 FT.	3 FT.	29 FT.	32 FT.				
12''	18 FT.	8 FT.	4 FT.	35 FT.	38 FT.				

RESTRAINED LENGTH TABLE FOR PVC PIPE									
	НОВ	RIZONTAL BEI	ND						
PIPE SIZE	90°	45°	22 . 5°	TEE	DEAD END				
3''	8 FT.	4 FT.	2 FT.	16 FT.	21 FT.				
4′′	9 FT.	4 FT.	2 FT.	18 FT.	23 FT.				
6''	12 FT.	5 FT.	3 FT.	27 FT.	32 FT.				
8′′	16 FT.	7 FT.	3 FT.	37 FT.	42 FT.				
10′′	18 FT.	8 FT.	4 FT.	45 FT.	50 FT.				
12''	22 FT.	9 FT.	5 FT.	54 FT.	59 FT.				

NOTES:

- 1. ALL JOINTS WITHIN LENGTH "L" OF FITTING SHALL BE RESTRAINED.
- 2. PLACE RESTRAINED JOINT AGAINST UNDISTURBED EARTH. IF PLACED AGAINST BACKFILL THE BEARING SURFACE AND UNDISTURBED SOIL SHALL BE COMPACTED TO A MINIMUM OF 90% STANDARD PROCTOR DENSITY.
- 3. CONTRACTOR SHALL FURNISH AND INSTALL RESTRAINED JOINT FITTINGS IN ACCORDANCE WITH MANUFACTURERS REQUIREMENTS.
- 4. THE RESTRAINED LENGTH TABLE IS BASED ON TYPE 4 LAYING CONDITION, 100 PSI (MAX) INTERNAL PIPE PRESSURE, 1.5 SAFETY FACTOR AND SILTY GRAVEL MIXTURE.
- 5. PIPE DEPTH SHALL BE A MINIMUM OF 42" UNLESS OTHERWISE SHOWN.


RESTRAINED JOINT FITTING

CHRISTOPHER B. BURKE ENGINEERING, LT 9575 W. Higgins Road, Suite 600 Rosemont, Illinois 60018 (847) 823-0500

USER NAME = rbillings	DESIGNED - JPC	REVISED -
	DRAWN - ROB	REVISED -
PLOT SCALE = 50'	CHECKED - JPC	REVISED -
PLOT DATE = 12/13/2019	DATE - 12/09/2019	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Cl	HICAGO RO		MAIN DET		IBUTARY
	SHEET	OF	SHEETS	STA.	TO STA.



55100400 STORM SEWER REMOVAL 10"					TOTAL	TOTAL (FT) 306	
FROM STAT	ION	OFFSI	= 1	TO STATION	OFFS	ET	SUBTOTAL (FT)
149+47		23.7	LT	149+59	28.9	LT	15
150+69		13.4	RT	150+69	24.7	LT	38
152+19		13.9	RT	152+19	25.4	LT	39
152+21		13.9	RT	152+21	25.3'	RT	11
153+69		14.6	RT	153+69	25.5'	RT	11
153+71		14.6	RT	153+71	25.6	LT	40
154+45		14.9	RT	154+45	25.1'	RT	10
154+45		14.7	RT	154+45	25.4	LT	40
155+97		15.2	RT	155+97	25.3'	RT	10
156+02		15.2	RT	156+02	25.4	LT	41
157+65		15.8	RT	157+65	25.4	LT	41
157+67		15.8	RT	157+67	25.4	RT	10

X5510100	S	TORM SE	WER I	REMOVAL	TOTAL	(FT)	10	
FROM STA	TION OFFSET			TO STATION	OFF:	SET	SUBTOTAL	(FT)
150+0	13	13.1	RT	150+69	16.3	RT	10	

55100500	S	TORM SE	WER	REMOVAL, 12"	TOTAL (FT)	17
FROM STA	NOIT	OFFS	ET	TO STATION	OFFSET	SUBTOTAL (FT)
149+7	2	22.5	LT	149+89	22.1' LT	17

55100700	STORM SEW	ΈR	REMOVAL, 15"	TOTAL (FT)	30
FROM STATION	OFFSET		TO STATION	OFFSET	SUBTOTAL (FT)
149+80	23.0'	LT	149+95	23.0' LT	15
149+80	27.0	LT	149+95	273.0' LT	15

55100900	STORM SEWER			REMOVAL, 18	TOTAL (FT) 11
FROM STAT	ATION OFFSET		TO STATION	OFFSET	SUBTOTAL (FT)	
150+08		23.7'	LT	150+19	23.7 L	Г 11

STORM SEWER SUMMARY						
PAY ITEM # PIPE DESCRIPTION						
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	537				
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	170				
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	42				

60255500	MANHOLES TO B	E ADJUSTED	W/ NEW TYPE 1	FRAME, CLOSED LID	TOTAL (EACH) 1
STRUCTURE NO.	STATION	OFFSET	RIM ELEVATION	INVERT ELEVATION	SUBTOTAL (EACH)
S19	156+42	15.3' RT	644.72	INV (N) 639.94 INV (S) 639.94	1

60500060	REMOVING	INLETS		TOTAL (EACH) 16
STRUCTURE NO.	STATION	OFFSI	ΕT	SUBTOTAL (EACH)
S1	150+69	24.0	LT	1
S2	149+45	24.0	LT	1
S4	153+69	24.0	RT	1
S5	153+71	24.0	LT	1
S6	154+45	24.0	RT	1
S7	154+44	24.0	LT	1
S8	155+97	24.0	RT	1
59	156+02	24.0	LT	1
S10	157+65	24.0	LT	1
S11	157+65	24.0	RT	1
S14	151+85	24.0	LT	1
S15	152+55	24.0'	LT	1
S16	151+85	24.0'	RT	1
S17	152+55	24.0	RT	1
520	152+21	24.9'	RT	1
S21	152+19	24.8	LT	1
				•

60260505	INLETS TO E TYPE 3V FRA	TOTAL (EACH)	1			
STRUCTURE NO.	STATION	OFFSET		RIM ELEVATION	SUBTOTAL (EACH	
S3	149+46	24.8'	RT	644.95	1	

60260100	INLETS TO E	BE ADJU	STED	TOTAL (EACH)	2	
STRUCTURE NO.	STATION	OFFS	ET	RIM ELEVATION	SUBTOTAL (EA	ACH)
S12	147+89	28.2	RT	645.10	1	
S13	148+36	31.7'	RT	645.91	1	

*** \$12 AND \$13 ADJUSTED W/ NEW TYPE 23 FRAME & GRATE DURING MAINTENANCE OF PEDESTRIAN ACCESS


60265900	VALVE VAULTS TYPE 1 FRAME	TOTAL (EACH)	1		
STRUCTURE NO.	STATION	OFFSET	RIM ELEVATION	SUBTOTAL (EA	4CH
S26	148+50	28' RT		1	

60265900	VALVE VAULTS	TO BE ADJU	ISTED***	TOTAL (EACH)	3
STRUCTURE NO.	STATION	OFFSET	RIM ELEVATION	SUBTOTAL (EA	ACH)
S24	147+82	28' RT	645.86	1	
S25	148+28	50' RT	646.66	1	
S27	147+57	28' RT		1	

**** S24 AND S25 ADJUSTED W/ NEW TYPE 1 FRAME, CLOSED LID DURING MAINTENANCE OF PEDESTRIAN ACCESS

DIAMETER	DISCHARGE		SLOPE (feet per foot)
d (inches)	Q (cfs)	n = 0.012	n = 0.013	n = 0.024
8	1.05	0.0064	0.0075	0.026
10	1.64	0.0048	0.0056	0.019
12	2.36	0.0037	0.0044	0.015
15	3.68	0.0028	0.0032	0.011
18	5.30	0.0022	0.0026	0.0087
21	7.22	0.0018	0.0021	0.0071
24	9.43	0.0015	0.0017	0.0059
27	11.9	0.0013	0.0015	0.0051
30	14.7	0.0011	0.0013	0.0044
33	17.8	0.00097	0.0011	0.0039
36	21.2	0.00086	0.0010	0.0034
42	28.9	0.00070	0.00082	0.0028
48	37.7	0.00059	0.00069	0.0023
54	47.7	0.00050	0.00059	0.0020
60	58.9	0.00044	0.00051	0.0017
66	71.3	0.00038	0.00045	0.0015
72	84.8	0.00024	0.00040	0.0014

Slopes Necessary to Create Minimum Velocity of 3 ft/sec In Pipes Flowing Full Table 8-008.04



LATERAL CONNECTION DETAIL FOR P18, P20, & P21

60260300	INLETS TO BE AL	DJUSTED WIT	H NEW TYPE 1 FRAME, OPEN LID	TOTAL (EACH) 1
STRUCTURE NO.	STATION	OFFSET	RIM ELEVATION	SUBTOTAL (EACH)
S22	148+02	18.6' LT	645.10	1
60250500		BASINS TO B	E ADJUSTED W / NEW	TOTAL (EACH) 1

60250500	60250500 CATCH BASINS TO BE ADJUSTED W / NEW TYPE 1 FRAME, CLOSED LID TOTAL (EACH							
STRUCTURE NO.	STATION	OFFSET	RIM ELEVATION	SUBTOTAL (EACH)				
S23	147+95	19.7' RT	645.16	1				

			DRAINAGE STRUCTURE SCHEDULE					
STRUCTURE	CTATION	* _{OFFSET}	CTRUCTURE TYPE	RIM				
NO.	STATION *OFFSET STRUCTURE TYPE		ELEVATION	NORTH	EAST	SOUTH	WEST	
S1	150+69	24.0' LT	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	644.58		640.58		
S2	149+45	24.0' LT	CATCH BASINS, TYPE A, 4' DIAMETER, TYPE 3V FRAME AND GRATE	644.96	640.96		640.96	
S4	153+69	24.0' RT	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	644.07				640.09
S5	153+71	24.0' LT	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	644.07		640.19		
S6	154+45	24.0' RT	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	644.21				640.26
S7	154+44	24.0' LT	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	644.21		640.37		
S8	155+97	24.0' RT	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	644.50				640.62
59	156+02	24.0' LT	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	644.51		640.75		
S10	157+65	24.0' LT	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	644.83		640.95		
S11	157+67	24.0' RT	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	644.84				640.84
S14	151+85	24.0' LT	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	643.86	639.86			
S15	152+55	24.0' LT	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	643.85			639.85	
S16	151+85	24.0' RT	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	643.86	639.86			
S17	152+55	24.0' RT	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	643.85			639.85	
S18	152+23	13.9' RT	MANHOLES, TYPE A, 8' DIAMETER, TYPE 1 FRAME, CLOSED LID	643.96	638.95	639.68	638.95	639.58
S20	152+23	24.0' RT	CATCH BASINS, TYPE A, 4' DIAMETER, TYPE 3V FRAME AND GRATE	643.81	639.72		639.73	639.72
521	152+23	24.0' LT	CATCH BASINS, TYPE A, 4' DIAMETER, TYPE 3V FRAME AND GRATE	643.81	639.72	639.72	639.73	
S27	148+68	24.0' RT	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	644.74				644.74
528	148+68	21.6 LT	CATCH BASINS, TYPE A, 4' DIAMETER, TYPE 3V FRAME AND GRATE	644.78	641.23	641.23		

^{*} OFFSET FOR DRAINAGE STRUCTURES IN CURB & GUTTER IS TO EDGE OF PAVEMENT. ALL OTHER OFFSETS ARE TO THE CENTER OF THE STRUCTURE.


	STORM SEWER SCHEDULE												
PIPE NO.	PIPE DESCRIPTION	PIPE SIZE (DIA) (IN)	LENGTH (FT)	SLOPE (%)	FROM STRUCTURE	TO STRUCTURE/ PIPE	TRENCH BACKFILL (CU YD)						
P1	STORM SEW CL A 2	12	38	EX	S1	P20	7.8						
P2	STORM SEW CL A 1	12	36	0.37	S14	521	5.1						
P3	STORM SEW CL A 1	12	36	0.37	S15	S21	6.2						
P4	STORM SEW CL A 1	12	36	0.37	S21	S18	7.0						
P5	STORM SEW CL A 1	12	36	0.37	S16	S20	6.2						
P6	STORM SEW CL A 1	12	36	0.37	S17	S20	6.2						
P7	STORM SEW CL A 1	12	10	0.37	S20	S18	1.8						
P8	STORM SEW CL A 1	12	40	EX	S5	P21	6.9						
P9	STORM SEW CL A 1	12	11	EX	54	P21	2.0						
P10	STORM SEW CL A 1	12	40	EX	S7	P21	6.9						
P11	STORM SEW CL A 1	12	10	EX	S6	P21	1.8						
P12	STORM SEW CL A 1	12	41	EX	S9	P21	6.7						
P13	STORM SEW CL A 1	12	10	EX	S8	P18	1.7						
P14	STORM SEW CL A 1	12	42	EX	S10	P18	7.7						
P15	STORM SEW CL A 1	12	10	EX	S11	P18	1.8						
P16	EX 12" STORM SEW	EX 12	8	EX	S3	PR CULVERT	4.4						
P17	STORM SEW CL A 1	12	10	EX	S2	P19	2.4						
P18	EX 30"x45" ELLIP.	EX 30"x45" ELLIP.	8	EX	EX MH	S19	21.8**						
P19	EX 15" STORM SEW	EX 15	8	EX	EX MH	PR CULVERT	9.2						
P20	EX 30"x45" ELLIP.	EX 30"x45" ELLIP.	8	EX	S18	PR CULVERT	121.1**						
P21	EX 30"x45" ELLIP.	EX 30"x45" ELLIP.	8	EX	S19	S18	108.2**						
P22	EX 15" STORM SEW	EX 15	8	EX	EX MH	PR CULVERT	3.8						
P23	EX 18" STORM SEW	EX 18	8	EX	EX MH	PR CULVERT	3.7						
P24	STORM SEW CL A 1	12	45	0.37	S27	S28	5.0						
P25	STORM SEW CL A 1	12	73	0.37	S28	S2	10.4						
P26	STORM SEW CL A 2	12	3.8	0	JC2	PR CULVERT	0						
P27	STORM SEW CL A 1	12	1.5	0	JC2	JC2	0						
P28	STORM SEW CL A 1	36	85	0.10	JC1	JC2	40						
P29	STORM SEW CL A 1	36	85	0.10	JC1	JC2	40						


REINSTATE EXISTING STORM SEWER (P16, P19, P20, P22, AND P23) THRU PROPOSED CULVERT WALLS. COST IS INCLUDED IN BOX CULVERT PAY ITEM.


** COST INCLUDED IN EXPLORATION TRENCH, SPECIAL.



USER NAME = JENT	DESIGNED - JMT	REVISED -
	DRAWN - IH	REVISED -
PLOT SCALE = 100.0000 ' / in.	CHECKED - JMT	REVISED -
PLOT DATE = 1/17/2020	DATE - 08/16/2019	REVISED -







PAVEMENT MARKING LEGEND

- 1 THERMOPLASTIC PAVEMENT MARKING LINE 4" (WHITE 10' LINE, 30' SPACE)
- 2) THERMOPLASTIC PAVEMENT MARKING LINE 4" (DOUBLE YELLOW) @ 11" C-C
- 3 THERMOPLASTIC PAVEMENT MARKING LINE 12" (WHITE 6' LINE, 2' SPACE)
- 4 THERMOPLASTIC PAVEMENT MARKING LINE 24" (WHITE)
- (5) RAISED REFLECTIVE PAVEMENT MARKER

LANDSCAPING LEGEND

SEEDING, CLASS 4B (MODIFIED) AND 5B (MODIFIED)
INTERPLANTED WITH PRAIRIE PLUGS
W/ HEAVY DUTY EROSION CONTROL BLANKET (SPECIAL)

SODDING

SODDING, SALT TOLERANT




USER NAME = JENT	DESIGNED	-	LRC	REVISED -
	DRAWN	-	IH	REVISED -
PLOT SCALE = 100.0000 ' / in.	CHECKED	-	JMT	REVISED -
PLOT DATE = 1/17/2020	DATE	-	08/16/2019	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

 		G AND LAI ER THORN		NG PLANS RIBUTARY	
SHEET	OF	SHEETS	STA.	TO S	TA.

F.A.U. RTE.	SECTION		COUNTY	TOTAL SHEETS	SHE NO
2860	2018-055-CR	COOK	67	29	
			CONTRACT	NO.	62G
	ILLINOIS	FED. AI	D PROJECT		



GENERAL NOTES:

- 1.It will be the responsibility of the Contractor to direct the stream flow during construction in order to keep the Construction areas free of water. The method of water diversion shall be subject to the approval of the Engineer and the cost shall be included with the cost of the Concrete Box Culverts.
- 2. Layout of the slope protection system may be varied to suit ground conditions in the field as directed by the Engineer.
- 3.The limits and quantities of removal and replacement shown are based on the boring data and may be modified by the District Geotechnical and Field Engineers for variable subsurface conditions encountered in the field.
- 4.The Rock fill shall be capped with 6 in. of CA7 and satisfy the Standard Specifications unless otherwise indicated in the Special Provisions. The cost of the capping material shall be included in the pay item for Rock fill.
- 5. Precast alternate is not allowed.

INDEX OF SHEETS

- S-01 General Plan and Elevation
- S-02 General Notes, Index of Sheets and Total Bill of Material
- S-03 Culvert Plan Top Slab Details
- S-04 Culvert Plan Bottom Slab Details
- S-05 Culvert Sections and Details (Sheet 1 of 3)
- S-06 Culvert Sections and Details (Sheet 2 of 3)
- S-07 Culvert Sections and Details (Sheet 3 of 3)
- S-08 Bicycle Railing Plan and Elevation
- S-09 Bicycle Railing Details
- S-10 Soil Boring Logs

TOTAL BILL OF MATERIAL

ITEM	UNIT	TOTAL
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	720
STONE RIPRAP, CLASS A4	SQ YD	286
FILTER FABRIC	SQ YD	286
REMOVAL OF EXISTING STRUCTURES	EACH	1
REINFORCEMENT BARS	POUND	87,690
BICYCLE RAILING	FOOT	126
NAME PLATES	EACH	1
CONCRETE BOX CULVERTS	CU YD	353.9
MEMBRANE WATERPROOFING SYSTEM FOR BURIED STRUCTURES	SQ YD	426
ROCK FILL	CU YD	811

STATION 149+95.42

BUILT 20__ BY


STATE OF ILLINOIS

F.A.U. RTE 2860
(CHICAGO ROAD)

SECTION 2018-055-CR
LOADING HL-93


STRUCTURE NO. 016-2305


NAME PLATE
See Std. 515001



SECTION THRU BARREL

*At upstream end, NW and SW cells only.





WATERWAY INFORMATION

	Exist. Overtopping Elev. = 644.01 at Sta. 152+00													
Drainage Area = 2.2 Square Miles Prop. Overtopping Elev. = 644.01 at Sta. 152+00														
Flood Event	Freq.	Q	Opening	- Sq. Ft.	Nat.	Head	- Ft.	Headwai	ter Elev.					
Trood Event	Yr.	C.F.S.	Exist.	Prop.	H.W.E.	Exist.	Prop.	Exist.	Prop.					
	10	375	50	156	642.8	1.0	0.0	643.8	642.8					
Design	50	520	58	156	643.4	0.9	0.0	644.3	643.4					
Base	100	590	61	156	643.7	0.8	0.1	644.5	643.8					
Scour Design Check	200	640												
Overtop Exist.														
Overtop Prop.														
Max. Calc.	500	735	65	156	644.1	0.5	0.0	644.6	644.1					

10-year velocity through the existing culvert = 7 ft/s 10-year velocity through proposed culvert = 3 ft/s

2 year flow rate (Q) = 280 cfs

Estimated water surface elevation = 639.33 ft


HBM ENGINEERING GROUP, LLC

USER NAME =	DESIGNED	-	MAA, SK	REVISED -
	CHECKED	-	MI, RTB	REVISED -
PLOT SCALE =	DRAWN	-	MAA, SK	REVISED -
PLOT DATE =	DATE	-	12/12/2019	REVISED -


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


GENERAL NOTES, INDEX OF SHEETS AND TOTAL BILL OF MATERIAL	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	
STRUCTURE NO. 016-2305	2860	2018-055-CR	соок	67	31
	CONTRACT NO. 62G92				
SHEET S-2 OF S-10 SHEET		ILLINOIS FED A	D PROJECT		


^{**}Non- woven geotextile fabric shall conform to the requirement of Article 1080.01 of the Standard Specifications. The minimum weight of the fabric shall be 6 ounces per square yard. Cost included with Rock fill




12/13/2019 10:07:20 AM









* Cut bars in field to fit

NOTE:


1. At locations where pipes meet the culvert, ends shall be sealed per Art. 542.04(d).




USER NAME =	DESIGNED	-	MAA, SK	REVISED	-
	CHECKED	-	MI, RTB	REVISED	-
PLOT SCALE =	DRAWN	-	MAA, SK	REVISED	-
PLOT DATE =	DATE	-	12/12/2019	REVISED	-


CULVERT SECTIONS AND DETAILS (SHEET 2 OF 3)											
STRUCTURE NO. 016-2305											
CHEET	0.6	ΩE	C 10	CHEET							

F.A.U. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEE NO.	
2860	2018-055-CR		соок	67	35
			CONTRA	CT NO. 6	32G92
	ILLINOIS	FED. A	D PROJECT		





12/13/2019 10:08:13 AM



SOIL BORING LOG

Page <u>1</u> of <u>1</u>

Date ___5/22/19

ROUTE DESCRIPTION Chicago Road Over Thorn Creek Tributary LOGGED BY E. Mueller SECTION 059-0102 MFT LOCATION Over Thorn Creek Tributary, SEC. , TWP. , RNG. Latitude , Longitude Cook Hollow Stem Auger COUNTY **DRILLING METHOD** HAMMER TYPE D UM В В SN 016-1341 STRUCT, NO. Surface Water Elev. L 0 W С 0 Ε 0 N/A ft Station Stream Bed Elev. s 0 S BORING NO. Groundwater Elev.: S S Qu Qu Station 149+80 First Encounter 637.6 ft**▼** 19.2 ft LT 638.1 ft∑ Offset **Upon Completion** Ground Surface Elev. 645.05 ft (ft) (/6") (tsf) (%) (ft) (/6") (tsf) (%) After 0 Hrs. Asphalt (2.0 inches) Gray, Silty Clay (continued) 644.05 PCC (10.0 inches) Gray, Crushed Limestone CA-06, 2.3 27 1.3 19 5 В Dark Gray, Silty Clay В 4 1.2 14 7 B 4 1.0 30 -25 6 В 639.55 Brown and Gray, Silty Clay Gray, Sandy Gravel 0.8 27 10 2 В 0.4 37 14 -10 2 В 0.5 34 4 В 1.3 22 -15 5 В 610.05 -35 - Silt Seam at 34.5 ft. End of Boring 1.4 19 В Sand Seam at 17.0 ft. Gray, Sand 626.05 1.6 19 Gray, Silty Clay 4

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer) The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)

Illinois Department of Transportation

Division of Highways

Millennia Professional Services of Illinois, Ltd.

FAU Route 2860/Chicago

SOIL BORING LOG

Page $\underline{1}$ of $\underline{1}$

Date ___5/22/19

ROUTE	Road		CR	IPTION	1	Chicag	o Road Over Thorn Creek Tributary	L0	OGG	ED BY	E. M	lueller
SECTION	059-0102 MF	Т	_ [OCAT	ON_	Over -	horn Creek Tributary, SEC., TWP.	, RNG. ,				
							de , Longitude					
COUNTY	Cook D	RILLING	ME	THOD		Но	low Stem Auger HAMMER	TYPE		A	uto	
STRUCT. NO			D E P	B L O	U C S	M 0 1	Surface Water Elev. N/A Stream Bed Elev. N/A		D E P	B L O	U C S	M 0 -
BORING NO Station Offset	150+30 19.3 ft RT	<u> </u>	T H (ft)	W S (/6")	Qu (tsf)	S T (%)	Upon Completion 638.8		H (ft)	(/6")	Qu (tsf)	S T (%)
Ground Surface Asphalt (2.0 inche		/644.63	(11)	(,0,)	(131)	(70)	After 0 Hrs. Gray, Silty Clay (continued)	_ π	(11)	(,,,	(131)	(70)
PCC (10.0 inches		643.80	_	-			Gray, Silty Clay (continued)		_			
Gray, Crushed Li	<u>, </u>			10						4		
FILL	1110010110 07 (00,	/		5	2.3	24	- Sand Seam at 21.5 ft.			4	1.9	19
Black, Silty Clay				5	В					6	В	
		641.80					L	621.80				
Brown and Gray,	Silty Clay		_	16			Gray, Silty Clay Loam		_	4		
		-		4		20				4	0.6	22
			-5	3					-25	5	В	
		-		1				619.30				
		∇					Gray, Silty Clay					
		_	_	2					_	4	4.0	
		Ž		2	0.8 B	23				4 5	1.6 B	17
		636.80	_		6				_		В	
Gray, Silty Clay		030.00		-								
City, City City			_	0					_	4		
				0	0.3	49				6	2.6	23
			-10	0	В				-30	6	В	
			_						_			
				0			Gray, Sand	<u>613.80</u>				
			_	0	0.1	33	Gray, Sand		_			
				1	В	**						
		-		2	0.0					5		44
				2	0.3 B	32		000.00		5 7		14
		629.30	-15	'			End of Boring	609.80	-35	<u>'</u>		
Gray, Silty Clay		029.30	_	1			End of Boiling		_			
City, City City		-		5								
				6	1.6	22						
				0	В							
				1								
			_	4					_			
		-		5	1.9	22						
			-20	1 - 1	В				-40			
			20	-								ш

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer) The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)

DESIGNED - MAA, SK REVISED -JSER NAME = CHECKED - MI, RTB REVISED -REVISED -DATE - 12/12/2019 REVISED -

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

SECTION COUNTY **SOIL BORING LOGS** 2860 2018-055-CR соок 67 39 **STRUCTURE NO. 016-2305** CONTRACT NO. 62G92 SHEET S-10 OF S-10 SHEET

TOTAL BILL OF MATERIAL

ITEM	UNIT	TOTAL
Concrete Structures	Cu. Yd.	13.8
Reinforcement Bars, Epoxy Coated	Pound	2720
Frames And Lids, Type 5, Open Lid	Each	3




DATE SIGNED: 1/17/2020 EXP. DATE: 11/30/2020



ELEVATION

0.107%

36"⊘ Storm Sewer




DESIGN SPECIFICATIONS

2002 AASHTO Std. Specifications

DESIGN STRESSES FIELD UNITS

f'c = 3,500 psi fy = 60,000 psi (Reinforcement)



PLAN

Accurate

1/16/2020 2:41:33 PM

USER NAME = JENT	DESIGNED - SAT	REVISED -
	CHECKED - SPS	REVISED -
PLOT SCALE =	DRAWN - JN	REVISED -
PLOT DATE = 1/16/2020	CHECKED - JMT	REVISED -

Frames and lids, Type 5,

© Junction Chamber 1

∽639.55

6" 4'-0"

5'-0"

1-11"Ø Opening

Open lid (cast base not used)

-Junction Chamber 1

-Inv. Elev. 639.89

Frames and lids, Type 5,

Open lid (cast base not used)

Inv. Elev. 639.80 -

Elev. 639.00-

Q Junction Chamber 2

3'-0" 4'-6"

8'-0" 9'-0" -T/Weir Elev. 643.00


- Elastomeric Check Valve

12"Ø Storm Sewer

1-11"Ø Opening

Junction Chamber 2

A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
860	2018-055-CR	соок	67	40
-		CONTR	ACT NO. 6	2G92
	ILLINOIS	ED. AID PROJECT		



Accurate

USER NAME = johnn DESIGNED -REVISED DRAWN REVISED CHECKED REVISED PLOT DATE = 12/12/2019 DATE REVISED

BOTTOM PLAN

6-#5 h(E) bars at 12" cts. (Bott.)

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

BAR h12(E)

BAR h14(E)

SCALE:

JUNCTION CHAMBER 1 - DETAILS CHICAGO ROAD OVER THORN CREEK TRIBUTARY SHEETS STA.

NORTH ELEVATION

(Looking South)

COUNTY TOTAL SHEET NO. COOK 67 41 SECTION 2018-055-CR CONTRACT NO. 62G92


box culvert manufacturer.


I.F. = Inside Face


Bott. = Bottom

5.3

980







4X2-#5 h14(E) around opening

1 additional #5 v10(E) bar (I.F.) each side of each opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

1 additional #5 h10(E) bar (I.F.) at top and bottom of opening

WEST ELEVATION (Looking East)

* Trim to fit around opening.


** Dimensions to be verified with the precast concrete box culvert manufacturer.


I.F. = Inside Face Bott. = Bottom

٨	USER NAME = johnn	DESIGNED -	REVISED -
Accurate		DRAWN -	REVISED -
GROUP, INC.	PLOT SCALE = 4:0 ':' / in.	CHECKED -	REVISED -
	PLOT DATE = 12/12/2019	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCALE:






l 🔥									L
A	С		u			t	е		L
		GF	ROUP	, IN	c.				H
								- 1	

STATE OF ILLINOIS	
DEPARTMENT OF TRANSPORTATION	

SCALE:

JUNCTION CHAMBER 2 DETAILS - II CHICAGO HEIGHTS-GLENWOOD RD AT THORN CREEK					F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
					2860	2018-055-CR	соок	67	43		
Cili	CHICAGO HEIGHTS-GLENWOOD RD AT THORN CREEK							CONTRACT	NO.	62G92	
	SHEET	OF	SHEETS	STA.	TO STA.		ILLINOIS FED. AID PROJECT				




DESIGN STRESSES

 $f'c = 3,500 \ psi$


fy = 60,000 psi (Reinforcement)

SCALE:




- Front Face

1½" R



TYPE Z LADDER RUNG PLAN




DETAIL A ELASTOMERIC CHECK VALVE


BILL OF MATERIAL JUNCTION CHAMBER 2

Bar	No.	Size	Length	Shape		
a10(E)	32	#5	9'-10"			
a11(E)	11	#5	8'-8"			
h10(E)	56	#5	9'-8"			
h11(E)	12	#5	8'-8"			
h12(E)	32	#5	4'-2"			
h13(E)	8	#5	2'-0"			
h14(E)	16	#5	5'-0"			
v10(E)	57	#5	5'-8"			
v11(E)	14	#5	5'-3"			
Concrete	Structures		Cu. Yd.	8.5		
Reinforce	ment Bars,	Pound	1740			
Ероху Со	ated	Found	1740			
Frames A	nd Lids, Ty	Each	2			
Open Lid			Lacii	2		

NOTES:


- 1. Reinforcement Bars designated (E) shall be epoxy coated.
- Reinforcement bars shall conform to the requirements of ASTM A706 Gr 60. See Special Provisions.
- 3. The ladder rungs shall be aluminum, conforming to ASTMB361-Alloy 6061-T6 or shall be ductile iron. Aluminum ladder rungs shall receive a heavy coat of bituminous paint or cold applied asphaltic mastic for the portion embedded in concrete. The coating must extend beyond the embedment at least two inches.
- 4. The contractor may submit an alternative ladder rung detail for the Engineer's approval.
- 5. All costs for compacted subbase or CLSM, ladder rungs, and all appurtenances required to complete this work shall be included in the cost of "Concrete Structures".
- 6. Frames and lids, Type 5, Open lid cast base not used.






BAR h12(E)

BAR a10(E)





BAR h14(E)


BAR v11(E)


USER NAME = johnn	DESIGNED -	REVISED -	
	DRAWN -	REVISED -	
PLOT SCALE = 4:0 ':' / in.	CHECKED -	REVISED -	
PLOT DATE = 12/12/2019	DATE -	REVISED -	


STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**


СНІ		NCTION CI			III DRN CREEK
	SHEET	OF	SHEETS	STA.	TO STA.


F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEE1
2860	2018-055-CR	соок	67	44
		CONTRACT	NO.	62G92
	TILLINOIS FED. AT	ID PROJECT		














































DETAIL "A"

LATERAL CONNECTION TO EXISTING SEWER
OF 27" (675) OR SMALLER






<u>DETAIL "B"</u> CLASS SI CONCRETE COLLAR

CONSTRUCTION SEQUENCE

- 1. CUT THE EXISTING END OF THE PIPE SO AS TO PRESENT A FLUSH BUTT JOINT. BRUSH AND CLEAN ALL PIPES.
- 2. APPLY THE MASTIC JOINT SEALANT TO THE FIRST 6" (150) OF EACH PIPE.
- 3. BUTT THE PIPES TOGETHER LEAVING A MINIMUM OF 12' × 6' (300 × 150) DEEP EXCAVATION UNDER AND AROUND EACH PIPE END.
- 4. CUT A PIECE OF SHEET METAL GAGE NO. 19 1.1 (0.0418) 18" (450) WIDE BY THE OUTSIDE CIRCUMFERANCE OF THE PIPE PLUS 3" (75) LONG.
- . WRAP THE SHEET METAL AROUND THE PIPES, 9" (225) ON EACH SIDE OF THE JOINT, STARTING AT THE TOP OF THE PIPE.
- 6. LAP THE SHEET METAL AT LEAST 3" (75) AT THE TOP OF THE PIPE AND PLACE THE MASTIC JOINT SEALANT BETWEEN THE LAP.
- PLACE TWO METAL BANDS AROUND THE SHEET METAL AND TIGHTEN.
- 8. WIPE OFF ANY EXCESS MASTIC JOINT SEALANT THAT OOZES OUT FROM BETWEEN THE SHEET METAL AND THE PIPES.
- 9. PLACE CLASS SI CONCRETE AROUND THE JOINT.



DETAIL "C"

PROPOSED LATERAL
CONNECTION TO EXISTING SEWER
OF 30" (750) OR LARGER

NOTES

MATERIAL

MATERIAL USED FOR THE TEE OR WYE SECTION SHALL BE COMPATIBLE WITH THE EXISTING STORM SEWER OR THE PROPOSED STORM SEWER.

CONSTRUCTION METHODS

- I. THIS WORK SHALL BE CONSTRUCTED IN CONFORMANCE WITH THE APPLICABLE PORTIONS OF SECTION 550 OF THE STANDARD SPECIFICATIONS.
- II. CONNECTION TO AN EXISTING STORM SEWER SHALL BE BY EITHER OF THE FOLLOWING METHODS:

 A) PROPOSED STORM SEWER CONNECTION TO EXISTING SEWER OF 27" (675) OR SMALLER SEE
 - B) PROPOSED STORM SEWER CONNECTION TO EXISTING SEWER OF 30" (750) OR LARGER SEE DETAIL "C".

IF THE EXISTING SEWER PIPE IS CRACKED, BROKEN OR OTHERWISE DAMAGED BY THE CONTRACTOR IN MAKING THE CIRCULAR OPENING, THE CONTRACTOR SHALL REPLACE THAT SECTION OF PIPE WITH PIPE EQUAL AND SIMILAR IN ALL RESPECTS TO THE PIPE IN THE EXISTING SEWER, IN A CAREFUL WORKMANLIKE MANNER, WITHOUT EXTRA COMPENSATION.

GENERAL

CARE MUST BE TAKEN TO PREVENT DEBRIS FROM ENTERING THE SEWER. ALL DEBRIS WHICH ENTERS THE SEWER MUST BE REMOVED. THE SEWER MUST BE LEFT CLEAN AND UNOBSTRUCTED UPON COMPLETION OF THE CONTRACT.

CARE MUST BE TAKEN TO PREVENT ANY PART OF THE NEW PIPE CONNECTION FROM PROJECTING INTO THE EXISTING SEWER.

BASIS OF PAYMENT

TEE OR WYE CONNECTIONS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR STORM SEWER TEE OR WYE OF THE TYPE AND SIZE SPECIFIED IN THE PLANS, THIS PRICE SHALL INCLUDE ALL EXCAVATION OF THE TRENCH, REMOVAL OF THE EXISTING STORM SEWER, FURNISHING AND INSTALLING THE SPECIFIED TEE OR WYE SECTION, FURNISHING AND INSTALLING THE REQUIRED CONCRETE COLLAR, AND ALL OTHER MATERIAL NECESSARY TO COMPLETE THIS WORK AS SHOWN AND SPECIFIED.


REMOVAL AND REINSTALLATION OF EXISTING STORM SEWER ADJACENT TO THE PROPOSED TEE OR WYE SECTION, FOR THE PURPOSE OF FACILITATING THE INSTALLATION OF THE TEE OR WYE SECTION, WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE UNIT PRICE BID FOR THE WORK.

TRENCH BACKFILL, EXCAVATION IN ROCK AND REMOVAL AND REPLACEMENT OF UNSUITABLE MATERIAL BELOW PLAN BEDDING GRADE WILL BE PAID FOR SEPARATELY.

CONCRETE COLLAR FOR CONNECTING A PROPOSED STORM SEWER TO AN EXISTING STORM SEWER WILL NOT BE PAID PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF THE PROPOSED STORM SEWER.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.


FILE NAME =	USER NAME = gaglianobt	DESIGNED - M. DE YONG	REVISED - M. DE YONG 05-08-92		DETAIL OF STORM SEWER	F.A.U. SECTION	COUNTY TOTAL SHEET NO.
W:\diststd\22x34\bdØ7.dgn		DRAWN -	REVISED - R. SHAH 09-09-94	STATE OF ILLINOIS		2860 2018 - 055 - CR	COOK 67 60
	PLOT SCALE = 50.000 '/ IN.	CHECKED -	REVISED - R. SHAH 10-25-94	DEPARTMENT OF TRANSPORTATION	CONNECTION TO EXISTING SEWER	BD500-01 (BD-7)	CONTRACT NO. 62G92
	PLOT DATE = 1/4/2008	DATE - 07-25-90	REVISED - R. SHAH 06-12-96		SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED.	AID PROJECT



CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT

ALL DIMENSIONS ARE UNLESS (MILLIMETERS)
UNLESS OTHERWISE SHOW

c NAME =	USER NAME = drivakosgn	DESIGNED - A. HOUSEH	REVISED - R. SHAH 10-			CURB OR CURB ANI	CUTTER	F.A.U.	SECTION	COUN	TOTAL SHEET
c:\pw_work\pwidot\drivakosgn\d0108315\bd2	4.dgn	DRAWN -	REVISED - A. ABBAS 03	STATE OF ILLINOIS				2860	2018 - 055 - CR	соок	61
	PLOT SCALE = 50.000 ' / IN.	CHECKED -	REVISED - M. GOMEZ 01	DEPARTMENT OF TRANSPORTATION		REMOVAL AND REPL	ACEMENT		BD600-06 (BD-24)	CONTRACT	No. 2
	PLOT DATE = 12/15/2009	DATE - 03-11-94	REVISED - R. BORO 12-		SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA. TO STA.	FED. RO	DAD DIST. NO. 1 ILLINOIS FED.	AID PROJECT	



NOTES:

- SIDE ROAD WITH A SPEED LIMIT OF 40 MPH (60 km/h) OR LESS AS SHOWN ON THE DRAWING AND AS DIRECTED BY THE ENGINEER:
 - a) ONE "ROAD CONSTRUCTION AHEAD" SIGN 36 x 36 (900x900) WITH A FLASHER MOUNTED ON IT APPROXIMATELY 200" (60 m) IN ADVANCE OF THE MAIN ROUTE.
 - b) THE CLOSED PORTION OF THE MAIN ROUTE SHALL BE PROTECTED BY BLOCKING WITH TYPE I, TYPE II OR TYPE III BARRICADES, 1/3 OF THE CROSS SECTION OF THE CLOSED PORTION.
- 2. SIDE ROAD WITH A SPEED LIMIT GREATER THAN 40 MPH (60 km/h) AS SHOWN ON THE DRAWING AND AS DIRECTED BY THE ENGINEER:
 - a) ONE "ROAD CONSTRUCTION AHEAD" SIGN 48 x 48 (1.2 m x 1.2 m) WITH A FLASHER MOUNTED ON IT APPROXIMATELY 500" (150 m) IN ADVANCE OF THE MAIN ROUTE.
 - b) THE CLOSED PORTION OF THE MAIN ROUTE SHALL BE PROTECTED BY BLOCKING WITH TYPE III BARRICADES, 1/2 OF THE CROSS SECTION OF THE CLOSED PORTION.
- 3. CONES MAY BE SUBSTITUTED FOR BARRICADES OR DRUMS AT HALF THE SPACING DURING DAY OPERATIONS. CONES SHALL BE A MINIMUM OF 28 (710) IN HEICHT
- 4. WHEN THE SIDE ROAD LIES BETWEEN THE BEGINNING OF THE MAINLINE SIGNING AND THE WORK ZONE, A SINGLE HEADED ARROW (M6-1) SHALL BE USED IN LIEU OF THE DOUBLE HEADED ARROW (M6-4).

SCALE: NONE


- 5. WHEN WORK IS BEING PERFORMED ON A SIDE ROAD OR DRIVEWAY, FOLLOW THE APPLICABLE STANDARD(S). THE DIRECTIONAL ARROW (M6-1 OR M6-4) SHALL BE COVERED OR REMOVED WHEN NO LONGER CONSISTENT WITH THE TRAFFIC CONTROL SET-UP.
- 6. ADVANCE WARNING SIGNS ARE TO BE OMITTED ON DRIVEWAYS UNLESS OTHERWISE SPECIFIED IN THE PLANS OR BY THE ENGINEER.
- 7. THE TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS SHALL BE INCLUDED IN THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.

All dimensions are in inches (millimeters) unless otherwise shown.

FILE NAME =	USER NAME = footemj	DESIGNED - L.H.A.	REVISED	- A. HOUSEH 10-15-96
pw:\\ILØ84EBIDINTEG.ıllınoıs.gov:PWIDOT\Do	cuments\IDOT Offices\District 1\Projects\Dist	St 0R2WM \CADData\CADsheets\tc10.dgn	REVISED	-T. RAMMACHER 01-06-00
	PLOT SCALE = 50.000 '/ in.	CHECKED -	REVISED	- A. SCHUETZE 07-01-13
Default	PLOT DATE = 9/15/2016	DATE - 06-89	REVISED	 A. SCHUETZE 09-15-16


STATI	E OI	ILLINOIS
DEPARTMENT	0F	TRANSPORTATION


	TRAFFIC (CONTROL	AND PI	ROTECT	ION FOR	F.A.U. RTE.	SECTION
ÇII	DE BUYDS	INITERS	ECTIONS	VMD I	DRIVEWAYS	2860	2018 - 055 - CR
311	DE HOADS	, INTLIIS	LUTIUNS,	AIND	DIIIVEVVAIS		TC-10
	SHEET 1	OF 1	SHEETS	STA.	TO STA.		ILL INOIS




*** REDUCE TO 40' (12 m) O.C. ON CURVES WITH POSTED OR ADVISORY SPEED 45 M.P.H. (70 km/h) OR LESS.

TWO-LANE/TWO-WAY






TWO-WAY LEFT TURN



MULTI-LANE/UNDIVIDED



MULTI-LANE/DIVIDED

GENERAL NOTES

- MARKERS USED WITH DASHED LINES SHALL BE CENTERED IN THE GAP BETWEEN SEGMENTS.
- 2. MARKERS USED ADJACENT TO SOLID LINES SHALL BE OFFSET 2 TO 3 (50 TO 75) TOWARD TRAFFIC AS SHOWN.
- 3. MARKERS THROUGH TANGENTS LESS THAN 500' (150 m) IN LENGTH BETWEEN CURVES SHALL BE INSTALLED AT THE LESSER OF THE TWO CURVE SPACINGS.

LANE MARKER NOTES

A. USE DOUBLE LANE LINE MARKERS SPACED AS SHOWN.

B. REDUCE TO 40' (12 m) O.C. ON CURVES WHERE ADVISORY SPEEDS ARE 10 M.P.H (20 km/h) LOWER THAN POSTED SPEEDS.

SYMBOLS

---- YELLOW STRIPE

── WHITE STRIPE

- ONE-WAY AMBER MARKER
- ONE-WAY CRYSTAL MARKER (₩/0)
- ◆ TWO-WAY AMBER MARKER


DESIGN NOTES

- 1. DOUBLE LANE LINE MARKERS SHALL BE USED UNLESS SPECIFIED OTHERWISE.
- 2. EXCEPT AS SHOWN ON THE LANE REDUCTION TRANSITION AND FREEWAY EXIT RAMP DETAIL, MARKERS ARE NOT TO BE SPECIFIED ON RIGHT EDGE LINES.
- 3. THE EXACT MARKER LIMITS, SPACING, AND COLOR SHALL BE INCLUDED IN THE PLANS WHEN STANDARD SPECIFICATIONS ARE NOT BEING USED.
- 4. MARKERS SHOULD NOT BE USED ALONGSIDE CURBS EXCEPT FOR EXTREMELY SHORT SECTIONS OF CURBS WHERE NOT MORE THAN TWO MARKERS WOULD BE

LEFT TURN

All dimensions are in inches (millimeters) unless otherwise shown.

FILE NAME =	USER NAME = leyso	DESIGNED -	REVISED - T. RAMMACHER 09-19-94		TYPICAL APPLICATIONS	F.A.U.	SECTION	COUNTY	SHEETS	SHEET
c:\pw_work\pwidot\leysa\d0108315\tc11.dgr		DRAWN -	REVISED -T. RAMMACHER 03-12-99	STATE OF ILLINOIS		2860	2018 - 055 - CR	соок	67	63
	PLOT SCALE = 50.000 '/ IN.	CHECKED -	REVISED -T. RAMMACHER 01-06-00	DEPARTMENT OF TRANSPORTATION	RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)	2000	TC-11	CONTRAC	T NO. 62	.G92
	PLOT DATE = 3/2/2011	DATE -	REVISED - C. JUCIUS 09-09-09		SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.	FED. RO	DAD DIST. NO. 1 ILLINOIS F	FED. AID PROJECT		



2' (600)

DETAIL "B"

DRAWN

DATE

CHECKED

12 (300) WHITE

DESIGNED - EVERS

03-19-90

REVISED -

REVISED -

REVISED

- 6 (150) WHITE

TYPICAL CROSSWALK MARKING

MARKINGS SHALL BE INSTALLED PARALLEL TO THE CENTERLINE OF


DETAIL "A"


USER NAME = leysa

PLOT DATE = 6/23/2017

8 (200) WHITE-

12 (300) WHITE DIAGONALS @ 10' (3 m) OR LESS SPACING ISLAND OFFSET FROM PAVEMENT EDGE






LEFT AND U-TURN

5'-4" (1620)

√ 32 R (810)

U-TURN



D(FT)

425

SPEED LIMIT

45

50

55

LANE REDUCTION TRANSITION

* LANE REDUCTION ARROWS REQUIRED AT SPEEDS OF 45 MPH OR GREATER OR WHEN SPECIFIED IN PLANS.

TYPE OF MARKING	WIDTH OF LINE	PATTERN	COLOR	SPACING /REMARKS
CENTERLINE ON 2 LANE PAVEMENT	4 (100)	SKIP-DASH	YELLOW	10' (3 m) LINE WITH 30' (9 m) SPACE
CENTERLINE ON MULTI-LANE UNDIVIDED PAVEMENT	2 @ 4 (100)	SOLID	YELLOW	11 (280) C-C
NO PASSING ZONE LINES: FOR ONE DIRECTION FOR BOTH DIRECTIONS	4 (100) 2 0 4 (100)	SOLID SOLID	YELLOW YELLOW	5½ (140) C-C FROM SKIP-DASH CENTERLINE 11 (280) C-C OMIT SKIP-DASH CENTERLINE BETWEEN
LANE LINES	4 (100) 5 (125) ON FREEWAYS	SKIP-DASH SKIP-DASH	WHITE WHITE	10' (3 m) LINE WITH 30' (9 m) SPACE
DOTTED LINES (EXTENSIONS OF CENTER, LANE OR TURN LANE MARKINGS)	SAME AS LINE BEING EXTENDED	SKIP-DASH	SAME AS LINE BEING EXTENDED	2' (600) LINE WITH 6' (1.8 m) SPACE
EDGE LINES	4 (100)	SOLID	YELLOW-LEFT WHITE-RIGHT	OUTLINE MEDIANS IN YELLOW
TURN LANE MARKINGS	6 (150) LINE; FULL SIZE LETTERS & SYMBOLS (8' (2.4m))	SOLID	WHITE	SEE TYPICAL TURN LANE MARKING DETAIL
TWO WAY LEFT TURN MARKING	2 @ 4 (100) EACH DIRECTION 8' (2.4m) LEFT ARROW	SKIP-DASH AND SOLID IN PAIRS	YELLOW	10' (3 m) LINE WITH 30' (9 m) SPACE FOR SKIP-DASH; 5½ (140) C-C BETWEEN SOLID LINE AND SKIP-DASH LINE SEE TYPICAL TWO-WAY LEFT TURN MARKING DETAIL
CROSSWALK LINES (PEDESTRIAN) A. DIAGONALS (BIKE & EQUESTRIAN) B. LONGITUDINAL BARS (SCHOOL)	2 @ 6 (150) 12 (300) @ 45° 12 (300) @ 90°	SOLID SOLID SOLID	WHITE WHITE WHITE	NOT LESS THAN 6' (1.8 m) APART 2' (600) APART 2' (600) APART 3' (600) APART SEE TYPICAL CROSSWALK MARKING DETAILS.
STOP LINES	24 (600)	SOLID	WHITE	PLACE 4' (1.2 m) IN ADVANCE OF AND PARALLEL TO CROSSWALK, IF PRESENT. OTHERWISE, PLACE AT DESIRED STOPPING POINT. PARALLEL TO CROSSROAD CENTERLINE, WHERE POSSIBLE
PAINTED MEDIANS	2 @ 4 (100) WITH 12 (300) DIAGONALS @ 45° NO DIAGONALS USED FOR 4' (1.2 m) WIDE MEDIANS	SOLID	YELLOW: TWO WAY TRAFFIC WHITE: ONE WAY TRAFFIC	II (280) C-C FOR THE DOUBLE LINE SEE TYPICAL PAINTED MEDIAN MARKING.
GORE MARKING AND CHANNELIZING LINES	8 (200) WITH 12 (300) DIAGONALS @ 45°	SOLID	WHITE	DIACONALS: 15' (4,5 m) C-C (LESS THAN 30MPH (50 km/h)) 20' (6 m) C-C 30MPH (50 km/h) TO 45MPH (70 km/h)) 30' (9 m) C-C (0VER 45MPH (70 km/h))
RAILROAD CROSSING	24 (600) TRANSVERSE LINES; "RR" IS 6' (1.8 m) LETTERS; 16 (400) LINE FOR "X"	SOLID	WHITE	SEE STATE STANDARD 780001 AREA OF: "R"=3.6 SO. FT. (0.33 m²) EACH "X"=54.0 SO. FT. (5.0 m²)
SHOULDER DIAGONALS (REQUIRED FOR SHOULDERS > 8')	12 (300) @ 45°	SOLID	WHITE - RIGHT YELLOW - LEFT	50' (15 m) C-C (LESS THAN 30MPH (50 km/h)) 75' (25 m) C-C (30 MPH (50 km/h) TO 45MPH (70 km/h) 150' (45 m) C-C (OVER 45MPH (70 km/h))
U TURN ARROW	SEE DETAIL	SOLID	WHITE	16.3 SF
2 ARROW COMBINATION LEFT AND U TURN	SEE DETAIL	SOLID	WHITE	30.4 SF

FOR FURTHER DETAILS ON PAVEMENT MARKING REFER TO STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND STATE STANDARD 780001.

SCALE: NONE

All dimensions are in inches (millimeters) unless otherwise shown.

C. JUCIUS 09-09-0 C. JUCIUS 07-01-13 C. JUCIUS 12-21-15 C. JUCTUS 04-12-16

AREA = 15.6 SO. FT. (1.5 m²) (1.5 m²) * TURN LANES IN EXCESS OF 400' (120 m) IN LENGTH MAY HAVE AN ADDITIONAL SET OF ARROW - "ONLY" INSTALLED MIDWAY BETWEEN THE OTHER TWO SETS OF

TYPICAL LEFT (OR RIGHT) TURN LANE


TYPICAL TURN LANE MARKING


STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

DISTRICT ONE			F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
TYPICAL PAVEMENT MARKINGS				2860	2018 - 055 - CR	COOK	67	64		
		IUAL I A	VLIVILIAI	WAIKINGS	,		TC-13	CONTRACT	NO. 62	G92
	SHEET 1	OF 1	SHEETS	STA	TO STA		THE IMORE FED.	ID DDO IECT		

FILE NAME =

W:\diststd\22x34\tc13.dar






NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN () WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

l	FILE NAME =	USER NAME = gaglianobt	DESIGNED -	REVISED - R. MIRS 09-15-97			ARTERIAL ROAD		F.A.U. RTF.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	W:\diststd\22x34\tc22.dgn		DRAWN -	REVISED - R. MIRS 12-11-97	STATE OF ILLINOIS		INFORMATION SIGN		2860	2018 - 055 - CR	соок	67	
		PLOT SCALE = 50.000 '/ IN.	CHECKED -	REVISED -T. RAMMACHER 02-02-99	DEPARTMENT OF TRANSPORTATION		INFURMATION SIGN			TC-22	CONTRACT	NO. 620	.G92
		PLOT DATE = 1/4/2008	DATE -	REVISED - C. JUCIUS 01-31-07		SCALE: NONE	SHEET NO. 1 OF 1 SHEETS STA.	TO STA.	FED. RO		D PROJECT		



3.0" RADIUS, 0.5" BORDER, WHITE ON GREEN; REFLECTORIZED "DRIVEWAY" D; "ENTRANCE" D; STANDARD ARROW CUSTOM 12.0" x 5.0"

NOTES:

- 1. HALF OF THE SIGNS WILL REQUIRE A LEFT HAND FACING ARROW.
- 2. TWO SIGNS SHALL BE USED AT EACH COMMERCIAL ENTRANCE PLACED BACK-TO-BACK: ONE WITH A RIGHT HAND ARROW (SHOWN) SHALL BE PLACED ON THE NEAR RIGHT SIDE THE DRIVEWAY AND ONE WITH A LEFT HAND ARROW SHALL BE PLACED ON THE FAR LEFT SIDE OF THE DRIVEWAY.
- 3. SIGNS TO BE PAID FOR AS ITEM "TEMPORARY INFORMATION SIGNING".

FILE NAME =	USER NAME = gaglianobt	DESIGNED -	REVISED - C. JUCIUS 02-15-07
c:\pw_work\pwidot\gaglianobt\d01083!5\tc	26.dgn	DRAWN -	REVISED -
	PLOT SCALE = 50.000 '/ in.	CHECKED -	REVISED -
	PLOT DATE = 12/13/2012	DATE -	REVISED -

STATE 0	F ILLINOIS
DEPARTMENT OF	TRANSPORTATION

	DRIVEWAY ENTRANCE SIGNING						F.AU. SECTION		TOTAL SHEETS	SHEET NO.
							2018 - 055 - CR	COOK	67	67
							TC-26	CONTRACT	NO. 62	G92
SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA. FED. ROAD DIST. NO.							AD DIST. NO. 1 ILLINOIS FED. A	ID PROJECT		