



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 27, 2020

SUBJECT: FAI Route 55 (I-55)
Project NHPP-MAMH(434)
Section (68-1,3 RS-3, 68-2 RS-5) BR
Montgomery County County
Contract No. 72D31
Item No. 127, March 6, 2020 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page i of the Table of Contents to the Special Provisions.
3. Revised pages 17 and 18 of the Special Provisions.
4. Revised sheets 1, 11, 16, 17, 20, 32, and 278-307 of the Plans.
5. Added sheet 217A to the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	2
STATUS OF UTILITIES TO BE ADJUSTED	4
TRAFFIC CONTROL PLAN	8
DETOUR SIGNING.....	19
MEDIAN CLOSURE.....	20
ROAD CLOSURE	21
USE OF SUB-BASE GRANULAR MATERIAL TO ELIMINATE EXPOSURE OF EXCESS DROP OFFS.....	22
REAL-TIME TRAFFIC CONTROL SYSTEM	22
SMART TRAFFIC MONITORING SYSTEM.....	25
BASE COURSE (OPTION)	27
BOX CULVERT TO BE CLEANED	27
CLEANING BRIDGE SEATS	28
CLEANING UNDERDRAIN OUTLETS.....	29
CONCRETE CURB REPAIR.....	29
CONCRETE MEDIAN SURFACE REMOVAL.....	30
CONCRETE MEDIAN, TYPE SM (DOWELLED)	30
CONTRACTOR ACCESS	30
CULVERT STATION 1625+75.....	31
CULVERT STATION 70+40.....	31
DRAINAGE STRUCTURE TO BE REMOVED	31
EMBANKMENT.....	32
HOT-MIX ASPHALT SHOULDER REMOVAL AND REPLACEMENT (SPECIAL).....	33
LITCHFIELD WEIGH STATION – MAINLINE WEIGH-IN-MOTION (WIM) SENSOR AND WIM ELECTRONICS UPGRADE	34
MEDIAN SURFACE REMOVAL.....	40
PAVEMENT REMOVAL (SPECIAL).....	41
OUTLET MARKER	41
PAVEMENT STATIONING NUMBERS AND PLACEMENT	42
PIPE CULVERT TO BE CLEANED	42

Revised 2/27/2020

TRAFFIC CONTROL AND PROTECTION, STANDARD 701427

Traffic Control and Protection, Standard 701427 shall be used for moving or intermittent operations on a multilane facility. This work may include, but not necessarily be limited to, landscaping, pavement marking and utility operations. This standard will not be measured for payment in accordance with Article 701.19(a) of the Standard Specifications.

TRAFFIC CONTROL AND PROTECTION, STANDARD 701428

Traffic Control and Protection, Standard 701428 shall be used for setup and removal of lane closures on freeways/expressways having ADT greater than 25,000. This standard will not be measured for payment in accordance with Article 701.19(a) of the Standard Specifications.

TRAFFIC CONTROL AND PROTECTION, STANDARD 701451

Traffic Control and Protection, Standard 701451 shall be used for the temporary closure of any ramp adjacent to I-55 when connections require the full closure of a ramp. TRAFFIC CONTROL AND PROTECTION 701451 will be measured for and paid for at the contract unit price per LUMP SUM for TRAFFIC CONTROL AND PROTECTION, STANDARD 701451.

TRAFFIC CONTROL AND PROTECTION, STANDARD 701456

Traffic Control and Protection, Standard 701456 shall be used for work on exit ramps adjacent to I-55 when a partial ramp closure encroaches on a lane of traffic. TRAFFIC CONTROL AND PROTECTION 701456 will be measured for and paid for at the contract unit price per LUMP SUM for TRAFFIC CONTROL AND PROTECTION, STANDARD 701456.

TRAFFIC CONTROL AND PROTECTION, STANDARD 701701

Traffic Control and Protection, Standard 701701 shall be used along IL 108 at the intersections of the Frontage Road and Ramps. TRAFFIC CONTROL AND PROTECTION 701701 will be measured for and paid for at the contract unit price per LUMP SUM for TRAFFIC CONTROL AND PROTECTION, STANDARD 701701.

TRAFFIC CONTROL AND PROTECTION, STANDARD 701901

Traffic Control and Protection, Standard 701901 includes the traffic control device details.

TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21

Traffic Control and Protection, Standard BLR 21 shall be used for Road Closure during construction operations on CH 24. TRAFFIC CONTROL AND PROTECTION BLR 21 will be measured for and paid for at the contract unit price per LUMP SUM for TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21.

This page intentionally left blank.