



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 21, 2020

SUBJECT: Route FAU 9835 (Elm Street)  
Section 18-00045-00-RS (Greenville)  
Bond County  
Contract No. 97720  
Item 164  
March 6, 2020 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

### **1. Revised page 6 of the special provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

### LONGITUDINAL JOINT SEALANT

This work shall conform to Article 406 of the Standard Specifications for Road and Bridge Construction, as well as Special Provision 80398 of the Special Provisions. A single layer Joint Sealant shall be placed between the Binder Course and Surface Course. Width of the Sealant shall be 18" centered within 2"+/- of the joint. The Longitudinal Joint Sealant (LJS) shall be placed at an application rate of 1.47 lb/foot.

This work shall be paid for by the contract unit price per FOOT for LONGITUDINAL JOINT SEALANT.

### TEMPORARY PAVEMENT MARKING REMOVAL

This work shall conform to Article 703 of the Standard Specifications for Road and Bridge Construction. All Temporary Pavement Marking to be placed shall be removed prior to placement of the permanent pavement marking.

This work shall be paid for by the contract unit price per SQUARE FOOT for TEMPORARY PAVEMENT MARKING REMOVAL.