



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 25, 2020

SUBJECT: MS 1114 (W. Epperson Road)
Section 15-00253-00-BR
Bureau County
Contract No. 87719
Item 173
March 6, 2020 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised Index of Special Provisions**
- 2. Revised page 8 of the Special Provisions**
- 3. Revised sheet 2 of the Plans**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

INDEX OF SPECIAL PROVISIONS

| | |
|--|-------|
| LOCATION OF PROJECT | 1 |
| DESCRIPTION OF WORK | 1 |
| PUBLIC SERVICES NOTIFICATION | 1 |
| PRECAUTIONS FOR UTILITIES | 1 |
| DEPARTMENT OF THE ARMY COPRS OF ENGINEERS PERMIT | 1 |
| HOT-MIX ASPHALT BINDER COURSE, IL-19.0L, N30 | 2 |
| HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N30 | 2 |
| EARTH EXCAVATION (SPECIAL)..... | 2 |
| POROUS GRANULAR EMBANKMENT, SPECIAL..... | 2 |
| SEEDING, CLASS 3 (SPECIAL)..... | 2-3 |
| STONE RIPRAP, CLASS A4 (SPECIAL) | 3 |
| STONE RIPRAP, CLASS A5 (SPECIAL) | 3 |
| TRAFFIC CONTROL AND PROTECTION (SPECIAL)..... | 4-7 |
| STONE RIPRAP, CLASS A1 (SPECIAL) | 8 |
| TREE REMOVAL (6 TO 15 UNITS DIAMETER) | 8 |
| STATUS OF UTILITIES..... | 9-10 |
| ARMY CORPS PERMIT..... | 11-56 |
| LR 107-4 INSURANCE..... | 57 |
| LR 702 CONSTRUCTION MAINTAINANCE SIGNS | 58 |
| LR 1030 GROWTH CURVE..... | 59-60 |

Bureau County

Bureau

15-00253-00-BR

STONE RIPRAP, CLASS A1 (SPECIAL)

This item shall be in accordance with the applicable portions of Section 281 of the Standard Specifications for Road and Bridge Construction and as specified herein. This item shall consist of riprap placed beneath the precast culvert sections and cast-in-place apron as shown in the plans or as directed by the Engineer.

The filter fabric shall be omitted and not installed as part of the construction/installion of the riprap.

This work will be paid for at the contract unit price per TON for STONE RIPRAP, CLASS A1 1(SPECIAL).

TREE REMOVAL (6 TO 15 UNITS DIAMETER)

This work shall be done in accordance with all applicable portions of Section 201 of the Standard Specifications and the following.

The City of Princeton and Bureau County are within the known breeding range of the federally endangered Indiana bat (*Myotis sodalis*) and the threatened Northern long-eared Bat (*Myotis septentrionalis*). The Department of the Interior, U.S. Fish and Wildlife Service has made a determination of no impact on federally threatened and endangered species provided all tree clearing activities occur outside the bat's breeding season which extends from April 1 to September 30.

The City of Princeton will initiate tree removal prior to construction to comply with the requirements for tree removal. This removal action will consist of "dropping or felling" and removing the habitat suitable portion of the tree.

The Contractor shall remove the remaining stumps, felled trees and any remaining debris.

This work will be paid for at the contract unit price per unit for TREE REMOVAL (6 TO 15 UNITS DIAMETER).

"Revised 2/24/20"