



KEY NOTES:

- 1 EC TO SPLICE EXISTING CONDUCTORS TO ACCOMMODATE NEW LIGHTING CIRCUIT INDICATED ON PLAN. REMOVE OLD CIRCUITING LABEL ON POLE. PROVIDE A NEW LABEL SHOWING ALL NEW POLE INFORMATION.
- 2 EXISTING UNIT DUCT OR CONDUIT TO REMAIN.
- 3 EC TO CUT EXISTING UNIT DUCT 5' FROM EXISTING POLE. PULL BACK ALL CONDUCTORS BACK TO LAST EXISTING POLE TO REMAIN AND ABANDON UNIT DUCT IN PLACE.
- 4 WIRE EXISTING LIGHTS WITH NEW 1-1/2" UNIT DUCT WITH (3)*2 & (1)*4 GROUND.
- 5 EC TO RESPLICE CONDUCTORS TO RE-CIRCUIT EXISTING LIGHT POLE WITH NEW (3)*2 & (1)*4 GROUND. EXISTING CONDUCTORS IN EXISTING POLES ARE (3)*4 & (1)*6 GROUND. REMOVE EXISTING CONDUCTORS & PROVIDE NEW 1-1/2" UNIT DUCT TO ACCOMMODATE NEW WIRING.
- 6 REMOVE OLD CIRCUITING LABEL AND PROVIDE A NEW LABEL SHOWING ALL NEW POLE INFORMATION.

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL 394 SAFETY IMPROVEMENTS – GOODNOW ROAD TO BURRVILLE ROAD
LIGHTING PLAN**

F.A.P. RTE. 332	SECTION 2007-044 I	COUNTY WILL & COOK	TOTAL SHEETS 53	SHEET NO. 36
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60D34	

GRANT ANHALT SCHLOEMER
and Associates Inc.
One Honey Creek Corporate Center
125 South Ben Street, Suite 401
Wilmington, WI 53140
414 251-1300
414 251-1303
Web Site: www.gasol.com

USER NAME = #USER#	DESIGNED - BDB/CMP	REVISED -
PLOT SCALE = #SCALE#	DRAWN - JCC	REVISED -
PLOT DATE = 12/28/2007	CHECKED - BDB	REVISED -
	DATE - 12-31-07	REVISED -

SCALE: 1" = 50' SHEET NO. 6 OF 22 SHEETS STA. 2090+00 TO STA. 2118+00

L:\Jobs\2006\20063028-39\CAD\Electrical\adgn\00\E15.dwg 12/28/2007 10:28:19 AM

