

INDEX OF SHEETS

- 1 COVER PAGE
- 2 INDEX OF SHEETS, GENERAL NOTES, STATE STANDARDS
- 3 SUMMARY OF QUANTITIES
- 4-5 TRAFFIC STAGING PLANS
- 6 PAVEMENT MARKING PLAN
- 7-12 BRIDGE PLANS (SN 016-0518)
- 13-14 NB LAGRANGE RD DETOUR PLAN

LIST OF STATE STANDARDS

- 701301-02 LANE CLOSURE 2L, 2W, SHORT TIME OPERATIONS
- 701601-05 URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
- 701901 TRAFFIC CONTROL DEVICES
- 704001-04 TEMPORARY CONCRETE BARRIER

INDEX OF SHEETS

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. 48 HOUR NOTIFICATION IS REQUIRED.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FOR THE DEPARTMENT.

ALL DAMAGE TO EXISTING PAVEMENT MARKINGS OR RAISED REFLECTIVE PAVEMENT MARKERS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT NO COST TO THE DEPARTMENT

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE CONTRACTOR SHALL CONTACT PATRICE HARRIS AT (708) 597-9800 TWO (2) WEEKS PRIOR TO PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS

CONCRETE SUPERSTRUCTURE SHALL HAVE A SEVEN DAY MINIMUM CURE.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE NOTIFICATION OF ALL EMERGENCY SERVICES, SCHOOL DISTRICTS, I.D.O.'S COMMUNICATIONS CENTER, SPRINGFIELD TRUCK PERMIT SECTION AND OTHER AGENCIES AFFECTED BY THE CLOSURE. THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR POSTING SIGNS THAT WILL INDICATE THE DATES THE CLOSURE WILL BE IN PLACE.

THE CONTRACTOR SHALL CONTACT DISTRICT ONE TRAFFIC AT (847) 705-4424 ONE WEEK PRIOR TO IMPLEMENTING THE DETOUR SO TRAFFIC SIGNAL TIMINGS CAN BE ADJUSTED.

THE CONTRACTOR SHALL SALVAGE AND RETURN THE "TEMPORARY CONCRETE BARRIER (STATE OWNED)" (230 FT) AND THE "TEMPORARY IMPACT ATTENUATORS (STATE OWNED)" (1 EACH) TO:

DISTRICT BRIDGE OFFICE
1101 BIESTERFIELD RD
ELK GROVE VILLAGE, IL 60007

THIS WORK SHALL INCLUDE REMOVING, TRANSPORTING, AND UNLOADING THE ABOVE ITEMS TO THE BIESTERFIELD YARD WHICH COST IS INCLUDED IN THE COST OF "RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)."

FILE NAME = c:\projects\dl03708\design_aa.dgn	USER NAME = anseris	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, GENERAL NOTES AND STATE STANDARDS				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -		330	BR-H6-1-2	COOK	14	2				
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -						CONTRACT NO. 60D53				
	PLOT DATE = 12/28/2007	DATE -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT		