

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	BR-H6-1-2	COOK	14	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT 60D53

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE SFTY-2A				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES 100% STATE	016-0518			
50102400	CONCRETE REMOVAL	CU YD	22.8	22.8			
50157310	PROTECTIVE SHIELD	SQ FT	432	432			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	22.8	22.8			
50300300	PROTECTIVE COAT	SQ YD	63.3	63.3			
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	11050	11050			
50500505	STUD SHEAR CONNECTORS	EACH	76	76			
50501110	STRUCTURAL STEEL REMOVAL	POUND	11050	11050			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3050	3050			
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	67	67			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2			
67100100	MOBILIZATION	L-SUM	1	1			
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1			
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	125	125			
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	230	230			
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	375	375			
78300105	PAVEMENT MARKING REMOVAL	FOOT	1500	1500			
X0321781	MECHANICAL SPLICE	EACH	226	226			
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48	48			
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1			

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES					

12/28/2007 08:00:00 AM

\* SPECIALTY ITEMS

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

PLOT DATE: 12/28/2007