

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2320	113X-N	WILL	133	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
62910				

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN ILL-113 & ILL-129 & ILL-53 STATE 100%	URBAN TRAFFIC SIG. ILL-113 & ILL-129 & ILL-53 STATE 100%	URBAN PRE-EMPTION ILL-113 & ILL-129 & ILL-53 CITY 100%	URBAN LIGHTING ILL-113 & ILL-129 & ILL-53 CITY 100%	URBAN SIDEWALK ILL-113 & ILL-129 & ILL-53 STATE 50% CITY 50%	URBAN WATERMAIN ILL-113 & ILL-129 & ILL-53 CITY 100%
				1000-2A	Y031-1F	Y031-3D	Y030-1#	SFTY-1B	Y060
44000100	PAVEMENT REMOVAL	SQ YD	10302	10302					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	5647	5647					
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	160	160					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1574	1574					
44000300	CURB REMOVAL	FOOT	270	135					135
44000600	SIDEWALK REMOVAL	SQ FT	5075	5075					
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	283	283					
44004250	PAVED SHOULDER REMOVAL	SQ YD	306	306					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	170	170					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	113	113					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	86	68					18
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1103	1103					
50105220	PIPE CULVERT REMOVAL	FOOT	380	380					
54207153	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18"	FOOT	124.5	124.5					
54207165	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 30"	FOOT	250	250					
54207177	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 42"	FOOT	62	62					
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3	3					
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1					
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	4	4					
54214713	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18"	EACH	1	1					
54214725	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 30"	EACH	4	4					
54214737	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 42"	EACH	2	2					

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN ILL-113 & ILL-129 & ILL-53 STATE 100%	URBAN TRAFFIC SIG. ILL-113 & ILL-129 & ILL-53 STATE 100%	URBAN PRE-EMPTION ILL-113 & ILL-129 & ILL-53 CITY 100%	URBAN LIGHTING ILL-113 & ILL-129 & ILL-53 CITY 100%	URBAN SIDEWALK ILL-113 & ILL-129 & ILL-53 STATE 50% CITY 50%	URBAN WATERMAIN ILL-113 & ILL-129 & ILL-53 CITY 100%
				1000-2A	Y031-1F	Y031-3D	Y030-1#	SFTY-1B	Y060
54247110	GRATING FOR CONCRETE FLARED END SECTION 18"	EACH	3	3					
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1					
54247180	GRATING FOR CONCRETE FLARED END SECTION 42"	EACH	4	4					
54248110	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 18"	EACH	1	1					
54248150	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 30"	EACH	4	4					
54248170	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 42"	EACH	2	2					
542A0247	PIPE CULVERTS, CLASS A, TYPE 1 42"	FOOT	62	62					
542A5473	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	124.5	124.5					
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	431	431					
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	242.5	242.5					
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	563.7	563.7					
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	250.5	250.5					
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	192	192					
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	385	385					
550A0180	STORM SEWERS, CLASS A, TYPE 1 42"	FOOT	572	572					
55100300	STORM SEWER REMOVAL 8"	FOOT	95	95					
55100500	STORM SEWER REMOVAL 12"	FOOT	710	710					
55100700	STORM SEWER REMOVAL 15"	FOOT	55	55					
552A1300	STORM SEWERS JACKED IN PLACE, CLASS A 36"	FOOT	57	57					
• 56100600	WATER MAIN 6"	FOOT	507						507
• 56100700	WATER MAIN 8"	FOOT	281						281
• 56100800	WATER MAIN 10"	FOOT	835						835
• 56100900	WATER MAIN 12"	FOOT	400						400
• 56104900	WATER VALVES 6"	EACH	3						3
• 56105100	WATER VALVES 10"	EACH	2						2
• 56105200	WATER VALVES 12"	EACH	2						2
• 56108900	TAPPING VALVES AND SLEEVES 8"	EACH	1						1

9/14/2007 9:41:08 AM C:\Users\jrb\Documents\1015618.dwg

• SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
ILLINOIS 113 AT
ILLINOIS 129 AND ILLINOIS 53
PLOT DATE: 9/14/2007