F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2320	113X-N	WILL	133	5
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

- - - 62910

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: URBAN ILL-113 @ ILL-129 & ILL-53 STATE 100% I000-2A	URBAN TRAFFIC SIG. ILL-113 @ ILL-129 & ILL-53 STATE 100% Y031-1F	URBAN PRE-EMPTION ILL-113 @ ILL-129 & ILL-53 CITY 100% Y031-3D	URBAN LIGHTING ILL-113 @ ILL-129 & ILL-53 CITY 100% Y030-1E	URBAN SIDEWALK ILL-113 @ ILL-129 & ILL-53 STATE 50% CITY 50% SFTY-1B	URBAN WATERMAIN ILL-113 @ ILL-129 & ILL-53 CITY 100% Y060
•	56109210	WATER VALVES TO BE ADJUSTED	EACH	11						11
•	56200300	WATER SERVICE LINE 1"	FOOT	40						40
•	56200700	WATER SERVICE LINE 2"	FOOT	191						191
•	56201400	CORPORATION STOPS 1"	EACH	4						4
•	56201800	CORPORATION STOPS 2"	EACH	8						8
•	56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	30						30
•	56300200	ADJUSTING SANITARY SEWERS, OVER 8-INCH DIAMETER	FOOT	30						30
•	56300300	ADJUSTING WATER SERVICE LINES	FOOT	20						20
•	56400100	FIRE HYDRANTS TO BE MOVED	EACH	2						2
•	56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	4	4					
•	56400500	FIRE HYDRANTS TO BE REMOVED	EACH	3						3
•	56400600	FIRE HYDRANTS	EACH	1						1
•	56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	6						6
	60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	3	3					
	60107600	PIPE UNDERDRAINS 4"	FOOT	492	492					
	60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1					
	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	7	7					
	60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1					
	60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1	1					
	60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	3	3					
	60210000	CATCH BASINS, TYPE C, SPECIAL, TYPE 8 GRATE	EACH	1	1					
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1					
1	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7	7	1				
	60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3					
	60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2	2					
	60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	2	2					
	60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3						3

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: URBAN ILL-113 @ ILL-129 & ILL-53 STATE 100% I000-2A	URBAN TRAFFIC SIG. ILL-113 @ ILL-129 & ILL-53 STATE 100% Y031-1F	URBAN PRE-EMPTION ILL-113 @ ILL-129 & ILL-53 CITY 100% Y031-3D	URBAN LIGHTING ILL-113 @ ILL-129 & ILL-53 CITY 100% Y030-1E	URBAN SIDEWALK ILL-113 @ ILL-129 & ILL-53 STATE 50% CITY 50% SFTY-1B	URBAN WATERMAIN ILL-113 @ ILL-129 & ILL-53 CITY 100% Y060
	60249400	VALVE BOXES 6"	EACH	3						3
	60261540	INLETS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1	1					
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	11						11
	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	10	10					
	60500040	REMOVING MANHOLES	EACH	2	2					
	60500060	REMOVING INLETS	EACH	11	11					
	60600605	CONCRETE CURB, TYPE B	FOOT	2425	2425					
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	182	182					
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	4862	4862					
	60605500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (VARIABLE WIDTH GUTTER FLAG)	FOOT	200	200					
	60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	158	158					
	60617510	PAVED DITCH, TYPE B-30	FOOT	173	173					
	60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1315	1315					
	60624600	CORRUGATED MEDIAN	SQ FT	216	216					
	63200310	GUARDRAIL REMOVAL	FOOT	72	72					
•	66900200	NON-SPECIAL WASTE DISPOSAL	CU. YD	588	588					
•	66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1					
•	66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4					
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12					
	67100100	MOBILIZATION	L SUM	1	1					
	70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1					
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	90	90					
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1522	1522					
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	364	364					
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10530	10530					
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2256	2256					

• SPECIALTY ITEMS

1 Rev. 11-5-07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

ILLINOIS 113 AT ILLINOIS 129 AND ILLINOIS 53

PLOT DATE: 8/30/2007

8/30/2007
pw:\\pwidc\projects\b101648\design\bb_m32