

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
203	11BR-1	*	43	4
STA.		TO STA.		
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				
* WHITESIDE & ROCK ISLAND				

Item No.	Item	Unit	80% FED / 20% STATE	ROCK ISLAND COUNTY	WHITESIDE COUNTY	WHITESIDE COUNTY
			Total	I000	I000	X020-2A
			QUANTITY	ROADWAY	ROADWAY	BRIDGE
51202305	DRIVING PILES	FOOT	1088	--	--	1088
51203300	TEST PILE STEEL HP8X36	EACH	1	--	--	1
51203600	TEST PILE STEEL HP12X53	EACH	1	--	--	1
51204650	PILE SHOES	EACH	24	--	--	24
51500100	NAME PLATES	EACH	1	--	--	1
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15'	FOOT	144	--	144	--
54213450	END SECTIONS 15'	EACH	3	--	3	--
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	36	--	--	36
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4'	FOOT	101	--	--	101
60801015	FLAP GATE 15'	EACH	1	--	1	--
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	375	162.5	212.5	--
* 63000130	STEEL PLATE BEAM GUARD RAIL, TYPE A (SPECIAL)	FOOT	25	25	--	--
* 63100045	TRAFFIC BARRIER TERMINAL TYPE 2	EACH	1	1	--	--
* 63100085	TRAFFIC BARRIER TERMINAL TYPE 6	EACH	4	2	2	--
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	1	1	--
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	1	--	1	--
63200310	GUARDRAIL REMOVAL	FOOT	241	127	114	--
63500105	DELINEATORS	EACH	3	1	2	--
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	--	--
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MD	6	3	3	--
67100100	MOBILIZATION	L SUM	1	0.5	0.5	--
* 78001110	PAINT PAVEMENT MARKING - LINE 4'	FOOT	3820	1910	1910	--
78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	3	5	--
78200520	BARRIER WALL MARKERS, TYPE B	EACH	4	2	2	--
78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	3	1	2	--
* A2007814	TREE, TILIA AMERICANA (AMERICAN LINDEN/ BASSWOOD), 1-3/4' CALIPER, BALLED AND BURLAPPED	EACH	6	--	6	--
X0325519	DRAIN FOR AGGREGATE BASE COURSE	SQ YD	14	6	8	--
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1	--	--	1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1	--	--	1
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1	0.5	0.5	--
50800515	BAR SPLICERS	EACH	66	--	--	66
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5	--
Z0028415	GEO TECHNICAL REINFORCEMENT	SQ YD	772	436	336	--
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	0.5	0.5	--

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAS 203 (MOLINE ROAD)
 SECTION 11BR-1
 WHITESIDE & ROCK ISLAND COUNTIES

SCALE: VERT.
 HORIZ.
 DATE 12/05

DRAWN BY ARR
 CHECKED BY JKC