

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
203	11BR-1	*	43	8
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT				
* WHITESIDE & ROCK ISLAND				

BRIDGE APPROACH PAVEMENT SCHEDULE			
LOCATION (STA TO STA)	SQ YD	42001165 BRIDGE APPROACH PAVEMENT	
		SQ YD	50300300 PROTECTIVE COAT
STA 427+40.43 TO STA 427+70.43	111	111	
STA 428+71.17 TO STA 429+01.17	111	111	
TOTAL	222	222	

44000700 APPROACH SLAB REMOVAL	
LOCATION	SQ YD
STA 427+77.50 TO STA 427+97.40	57
STA 428+44.40 TO STA 428+64.30	57
TOTAL	114

542D0220 PIPE CULVERTS, CLASS D, TY 1, 15"	
LOCATION	FOOT
LT. STA. 435+00 (FIELD ENTRANCE)	76
LT. STA. 429+11 (FIELD ENTRANCE) *	68
TOTAL	144

54213450 END SECTIONS, 15"	
LOCATION	EACH
LT. STA. 435+00 (FIELD ENTRANCE)	2
LT. STA. 429+11 (FIELD ENTRANCE) *	1
TOTAL	3

60801015 FLAP GATE, 15" *	
LOCATION	EACH
STA 428+82, LT	1
TOTAL	1

* PROVISIONAL PAY ITEM SHOULD THE ENGINEER DETERMINE THE CULVERT AT THIS LOCATION DOES NOT OPERATE PROPERLY.

63000000 STEEL PLATE BEAM GUARD RAIL, TYPE A	
LOCATION	FOOT
STA 425+55.30 TO STA 427+17.80, RT.	162.5
STA 429+04.80 TO STA 429+79.80, RT.	75.0
STA 429+23.80 TO STA 430+61.30, LT.	137.5
TOTAL	375

63000130 STEEL PLATE BEAM GUARD RAIL, TYPE A, (SPECIAL)	
LOCATION	FOOT
STA 427+29.13, LT	25
TOTAL	25

63100045 TRAFFIC BARRIER TERMINAL, TYPE 2	
LOCATION	EACH
STA 427+29.13, LT.	1
TOTAL	1

63100085 TRAFFIC BARRIER TERMINAL, TYPE 6	
LOCATION	EACH
STA 427+17.80 TO STA 427+60.95, RT.	1
STA 427+36.80 TO STA 427+79.91, LT.	1
STA 428+61.69 TO STA 429+04.80, RT.	1
STA 428+80.65 TO STA 429+23.80, LT.	1
TOTAL	4

63100167 TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT)	
LOCATION	EACH
STA 425+55.30, RT.	1
STA 429+79.80, RT.	1
TOTAL	2

63100169 TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (FLARED)	
LOCATION	EACH
STA 430+61.3	1
TOTAL	1

63200310 GUARDRAIL REMOVAL	
LOCATION	FOOT
STA 426+70 TO STA 427+60, RT.	90
STA 427+68 TO STA 427+89, LT.	37
STA 428+62 TO STA 429+52, RT.	90
STA 428+83 TO STA 428+95, LT.	24
TOTAL	241

63500105 DELINEATORS	
LOCATION	EACH
STA 425+05.35, RT.	1
STA 430+29.8, RT.	1
STA 431+11.3, LT.	1
TOTAL	3

PAINT PAVEMENT MARKING		
	78001110	
	4" YELLOW	4" WHITE
LOCATION	FOOT	FOOT
STA 423+75 TO STA 432+25 (2 APPLICATIONS)	420	3400
TOTAL	3820	

78200410 GUARDRAIL MARKERS, TYPE A	
LOCATION	EACH
STA 425+05.3 TO STA 430+29.8, RT	5
STA 427+29.13 TO STA 431+11.26, LT	3
TOTAL	8

78200520 BARRIER WALL MARKERS, TYPE B *	
LOCATION	EACH
BRIDGE	4
TOTAL	4

* MARKERS SHALL BE BIDIRECTIONAL SILVER/ SILVER

78201000 TERMINAL MARKER - DIRECT APPLIED	
LOCATION	EACH
AT EACH TYPE 1 TERMINAL	3
TOTAL	3

TREE REPLACEMENT SCHEDULE					
CODE NO.	SCIENTIFIC NAME	COMMON NAME	SIZE	UNIT	QUANTITY
A2007814	TILIA AMERICANA	AMERICAN LINDEN/BRASSWOOD	1-3/4"	EACH	6

(SEE GENERAL NOTE 33 ON SHEET 2)