

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
549	117 T	OGLE	86	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNITS	TOTAL QUANTITY	Y007 80% Federal 20% State
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	53	53
20100500	TREE REMOVAL, ACRES	ACRE	0.6	0.6
* 20101400	NITROGEN FERTILIZER NUTRIENT	POUND	1440	1440
* 20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1440	1440
* 20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	1440	1440
20200100	EARTH EXCAVATION	CU YD	5114	5114
20400800	FURNISHED EXCAVATION	CU YD	2417	2417
21101615	TOPSOIL FURNISH AND PLACE, 4'	SQ YD	30733	30733
* 25000210	SEEDING, CLASS 2A	ACRE	15	15
* 25000310	SEEDING, CLASS 4	ACRE	1	1
■ 25000750	MOWING	ACRE	15	15
* 25100115	MULCH, METHOD 2	ACRE	16	16
* 25100630	EROSION CONTROL BLANKET	SQ YD	4588	4588
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	9600	9600
28000300	TEMPORARY DITCH CHECKS	EACH	91	91
28000400	PERIMETER EROSION BARRIER	FOOT	1593	1593
28000500	INLET AND PIPE PROTECTION	EACH	8	8
28100107	STONE RIPRAP, CLASS A4	SQ YD	138	138
28200200	FILTER FABRIC	SQ YD	138	138
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	1685	1685
35101400	AGGREGATE BASE COURSE, TYPE B	TON	508	508
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX'C, N50	TON	134	134
40800050	INCCIDENTAL HOT-MIX ASPHALT SURFACING	TON	83	83
42001200	PAVEMENT FABRIC	SQ YD	836	836
44201383	CLASS C PATCHES, TYPE IV, 12 INCH	SQ YD	836	836
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	74	74
48100100	AGGREGATE SHOULDERS, TYPE A	TON	1664	1664
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1

■ 100% STATE

PLOT DATE = Fri Dec 28 14:22:18 2007
 FILE NAME = c:\p\proj\jcs\117\05\11705.svr.dgn
 PLOT SCALE = 5/8"=1'-0"
 USER NAME = gertj