

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
549	117 T	OGLE	86	20
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SCHEDULES OF QUANTITIES

2500030

SEEDING, CLASS 4

ACRE	LOCATION	REMARKS
0.1	LT & RT Sta 801+50.0 TO 805+50.0	BOX 1
0.2	LT & RT Sta 810+00.0 TO 813+50.0	BOX 2
0.2	LT & RT Sta 1055+00.0 TO 1058+50.0	BOX 3
0.2	LT & RT Sta 1079+00.0 TO 1083+50.0	BOX 4
0.3	LT & RT Sta 1112+50.0 TO 1128+00.0	BOX 5
1	TOTAL LT & RT Sta.	

28000250

TEMPORARY EROSION CONTROL SEEDING

POUND	LOCATION	REMARKS
540	LT & RT Sta 801+50.0 TO 805+50.0	BOX 1
780	LT & RT Sta 810+00.0 TO 813+50.0	BOX 2
480	LT & RT Sta 1055+00.0 TO 1058+50.0	BOX 3
1320	LT & RT Sta 1079+00.0 TO 1083+50.0	BOX 4
6480	LT & RT Sta 1112+50.0 TO 1128+00.0	BOX 5
9600	TOTAL	

A TOTAL OF 6 DAYS FOR EACH OF THE 5 LOCATIONS.

25000750

MOWING

ACRE	LOCATION	REMARKS
0.8	LT & RT Sta 801+50.0 TO 805+50.0	BOX 1
1.1	LT & RT Sta 810+00.0 TO 813+50.0	BOX 2
0.6	LT & RT Sta 1055+00.0 TO 1058+50.0	BOX 3
2.0	LT & RT Sta 1079+00.0 TO 1083+50.0	BOX 4
10.5	LT & RT Sta 1112+50.0 TO 1128+00.0	BOX 5
15	TOTAL	

*MOWING CLASS 2A SEEDING AREAS ONLY.

28000300

TEMPORARY DITCH CHECKS *

EACH	LOCATION	REMARKS
9	LT Sta. 801+50.0 TO 805+50.0	BOX 1
9	RT Sta. 801+50.0 TO 805+50.0	BOX 1
6	LT Sta. 810+00.0 TO 812+50.0	BOX 2
5	RT Sta. 810+00.0 TO 812+50.0	BOX 2
10	RT Sta. 1055+00.0 TO 1058+50.0	BOX 3
7	RT Sta. 1079+00.0 TO 1081+12.5	BOX 4
14	LT Sta. 1123+65.0 TO 1128+00.0	BOX 5
31	RT Sta. 1113+00.0 TO 1128+00.0	BOX 5
91	TOTAL	

25100115

MULCH, METHOD 2

ACRE	LOCATION	REMARKS
0.9	LT & RT Sta 801+50.0 TO 805+50.0	
1.3	LT & RT Sta 810+00.0 TO 813+50.0	
0.8	LT & RT Sta 1055+00.0 TO 1058+50.0	
2.2	LT & RT Sta 1079+00.0 TO 1083+50.0	
10.8	LT & RT Sta 1112+50.0 TO 1128+00.0	
16	TOTAL	

28000400

PERIMETER EROSION BARRIER

EQOI	LOCATION	REMARKS
50	LT Sta. 803+63.4 TO 804+00.0	BOX 1
107	LT Sta. 812+50.0 TO 813+53.7	BOX 2
413	LT Sta. 1055+00.0 TO 1058+50.0	BOX 3
464	LT Sta. 1079+00.0 TO 1083+50.0	BOX 4
152	RT Sta. 1079+00.0 TO 1080+50.0	BOX 4
247	RT Sta. 1081+12.6 TO 1083+50.0	BOX 4
160	LT Sta. 1125+50.0 TO 1127+00.0	BOX 5
1593	TOTAL	

25100630

EROSION CONTROL BLANKET

SQ YD	LOCATION	REMARKS
292.6	LT Sta. 801+50.0 TO 805+50.0	BOX 1
288.4	RT Sta. 801+50.0 TO 805+50.0	BOX 1
203.6	LT Sta. 810+00.0 TO 812+50.0	BOX 2
173.6	RT Sta. 810+00.0 TO 812+50.0	BOX 2
151.2	RT Sta. 1055+00.0 TO 1058+50.0	BOX 3
157.2	RT Sta. 1079+00.0 TO 1081+12.5	BOX 4
370.1	LT Sta. 1123+65.0 TO 1128+00.0	BOX 5
2951.1	RT Sta. 1113+00.0 TO 1128+00.0	BOX 5
4588	TOTAL	

28000500

INLET AND PIPE PROTECTION

EACH	LOCATION	OFFSET (ft)	REMARKS
1	RT Sta. 803+63.4	31	BOX 1
1	RT Sta. 812+35.0	45	BOX 2
1	RT Sta. 813+08.0	28.35	BOX 2
1	RT Sta. 1056+42.3	47.6	BOX 3
1	RT Sta. 1081+12.7	69.25	BOX 4
1	RT Sta. 1117+20.0	36.3	BOX 5
1	RT Sta. 1125+61.0	71	BOX 5
1	RT Sta. 1126+11.0	39.6	BOX 5
8	TOTAL		

PLOT DATE = Fri, Dec 28 13:45:29 2007
 FILE NAME = c:\vpro\projects\2107065\107065evr.dgn
 PLOT SCALE = 500.0000 / IN.
 USER NAME = gaffj