

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
549	117 T	OGLE	86	25
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SCHEDULES OF QUANTITIES

70106500

TEMPORARY BRIDGE TRAFFIC SIGNALS

EACH	LOCATION	REMARKS
2	BOX NO. 2	STAGE 1
2	BOX NO. 3	STAGE 1
2	BOX NO.4	STAGE 1
2	BOX NO. 5	STAGE 1
8	TOTAL	

70106700

TEMPORARY RUMBLE STRIPS

EACH	LOCATION	REMARKS
6	BOX NO. 2	STAGING
6	BOX NO. 3	STAGING
6	BOX NO.4	STAGING
6	BOX NO. 5	STAGING
24	TOTAL	

USE 3 STRIPS LOCATIONS FOR EACH DIRECTION FOR EACH SIGNAL

70301000

WORK ZONE PAVEMENT MARKING REMOVAL

SQ. FT.	LOCATION	REMARKS
	BOX # 1	
26.7	Lt Sta. 803+43.2 TO 803+83.6	4" - Line TEMP PATCH
26.7	Rt Sta. 803+43.2 TO 803+83.6	4" - Line TEMP PATCH
	BOX # 2	
437.3	Lt Sta. 809+25.3 TO 815+87.9	4" - Line STAGE 1
437.3	Rt Sta. 809+25.3 TO 815+87.9	4" - Line STAGE 2
23.8	Lt Sta. 809+25.3	24"- Stop Bar STAGE 1
23.8	Lt Sta. 815+87.9	24"- Stop Bar STAGE 1
23.8	Rt Sta. 809+25.3	24"- Stop Bar STAGE 2
23.8	Rt Sta. 815+87.9	24"- Stop Bar STAGE 2
	BOX # 3	
482.0	Lt Sta. 1052+63.1 TO 1059+93.3	4" - Line STAGE 1
482.0	Rt Sta. 1052+63.1 TO 1059+93.3	4" - Line STAGE 2
23.8	Lt Sta. 1052+63.1	24"- Stop Bar STAGE 1
23.8	Lt Sta. 1059+93.3	24"- Stop Bar STAGE 1
23.8	Rt Sta. 1052+63.1	24"- Stop Bar STAGE 2
23.8	Rt Sta. 1059+93.3	24"- Stop Bar STAGE 2
	BOX # 4	
432.2	Lt Sta. 1077+79.2 TO 1084+34.0	4" - Line STAGE 1
432.2	Rt Sta. 1077+79.2 TO 1084+34.0	4" - Line STAGE 2
23.8	Lt Sta. 1077+79.2	24"- Stop Bar STAGE 1
23.8	Lt Sta. 1084+34.0	24"- Stop Bar STAGE 1
23.8	Rt Sta. 1077+79.2	24"- Stop Bar STAGE 2
23.8	Rt Sta. 1084+34.0	24"- Stop Bar STAGE 2
	BOX # 5	
501.2	Lt Sta. 1122+05.0 TO 1129+64.4	4" - Line STAGE 1
501.2	Rt Sta. 1122+05.0 TO 1129+64.4	4" - Line STAGE 2
23.8	Lt Sta. 1122+05.0	24"- Stop Bar STAGE 1
23.8	Lt Sta. 1129+64.4	24"- Stop Bar STAGE 1
23.8	Rt Sta. 1122+05.0	24"- Stop Bar STAGE 2
23.8	Rt Sta. 1129+64.4	24"- Stop Bar STAGE 2
4139	TOTAL	

70300520

PAVEMENT MARKING TAPE, TYPE III 4"

EQOI	LOCATION	REMARKS
	BOX # 2	
1325.2	Lt Sta. 809+25.3 TO 815+87.9	STAGE 1
1325.2	Rt Sta. 809+25.3 TO 815+87.9	STAGE 2
	BOX # 3	
1460.5	Lt Sta. 1052+63.1 TO 1059+93.3	STAGE 1
1460.5	Rt Sta. 1052+63.1 TO 1059+93.3	STAGE 2
	BOX # 4	
973.2	Lt Sta. 1079+47.4 TO 1084+34.0	STAGE 1
973.2	Rt Sta. 1079+47.4 TO 1084+34.0	STAGE 2
	BOX # 5	
1478.9	Lt Sta. 1122+15.0 TO 1129+54.4	STAGE 1
1478.9	Rt Sta. 1122+15.0 TO 1129+54.4	STAGE 2
10476	TOTAL	

70300570

PAVEMENT MARKING TAPE, TYPE III 24"

EQOI	LOCATION	REMARKS
	BOX # 2	
12	Lt Sta. 809+25.3	Stop Bar STAGE 1
12	Lt Sta. 809+25.3	Stop Bar STAGE 1
12	Rt Sta. 815+87.9	Stop Bar STAGE 2
12	Rt Sta. 815+87.9	Stop Bar STAGE 2
	BOX # 3	
12	Lt Sta. 1052+63.1	Stop Bar STAGE 1
12	Lt Sta. 1052+63.1	Stop Bar STAGE 1
12	Rt Sta. 1059+93.3	Stop Bar STAGE 2
12	Rt Sta. 1059+93.3	Stop Bar STAGE 2

PLOT DATE
FILE NAME
PLOT SCALE
USER NAME