CONTRACT NO. 64B89

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
654	109M	CARROLL	76	18
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

BITUMINOUS SCHEDULE

STATIONING	LENGTH FT	WIDTH FT	AREA SQ YD	35101400 AGG BASE CSE TYPE B ** TON	42300300 PCC PAVT 7 INCH SQ YD	40701891 HMA PAVT FULL DEPTH 10 1/2" SQ YD	40600990 TEMP RAMP SQ YD	40600982 HMA SURF REM BUTT - JOINTS SQ YD	48203021 HMA SHLDS, 6" SQ YD	40603310 HMS SURF CSE MIX "C" N50 TON	48101200 AGG SHLDS TYPE B TON	40603335 HMA SURF CSE MIX "D" N 50 TON	40800050 INCID HMA SURFACING N50 TON	*2001392 HMA SURF CSE SPECIAL TON	31100910 SUB-BASE GRAN-MAT TYPE A 12" SQ YD	31100935 SUB-BASE GRAN-MAT TYPE A 18" SQ YD	Z0005400 BRKR- RUN CRUSHED STONE TONS	21001000 GEO TECH FAB FOR GR STAB SQ YD	44000100 PAVT REM SQ YD	44004300 PAVT BREAKING SQ YD
IL 73																				
263 + 0 _ 264 + 75	175	26	505.6			505.6			155.6	17.4	76.8	56.6					717.5		505.6	
264 + 75 _ 270 + 25	550	26	1588.9			1588.9			488.9	54.8	241.4	178			2200					1588.9
270 + 25 _ 272 + 0	175	26	505.6			505.6			155.6	17.4	76.8	56.6			700				505.6	
272 + 0 _ 273 + 0	100	VAR*	1999.9			1999.9			88.9	10	43.9	224			400				1999.9	
273 + 0 _ 277 + 0	400	26	1155.6			1155.6			355.6	39.8	175.5	129.4			1600				1155.6	
277 + 0 _ 277 + 60	60	26	173.3			173.3			53.3	6	26.3	19.4					246		173.3	
PAYNE ROAD																				
23 + 55 _ 24 + 0	45	22	110								38		21.6			120		110.0		
24 + 0 _ 25 + 17	117	22	286								44.4		56.1			312		286		
25 + 17 _ 26 + 68	151	22	369.1												402.7			369.1		
26 + 94 _ 28 + 52	158	22	386.2												421.3			386.2		
28 + 52 _ 29 + 0	48	22	117.3								18.2		23			128		117.3		
29 + 0 _ 30 + 0	100	22	244.4								38		47.9			266.7		244.4		
30 + 0 _ 31 + 0	100	22	244.4								38		47.9			266.7		244.4		
31 + 0 _ 32 + 50	150	22	366.7								56.9		71.9			400		366.7		
IL 72 / SHANNON RD																				
60.00 + 93.47 _ 61.00 + 23.47								48.9												
60.00 + 12.84 _ 61.00 + 23.47	111	22	321.6				24.4						139.7		321.6					
61 + 23.47		22					24.4													
60.00 + 12.84 _ 60.00 + 48.84								48.9												
SOUTH / WEST BOLTON																				
700 + 11.36 _ 700 + 41.36								48.9												
700.00 + 11.36 _ 702 + 0	189	22	278.8				24.4				85.9		176.7		278.8					
702 + 2.78		22					24.4													
701 + 72.78 _ 702 + 2.78								48.9												
S. BOLTON/ PEARL CITY																				
798 + 42 _ 799 + 88	146	22	169.9				24.4				34.2		33.3		169.9					
22 + 50 LT PAYNE RD	PE		83.9	57.3									9.4							
25 + 50 RT PAYNE RD	PE		83.9	57.3									9.4							
31 + 0 LT PAYNE RD	PE		112	76.5									12.5							
264 + 75 LT IL 73	PE		111.1	75.9									12.4							
701 + 0 LT DETOUR	PE		134	91.8									15							
212 + 83 LT DETOUR	CE		63.9		63.9															
60 + 96 RT DETOUR	CE		63.9		63.9															
GOOD NEIGHBOR POLICY																				
Quantities are based on 10% of the actual areas																				
ZIER ROAD" from IL 72 TO LAKE TIMBER RD"	9874	22	24136								84.0			270.3						
ZIER ROAD" from TIMBER RD TO LAKE CARROLL BLVD"	2482	22	6066.1								21.1			67.9						
WEST SABIN CHURCH RD from SHANNON RD TO IL 73	21120	22	51626.7								179.6			578.2						
SHANNON RD FROM WEST BOLTON RD TO WEST SABIN CHURCH RD	2640	22	6453.3								22.4			72.3						
PEACE & QUIET RD (from EAST OF LAKE CARROLL SUBDIVISION - IL 73)	5280	25	14520								44.9			162.6						
SPRING VALLEY ROAD (from IL 73 - KITTRIDGE ROAD)	10560	22	25930.7								89.8			290.4						
KITTRIDGE ROAD (from SPRING VALLEY RD- IL 72)	10560	21	24640								89.8			276.0						
TOTALS				359	128	5929	122	196	1298	145	1526	664	677	1718	6494	1493	964	2124	4340	1589

* INCLUDING INTERSECTION AREA
** USE 12" THICKNESS, AND 18" FROM STA 263+00 TO STA 264+75 AND STA 277+00 TO STA 277+60
NOTE: the cost of the prime coats shall be included in the cost of the contract unit price per tons for HMA SURFACE COURSE MIX D N50.

1 REVISED SHEET 2/7/08

PLOT DATE = Fri Feb 01 09:24:53 2008
FILE NAME = c:\pw_work\d-95\b2089\d809\b2089d809cvr.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = geffjl