

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
654	109M	CARROLL	76	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NUMBER	ITEM	UNITS	TOTAL QUANTITY	90% FEDERAL 10% STATE I-000
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	163	163
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	21	21
20100500	TREE REMOVAL, ACRES	ACRE	0.4	0.4
20200100	EARTH EXCAVATION	CU YD	20619	20619
20200200	ROCK EXCAVATION	CU YD	6234	6234
20400800	FURNISHED EXCAVATION	CU YD	758	758
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	2124	2124
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	21732	21732
* 25000210	SEEDING, CLASS 2A	ACRE	2.4	2.4
* 25000310	SEEDING, CLASS 4	ACRE	2	2
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	362	362
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	362	362
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	362	362
■ 25000750	MOWING	ACRE	2.4	2.4
* 25100630	EROSION CONTROL BLANKET	SQ YD	2682	2682
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2003	2003
28000300	TEMPORARY DITCH CHECKS	EACH	124	124
28000400	PERIMETER EROSION BARRIER	FOOT	1352	1352
28000500	INLET AND PIPE PROTECTION	EACH	8	8
* 28000720	MULCH METHOD 2	ACRE	4.4	4.4
28100107	STONE RIPRAP, CLASS A4	SQ YD	44	44
28200200	FILTER FABRIC	SQ YD	44	44
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	6494	6494
31100935	SUB-BASE GRANULAR MATERIAL, TYPE A 18"	SQ YD	1493	1493
35101400	AGGREGATE BASE COURSE, TYPE B	TON	359	359
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	196	196
40600990	TEMPORARY RAMP	SQ YD	122	122
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	145	145
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	664	664
40701891	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10 1/2"	SQ YD	5929	5929

■ 100% STATE

*SPECIALTY ITEM

PLOT DATE = Fri, Dec 14, 07:58:53 2007
 FILE NAME = C:\Users\jg\Documents\64B89\64B89.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = gaff,jl