

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
654	109M	CARROLL	76	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ITEM NO.	DESCRIPTION	LOCATION	OFFSET (ft)	QUANTITY	UNIT	LOCATION	OFFSET (ft)	QUANTITY	UNIT	REMARKS
25000600	POTASSIUM FERTILIZER NUTRIENT									
	POUND	LOCATION	OFFSET (ft)							
	223	IL 73 L & R Sta. 262+50.0	T0	279+00.0						
	24	Payne Rd L & R Sta. 22+50.0	T0	26+68.0						
	71	L & R Sta. 27+50.0	T0	33+00.0						
	13	IL 72/Shannon Rd L & R Sta. 21+50.0	T0	213+50.0						
	22	South Bolton Road L & R Sta. 700+00.0	T0	702+50.0						
	9	South Bolton/Pearl City Road LT Sta. 798+42.0	T0	799+63.0						
	362	TOTAL								
28000400	PERIMETER EROSION BARRIER									
	FOOT	LOCATION	OFFSET (ft)							
	354	IL 73 RT Sta. 265+50	T0	268+50						
	538	LT Sta. 265+00	T0	270+00						
	209	LT Sta. 277+00	T0	279+00						
	251	Payne Rd LT Sta. 30+50	T0	33+00						
	1352	TOTAL								At discretion of the Engineer
28000500	INLET AND PIPE PROTECTION									
	EACH	LOCATION	OFFSET (ft)							
	1	IL 73 LT Sta. 264+53								FE CULVERT
	1	RT Sta. 268+23								DROP BOX
	1	RT Sta. 277+70								BOX CULVERT
	1	Payne Rd LT Sta. 22+75								PE CULVERT
	1	RT Sta. 25+75								FE CULVERT
	1	LT Sta. 28+00								AR CULVERT
	1	IL 72/Shannon Rd LT Sta. 60+50.0								
	1	South Bolton/Pearl City Road LT Sta. 799+62.0								
	8	TOTAL								
28000720	MULCH, METHOD 2									
	ACRE	LOCATION	OFFSET (ft)							
	2.47	IL 73 L & R Sta. 262+50.0	T0	279+00.0						
	0.27	Payne Rd L & R Sta. 22+50.0	T0	26+68.0						
	0.79	L & R Sta. 27+50.0	T0	33+00.0						
	0.28	IL 72/Shannon Rd L & R Sta. 21+50.0	T0	213+50.0						
	0.48	South Bolton Road L & R Sta. 700+00.0	T0	702+50.0						
	0.20	South Bolton/Pearl City Road LT Sta. 798+42.0	T0	799+63.0						
	4.4	TOTAL								
25100630	EROSION CONTROL BLANKET									
	SQ YD	LOCATION	OFFSET (ft)							
	682	IL 73 LT Sta. 262+50.0	T0	277+50.0						
	850	RT Sta. 262+50.0	T0	277+50.0						
	673	Payne Rd LT Sta. 22+50.0	T0	33+00.0						
	477	RT Sta. 22+50.0	T0	33+00.0						
	2682	TOTAL								
28000250	TEMPORARY EROSION CONTROL SEEDING									
	POUND	LOCATION	OFFSET (ft)							
	1336	IL 73 L & R Sta. 262+50.0	T0	279+00.0						
	146	Payne Rd L & R Sta. 22+50.0	T0	26+68.0						
	425	L & R Sta. 27+50.0	T0	33+00.0						
	28	IL 72/Shannon Rd L & R Sta. 21+50.0	T0	213+50.0						
	48	South Bolton Road L & R Sta. 700+00.0	T0	702+50.0						
	20	South Bolton/Pearl City Road LT Sta. 798+42.0	T0	799+63.0						
	2003	TOTAL								Temporary seeding on both Class 2A & Class 4 seeding areas;100 lb/acre.
28100107	STONE RIPRAP, CLASS A4									
	SQ YD	LOCATION	OFFSET (ft)							
	44	IL 73 LT Sta. 268+22.6								AT GRATED END SECTION
28200200	FILTER FABRIC									
	SQ YD	LOCATION	OFFSET (ft)							
	44	IL 73 LT Sta. 268+22.6								AT GRATED END SECTION
44000400	GUTTER REMOVAL									
	FOOT	LOCATION	OFFSET (ft)							
	188	South Bolton Road L & R Sta. 700+11	T0	700+79						
28000300	TEMPORARY DITCH CHECKS									
	EACH	LOCATION	OFFSET (ft)							
	56	IL 73 L & R Sta. 263+00	T0	277+50						
	68	Payne Rd L & R Sta. 22+50	T0	33+00						
	124	TOTAL								
44200071	PAVEMENT PATCHING, TYPE IV, 6 INCH									
	SQ YD	LOCATION	OFFSET (ft)							
	43	Shannon Road L & R Sta. 60+23.0								
	28	L & R Sta. 60+38.0								PROPOSED STORM SEWERS
	71	TOTAL								EXISTING STORM SEWERS

PLOT DATE = Thu Dec 13 14:40:08 2007  
 FILE NAME = S:\A\2007\64B89\64B89.dgn  
 PLOT SCALE = 1/8" = 1'-0"  
 USER NAME = gmf/jl