

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
654	109M	CARROLL	76	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ITEM NO.	DESCRIPTION	UNIT	LOCATION	LENGTH (ft)	REMARKS	ITEM NO.	DESCRIPTION	UNIT	LOCATION	LENGTH (ft)	REMARKS	OFFSET (ft)	REMARKS
50100300	REMOVAL OF EXISTING STRUCTURES NO.1	EACH	IL 73	268+22.6	EXISTING 6'X6' BOX CULVERT	54208635	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL, EQUIVALENT ROUND-SIZE 30"	FOOT	South Bolton / West Bolton Road			19	
		1						13.5	RT Sta. 600+54.4			41	
								14.5	South Bolton Road/Pearl City Road				
									LT Sta. 799+62.6				
									TOTAL				
50105200	REMOVAL OF EXISTING CULVERTS	EACH	Shannon Road Sta.	60+22.7	REMOVAL OF EXISTING 18" RCP ACROSS SHANNON ROAD.								
		1											
50800105	REINFORCEMENT BARS	POUND	IL 73	277+70.3	Concrete Collar	54210309	PIPE CULVERTS, TYPE 2, REINFORCED CONCRETE - ARCH, EQUIVALENT ROUND-SIZE 24"	FOOT	Payne Road	28+00.0			
		63	LT Sta.					47					
54001001	BOX CULVERT END SECTION, CULVERT NO.1	EACH	IL 73	268+22.6	6'X6' Box Culvert	54213450	END SECTIONS 15"	EACH	IL 73			33	FE
		1	LT Sta.					2	LT Sta. 264+75.0			27.14	FE
								2	Payne Road	25+50.0		39.5	FE
								2	South Bolton Road	701+00			
								6	LT Sta.				
									TOTAL				
54002020	EXPANSION BOLTS 3/4 INCH	EACH	IL 73	277+70.3	Concrete Collar	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	Shannon Road	60+43.4		41.69	north west corner
		12	LT Sta.					1	LT Sta.				
54010402	PRECAST CONCRETE BOX CULVERT 4'X2'	FOOT	IL 73	277+70.3	Extend Lt. side Only.	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	IL 73				At west end of 4'X2' Box Culvert
		4	Sta.					1	LT Sta. 277+70.3				
54010605	PRECAST CONCRETE BOX CULVERT 6'X6'	FOOT	IL 73	268+22.6	6'X6' Box Culvert	54214305	END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	South Bolton / West Bolton Road			19	
		141	Sta.					1	RT Sta. 600+54.4			41	
								1	South Bolton Road/Pearl City Road				
								2	LT Sta. 799+62.6				
									TOTAL				
542D1060	PIPE CULVERTS, CLASS D, TYPE 2 15"	FOOT	IL 73	264+75.0		54214299	END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	Payne Road	28+00.0			
		38	LT Sta.					2	Sta.				
		52	Payne Road										
		43	RT Sta. 25+50.0										
			South Bolton Road										
			LT Sta. 701+00										
		133	TOTAL										

PLOT DATE = Thu, Dec 13, 14:46:08, 2007
 FILE NAME = I:\Projects\10209365\640996c-vr.dgn
 PLOT SCALE = 50.00000 / IN.
 USER NAME = gaffj