SCHEDULE OF QUANTITIES

78001110 PAINT PAVEMENT MARKING - LINE 4"

FOOT WHITE	FOOT YELLOW	LOCATION (2 APPLICATIONS)				OFFSET (ft)	REMARKS
		IL 73					
1889		RT Sta.	263+00	TO	272+44		White Edge line Right
1889		LT Sta.	263+00	TO	272+44		White Edge line Left
1000		RT Sta.	273+00	TO	278+00		White Edge line Right
1000		LT Sta.	273+00	TO	278+00		White Edge line Left
2200	4400	Sta.	263+00	TO	274+00		Double Yellow -Center line
	1000	Sta.	274+00	TO	278+00		Solid RT/ Skip LT
		Payne Road					
436		RT Sta.	23+00	TO	25+18		White Edge line Right
436		LT Sta.	23+00	TO	25+18		White Edge line Left
806		RT Sta.	28+47	TO	32+50		White Edge line Right
806		LT Sta.	28+47	TO	32+50		White Edge line Left
	872	Sta.	23+00	TO	25+18		Double Yellow -Center line
	1612	Sta.	28+47	TO	32+50		Double Yellow -Center line
		South Bolton Rd					
	480	Sta.	700+35	TO	701+55		Double Yellow -Median
905		L & R Sta.	700+11	TO	702+00		White Edge line Right
		IL 72/ Shannon Rd					
680		L & R Sta.	60+13	TO	61+24		White Edge line Right
		South Bolton Rd/ Pearl City Rd					
360		LT Sta.	798+42	TO	799+88		White Edge line Right
12407	8364						
20771		TOTAL					

Note: CONTRACTOR SHALL CALL Kurt Glazier from the Bureau of operation prior to striping.
see GENERAL NOTES.

78001150 PAINT PAVEMENT MARKING - LINE 12"

FOOT	LOCATION				OFFSET (ft)	REMARKS
	South Bolton Rd					
50	Sta.	700+35	TO	701+55		Diagonals @ 20' Centers Yellow

78004280 PREFORMED PLASTIC PAVEMENT MARKING. TYPE B - INLAID - LINE 24"

FOOT		LOCATION		OFFSET (ft)	REMARKS
		Payne Road			
24		RT Sta.	26+40		Stop bar White
24		LT Sta.	27+22		Stop bar White
		South Bolton Rd			
26		LT Sta.	700+40		Stop bar White
		IL 72/ Shannon Rd			
28		LT Sta.	60+40		Stop bar White
102	TOTAL				

X0323455 ADJUST MONITORING WELL

EACH		LOCATION		OFFSET (ft)	REMARKS
		IL 72			
1		LT Sta.	212+62	28.0	
		Shannon Road			
1		LT Sta.	60+38	16.0	
1		LT Sta.	60+79	10.5	
1		LT Sta.	61+09	12.5	
4	TOTAL				

X0323660 DROP BOX NO.1

EACH	LOCATION		OFFSET (ft)	REMARKS
	IL 73			6'X8'X8' DROP STRUCTURE
1	RT Sta.	268+22.6		

X0325519 DRAIN FOR AGGREGATE BASE COURSE

SQ YD		LOCATION		OFFSET (ft)
		IL 73		
3		L & R Sta.	265+00.0	
3		L & R Sta.	268+22.0	
3		L & R Sta.	272+00.0	
3		L & R Sta.	277+00.0	
		Payne Road		
3		L & R Sta.	29+50.0	
15	TOTAL			

Z0020900 ESTABLISHING AND REFERENCING LAND SECTION MARKERS

EACH	LOCATION		OFFSET (ft)
	IL 73		
1	LT Sta.	272+43.0	5

PLOT DATE = Thu Dec 13 14:48:30 2007
FILE NAME = a:\projects\p200906\d00906ovr.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = goffj1