

# EARTHWORK SCHEDULE

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
654	109M	CARROLL	76	19
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STATION NO.	EARTH EX CUT CU YD	SHRINK FACTOR 25%	EMBANKMENT FILL CU YD	BALANCE WASTE (+) SHORT (-) CU. YDS.
IL ROUTE 73 262 + 50 TO 279 + 00	10094.1	7571	8275.4	-704.8
WEST PAYNE ROAD 22 + 50 TO 26 + 00	975.6	732	13.2	718.5
EAST PAYNE ROAD 27 + 50 TO 33 + 00	8883.3	6662	14.9	6647.6
IL 72 / SHANNON ROAD INTERSECTION 210 + 50 TO 213 + 50	345.1	259	8.4	250.4
SOUTH BOLTON / WEST BOLTON ROAD 700 + 00 TO 702 + 50	108.7	82	134.2	-52.7
SOUTH BOLTON / PEARLCITY ROAD 798 + 00 TO 799 + 63	212.6	159	15.9	143.6
	20619		8462	7003
	EARTH EX			WASTE (+)

ROCK CUT		BALANCE WASTE (+) SHORT (-) CU. YDS.
IL ROUTE 73 271 + 00 TO 278 + 00	4505.0	4505
EAST PAYNE ROAD 27 + 00 TO 30 + 50	1729	1729
TOTALS		6234

PLOT DATE = Thu Dec 13 14:46:31 2007  
 FILE NAME = c:\pcc\proj\64289\64289.dwg  
 USER NAME = gffj