

SUMMARY OF QUANTITIES

80% FED / 20% STATE

Y007

CODE NO.	ITEM	UNIT	TOTAL QTY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	44
20100500	TREE REMOVAL, ACRES	ACRE	0.25
20200100	EARTH EXCAVATION	CU YD	6383
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	100
* 25000210	SEEDING, CLASS 2A	ACRE	0.7
* 25000310	SEEDING, CLASS 4	ACRE	0.8
■ 25000750	MOWING	ACRE	1.5
* 25100115	MULCH, METHOD 2	ACRE	1.5
* 25100630	EROSION CONTROL BLANKET	SQ YD	481
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	450
28000300	TEMPORARY DITCH CHECKS	EACH	36
28000400	PERIMETER EROSION BARRIER	FOOT	129
28000500	INLET AND PIPE PROTECTION	EACH	3
28100107	STONE RIPRAP, CLASS A4	SQ YD	13
28200200	FILTER FABRIC	SQ YD	13
35101400	AGGREGATE BASE COURSE, TYPE B	TON	257
40600990	TEMPORARY RAMP	SQ YD	58
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	47
44201383	CLASS C PATCHES, TYPE IV, 12 INCH	SQ YD	160
48100100	AGGREGATE SHOULDERS, TYPE A	TON	608

■ NP 100% STATE

* Specialty Item