

# SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*303	129M&TS	WINNEBAGO	110	3
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS	FED. AID PROJECT	

CODE NUMBER	ITEM	UNIT	URBAN	HSIP	HSIP	NHS
			TOTAL QUANTITY	I000-1A 90% FED 10% STATE	Y031-1F 90% FED 7.5% STATE 2.5% COUNTY	I000-1A 80% FED 20% STATE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	108	108		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	357	357		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	171	171		
20200100	EARTH EXCAVATION	CU YD	10,524	10,524		
25000210	SEEDING, CLASS 2A	ACRE	4.1	4.1		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	369	369		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	369	369		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	369	369		
25000750	MOWING	ACRE	4.1	4.1		
25100115	MULCH, METHOD 2	ACRE	2.4	2.4		
25100630	EROSION CONTROL BLANKET	SQ YD	8,210	8,210		
25100900	TURF REINFORCEMENT MAT	SQ YD	147	147		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,460	2,460		
28000300	TEMPORARY DITCH CHECKS	EACH	78	78		
28000400	PERIMETER EROSION BARRIER	FOOT	2,200	2,200		
28000500	INLET AND PIPE PROTECTION	EACH	4	4		
28100107	STONE RIPRAP, CLASS A4	SQ YD	99	99		
28200200	FILTER FABRIC	SQ YD	99	99		
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	517	517		
31100935	SUB-BASE GRANULAR MATERIAL, TYPE A 18"	SQ YD	6,556	6,556		
31100965	SUB-BASE GRANULAR MATERIAL, TYPE A 24"	SQ YD	5,201	5,201		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	49	49		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	13.5	12.5		1.0
40600300	AGGREGATE (PRIME COAT)	TON	35.1	32.7		2.4
40600525	LEVELING BINDER (HAND METHOD), N50	TON	3	3		
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	281	281		
40600745	POLYMERIZED LEVELING BINDER (HAND METHOD), N90	TON	6	6		
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	298	214		84
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	555	411		144
40600990	TEMPORARY RAMP	SQ YD	654	632		22
40603080	HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N50	TON	185	185		
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N90	TON	9,653	9,653		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	296	296		
40603335	HOT-MIX ASPHALT SURFACE COURSF, MIX "D", N50	TON	412	412		
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1,402	1,259		143
44000100	PAVEMENT REMOVAL	SQ YD	580	580		
44004250	PAVED SHOULDER REMOVAL	SQ YD	387	387		
44004300	PAVEMENT BREAKING	SQ YD	1,736	1,736		
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	306	306		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	6,186	6,186		
48100100	AGGREGATE SHOULDERS, TYPE A	TON	613	613		

■ 100% STATE