

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*303	129M&TS	WINNEBAGO	110	24
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"

FOOT	LOCATION			
	IL 173			
224	Sta 236+91 - 244+76	Yellow - Painted Median		
98	Sta 242+51 - 244+76	White - Shoulder Median RT		
186	Sta 246+47 - 248+56	White - Shoulder Median RT		
134	Sta 247+78 - 248+14	White - Painted Island		
63	Sta 249+10 - 250+11	White - Shoulder Median RT		
236	Sta 251+66 - 259+51	Yellow - Painted Median		
221	Sta 250+11 - 260+13	White - Shoulder Diagonals RT		
	ARGYLE ROAD			
57	Sta 93+78 - 96+78	Yellow - Painted Median		
168	Sta 99+20 - 99+65	White - Painted Island		
	BELVIDERE ROAD			
101	Sta 100+64 - 101+30	White - Shoulder Median LT		
174	Sta 100+21 - 100+77	White - Painted Island		
170	Sta 103+27 - 108+92	Yellow - Painted Median		
1,832	TOTAL			

78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"

FOOT	LOCATION			
	IL 173			
11.3	Sta 247+75	White - Stop Bar		
14.0	Sta 247+85	White - Stop Bar		
18.0	Sta 247+89 - 247+98	White - Stop Bar		
15.5	Sta 248+89	White - Stop Bar		
15.6	Sta 248+89 - 248+98	White - Stop Bar		
11.3	Sta 249+03	White - Stop Bar		
	ARGYLE ROAD			
18.0	Sta 99+20 - 99+35	White - Stop Bar		
11.3	Sta 99+33	White - Stop Bar		
12.0	Sta 99+42	White - Stop Bar		
	BELVIDERE ROAD			
12.0	Sta 100+52	White - Stop Bar		
18.0	Sta 100+63 - 100+68	White - Stop Bar		
11.3	Sta 100+68	White - Stop Bar		
168.3	TOTAL			

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION			
	<u>Two-Way Amber</u>			
	IL 173			
28	Sta 236+91 - 247+76	40' o.c. - LT		
14	Sta 237+62 - 242+11	40' o.c. - RT		
28	Sta 242+11 - 247+76	20' o.c. - RT		
27	Sta 249+02 - 259+51	40' o.c. - RT		
24	Sta 249+02 - 254+31	20' o.c. - LT		
15	Sta 254+31 - 259+51	40' o.c. - LT		
	ARGYLE ROAD			
6	Sta 92+99 - 93+78	40' o.c. - RT Approach Side		
15	Sta 93+78 - 99+33	40' o.c. - LT		
29	Sta 93+78 - 99+33	20' o.c. - RT		
	BELVIDERE ROAD			
43	Sta 100+62 - 108+92	20' o.c. - LT		
22	Sta 100+62 - 108+92	40' o.c. - RT		
6	Sta 108+92 - 109+54	40' o.c. - LT Approach Side		
257	Sub-Total			

One-Way Crystal

16	Sta 244+76 - 247+86	20' o.c. - LT Turn Lane
16	Sta 244+76 - 247+86	20' o.c. - RT Turn Lane
14	Sta 248+89 - 251+66	20' o.c. - LT Turn Lane
	ARGYLE ROAD	
14	Sta 96+78 - 99+43	20' o.c. - LT Turn Lane
	BELVIDERE ROAD	
14	Sta 100+52 - 103+27	20' o.c. - LT Turn Lane
74	Sub-Total	
331	TOTAL	

78300100 PAVEMENT MARKING REMOVAL

SQ FT	LOCATION			
	IL 173			
1,131.3	Sta 239+81 - 256+78	Mainline Centerline		
26.0	Sta 247+80	Stop Bar (Existing)		
26.0	Sta 249+00	Stop Bar (Existing)		
559.3	Sta 237+17 - 245+56	Stage 3 - Centerline		
722.0	Sta 249+00 - 259+83	Stage 3 - Centerline		
779.0	Sta 236+72 - 260+09	Stage 3 - EOP (LT)		
354.0	Sta 236+72 - 247+34	Stage 3 - EOP (RT)		
317.3	Sta 250+11 - 259+63	Stage 3 - EOP (RT)		
40.0	Sta 247+73	Stage 3 - Stop Bar		
22.0	Sta 249+00	Stage 3 - Stop Bar		
33.0	Sta 245+55 - 247+75	Stage 3 - Painted Median		
	ARGYLE ROAD			
247.7	Sta 97+37 - 99+32	Stage 3 - Painted Median		
291.3	Sta 93+00 - 97+37	Stage 3 - Centerline		
237.0	Sta 93+00 - 99+69	Stage 3 - EOP (LT & Return)		
249.7	Sta 93+00 - 99+22	Stage 3 - EOP (RT & Return)		
84.0	Sta 99+28	Stage 3 - Stop Bar		
52.0	Sta 97+37 - 99+32	Stage 3 - Painted Median		
	BELVIDERE ROAD			
57.0	Sta 100+47 - 100+93	EOP - LT (Existing)		
58.7	Sta 100+02 - 101+50	EOP - RT (Existing)		
26.0	Sta 100+65	Stop Bar (Existing)		
5,313.3	TOTAL			

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION	
	BELVIDERE ROAD	
11	As Directed by the Resident	
11	TOTAL	

B2004814 TREE, MALUS SARGENTII (SARGENT CRABAPPLE) 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED

EACH	LOCATION	
	IL 173	
24	As Directed by the District Landscape Architect	
24	TOTAL	

PLOT DATE = Mon Dec 03 11:17:38 2007
 FILE NAME = c:\p\proj\129m&ts\281717_dbr1717.rvt.dgn
 PLOT SCALE = 50.0000 / 1 IN.
 REFERENCE = WREF