

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*303	129M&TS	WINNEBAGO	110	27

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

•(IL 173)

EARTHWORK SCHEDULE

	LOCATION	EARTH EXC (CUT)	EARTH EXC ADJ FOR SHRINK 25%	EMBANK FILL	EARTH WORK BALANCE WASTE (+) SHORTAGE (-)
		CU YD	CU YD	CU YD	CU YD
STAGE I	IL 173 RT STA 236+21.62 TO 242+50 RT STA 254+50 TO 260+12.68	981.8 1546.2	736.35 1159.65	123 7.5	613.35 1152.15
	IL 173 / BELVIDERE RD. TEMPORARY PAVEMENT NW QUADRANT	51.5	38.625	5.6	33.025
	IL 173 / BELVIDERE RD. TEMPORARY PAVEMENT NE QUADRANT	91	68.25	29	39.25
STAGE II	ARGYLE ROAD 93+00 TO 100+00	3372.6	2529.45	260.6	2268.85
	IL 173 RT STA 242+50 TO 254+50	2934.6	2200.95	466.4	1734.55
STAGE III	IL 173 LT STA 242+50 TO 254+50	258.1	193.58	1056.9	-863.33
	BELVIDERE ROAD 100+00 TO 109+50	1036.4	777.3	1858.3	-1081
STAGE IV	IL 173 LT STA 236+21.62 TO 242+50	145.9	109.43	128.1	-18.68
	LT STA 254+50 TO 260+12.68	105.8	79.35	147.5	-68.15
PROJECT TOTALS		10523.9	7892.93	4082.9	3810.03

PLOT DATE = Mon, Dec 03 11:17:08 2007
 FILE NAME = c:\p\projects\2007\17\17.dwg
 PLOT SCALE = 50.0000 / IN.
 REFERENCE = REF