CONTRACT NO. 64D51

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129M&TS	WINNEBAGO	110	51
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

Summary of Quantities for IL 173 @ Belevidere Rd

PAY CODE	ITEM	UNIT	TOTAL
#2001386	CELLULAR MODEM	EACH	1
72000100	SIGN PANEL TYPE I	SQ FT	12
72000200	SIGN PANEL TYPE II	SQ FT	18
80501000	SERVICE INSTALLATION (SPECIAL)	EACH	1
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	5
81400710	HEAVY-DUTY HANDHOLE PORTLAND CEMENT CONCRETE	EACH	2
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP TYPE USE) 1/C NO. 10	FOOT	1966
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4
82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	1892
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	2640
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3C	FOOT	55
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 14 FT.	EACH	4
87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT	EACH	4
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3
87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER (4@19.5')	FOOT	78
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	8
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	5
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4
88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	12
X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	585
X0324887	CONDUIT INSTALLED, 2 1/2" DIA., NON-METALLIC	FOOT	208
X0324888	CONDUIT INSTALLED, 4" DIA., NON-METALLIC	FOOT	439
X0325335	CONDUIT INSTALLED, 1 1/2" DIA., NON-METALLIC	FOOT	47
XX003163	EMERGENCY VEHICLE PRIORITY SYSTEM	EACH	1
XX003165	VIDEO CAMERA DETECTOR SYSTEM	EACH	1
XX006661	UNINTERRUPTIBLE POWER SUPPLY, STANDARD	EACH	1

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAP ROUTE 303 (IL 173)

SECTION 129M&TS

WINNEBAGO COUNTY

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = Mon Dec 03 09:46:05 2007
FILE NAME = s:\projects\c287\97\d97\d97signlins.dgn
PLOT SCALE = 20.0000 / IN.
USER NAME = polzinmj

TABULATION OF SIGNAL QUANTITIES