

SUMMARY OF QUANTITIES

50% Iowa / 50% Illinois
Maintenance
100% Rural SFTY-2A

paycode	description	units	total quantity
20400800	FURNISHED EXCAVATION	CU YD	55
28100127	STONE RIPRAP, CLASS B4	SQ YD	395
28200200	FILTER FABRIC	SQ YD	395
50300300	PROTECTIVE COAT	SQ YD	212
50102400	CONCRETE REMOVAL	CU YD	66.7
50104710	REMOVAL OF EXISTING BEARINGS	EACH	76
50157300	PROTECTIVE SHIELD	SQ YD	233
50300255	CONCRETE SUPERSTRUCTURE	CU YD	66.7
50501005	JACK AND REPOSITION BEARINGS	EACH	1
50501105	OPEN STEEL FLOOR	SQ FT	16,619
50600300	CLEANING AND PAINTING STEEL BRIDGE	L SUM	1
50606400	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES	L SUM	1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	9,980
52000110	PREFORMED JOINT STRIP SEAL	FOOT	396
52100520	ANCHOR BOLTS, 1"	EACH	1
58700300	CONCRETE SEALER	SQ FT	1,539
59000200	EPOXY CRACK INJECTION	FOOT	211
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9
67100100	MOBILIZATION	L SUM	1
X0325925	REPAIR OF EXISTING OPEN STEEL FLOOR WELDS	EACH	18
X0325926	FURNISHING AND INSTALLING FABRIC BEARINGS	EACH	76
X0325927	REMOVE AND REPLACE NONSHRINK GROUT BEARING PEDESTALS	EACH	12
X0325748	ACRYLIC COATING	SQ YD	221
X0325928	FIBER REINFORCED PROTECTION	SQ FT	1,989
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100900	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316(SPECIAL)	EACH	4
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,500
70300500	PAVEMENT MARKING TAPE, TYPE III	FOOT	14,500
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6,000
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	5,900
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1100
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	266
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	60
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1
Z0031200	JACKING AND CRIBBING	EACH	4
Z0032300	JACKING EXISTING SUPERSTRUCTURE	L SUM	1
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1

* SPECIALTY ITEM